Report of

Hydrogeological Investigation

Foto-Hut Site #91-1101

Route 4
Rutland, Vermont

December 1993

Prepared for:

Chittenden Bank NA
Two Burlington Square, P.O. Box 820
Burlington, Vermont 05402

Prepared by:

THE JOHNSON COMPANY, INC.
5 State Street
Montpelier, Vermont 05602
(802) 229-4600

THE JOHNSON COMPANY, INC.
Environmental Sciences and Engineering

December 6, 1993

Mr. Charles Schwer, Supervisor
Sites Management Section
Hazardous Materials Management Division
103 S. Main Street/West Office
Waterbury, Vermont 05671-0404

Re: Report of Hydrogeological Investigation for Foto-Hut Site,
Rutland, Vermont (Site #91-1011)
JCO #1-0342-2

Dear Chuck:

Enclosed please find the report for the Site referenced above. We have included an analysis of the likely contaminant sources. Pursuant to Sections 1922(10) and 1926 of the Vermont Underground Storage Tank Regulations it is our opinion that the costs of this investigation and the costs of the tank removal and associated contaminated soil and sludge disposal are eligible for reimbursement through the Petroleum Cleanup Fund (PCF).

The report includes recommendations for additional work. This additional work will commence with the preparation of a work plan for remedial investigations and remedial design. The work plan will also include a cost estimate for the investigations and design. The cost of generating the work plan is estimated to be $1,500. It is our opinion that these and other remedial costs are eligible for reimbursement through the PCF. Attached is the remedial investigation and design work plan for your review and approval.

We would appreciate your prompt review of these documents, and a written response as to the acceptability of the proposed work plan. If you have any questions or comments, please do not hesitate to call me or Martin Johnson at 229-4600.

Sincerely,

THE JOHNSON COMPANY, INC.

By: _____
Donald M. Maynard, CG
Project Geologist

cc: Chris Bishop

Civil/Environmental Engineering Hydrogeology Water Supply & Wastewater Disposal Hazardous Waste Remediation Hydrology Contaminant Fate Analysis
Soil & Water Science Geology & Geophysics Rivers and Dams Solid Waste Permitting
5 State Street Montpelier, VT 05602 ■ (802) 229-4600 Fax: (802) 229-5876

TABLE OF CONTENTS

LIST OF FIGURES

LIST OF TABLES

LIST OF APPENDICES

LIST OF ATTACHMENTS

1.0 INTRODUCTION

An extensive hydrogeological investigation has been completed at the Foto-Hut Site on Woodstock Avenue in Rutland, Vermont (the Site, see Figure 1, Site Location Map). This investigation was prepared in response to a request by Mr. Chris Bishop of the Chittenden Bank. The work performed during this investigation was detailed in a September 22, 1993 work plan presented to the Vermont Hazardous Materials Managements Division, Sites Management Section (HMMD). The work plan was approved by Mr. Charles Schwer, supervisor of the HMMD. The primary objectives of the work included:

1) Characterization of the extent, chemical nature, and concentration of contamination in the soils and upper surficial aquifer at the Site.
2) Determination of the sources, and migration pathways of the contamination.
3) Identification or confirmation of existing and potential receptors of the contamination.
4) Development of a conceptual design for a term monitoring and/or remedial plan.
5) Determination of what percentage of costs are eligible for reimbursement by the Vermont petroleum cleanup fund (PCF).

2.0 HISTORICAL PERSPECTIVE

The information presented in this section was collected during a background investigation conducted in the fall of 1993. The background investigation included a records search for any data regarding the history and operation of the Site and vicinity, including the following:

- Results of the following investigations and assessments available in the HMMD files:
  - ------- 1989 underground storage tank (UST) removal assessment for Bob's Texaco in Rutland, Vt. Vermont Hazardous Release Site #89-0377
  - ------- March 4, 1991 report of investigation at the Foto-Hut Site performed by The Johnson Company, Inc.
  - ------- April 1992 report of UST removal at the Foto-Hut Site prepared by The Johnson Company, Inc.
  - ------- August 1993 Remedial Investigation Report, H. A. Eddy Convenience Store in Rutland, Vt. prepared by The Johnson Company, Inc.
- December 16, 1992 and July 12, 1993 Preliminary Assessments of the Foto-Hut Site performed by the Vermont HMMD.



Figure 1 - Site Location Map

THE JOHNSON COMPANY, INC.
Environmental Sciences and Engineering
MONTPELIER, VERMONT

- Records of title searches (See Appendix A).
- Municipal or utility information on subsurface pipes or conduits.
- Water supply well logs and public water supply records.
- Existing geological maps available in the State Geologist's office.
- Soil Conservation Service soils maps.
- United States Geological Service (USGS) topographic maps.
- Vermont Mapping Program orthophotos.
- Town and City records.
- Department of Transportation and Public Works records.
- 1925 and 1971 Sanborn Insurance maps.

The Site is located near the terminal moraine system of the Burlington glacial stade. The Burlington stade was the last large scale advance of continental glacial ice during the Wisconsin Glaciation (about 12,000 years before present). Prior to the Burlington stade, Vermont was covered with ice greater than one mile thick at the Site. Sediments were deposited in the vicinity of the site by the glacier, and by associated lakes, rivers, and outwash fans. These sediments include: Dense silty basal tills; fine grained silt and clay lacustrine deposits; sandy fluvial deposits; coarse grained poorly sorted outwash deposits; and sandy ablation tills. Soils near the Site mapped by the Soils Conservation Service (in Appendix C) include: Georgia Stony Loam; Raynham Silt Loam; and Paxton Silt Loam. The Paxton Series Soils are directly below the Site. All three of these soils are characteristically low permeability sediments.

There are three buildings currently on the Site. One building (77 Woodstock Ave.) is over 85 years old, and is located in the southwest corner of the site (see Attachment 1, Groundwater Contour Map). The front half of this building has been used by Foto-Hut since 1987. The back half of the Foto-Hut building is vacant. The Foto-Hut building has a concrete slab floor, and five foot deep frost walls. The second existing building on the Site (87 Woodstock Ave.) is located on the southeast corner of the site (not shown on Groundwater Contour Map). This 16 year old building houses the Chittenden Bank. The third building is the Chittenden Bank drive-though service structure. Prior to 1925 until sometime after 1971, there was a fourth building located near the northwestern corner of the site. This building was a three car garage. Currently, most of the site is covered by buildings or asphalt. The Foto-Hut Site was used primarily as a laundry and dry-cleaning operation since prior to 1909 until 1970. The laundry was

called Rutland Cleaners and Dyers. Between 1970 and 1977, the Site was vacant. Other businesses have occupied the Foto-Hut building at one time or another, including: The Stitchery; Brownsville Girl Shoe Repair; Accent Realty; Grace A. Land Office; and Vermont Cycle.

Prior to 1925 until sometime before 1971, the southeast corner of the Site was used as a gasoline service station. This station was beneath the present location of the Chittenden Bank. The underground storage tanks were removed during construction of the bank.

The property immediately to the west of the Site (75 Woodstock Avenue) is owned by John Smart Antiques, and is currently being used as an antique store. This structure was built before 1925, and has a cellar in the southeast corner. The Smart building was used as an autobody and lacquer spraying shop (Brigg's Autobody) from before 1925 to 1987.

Across the Street from the Site at 84 Woodstock Avenue is a dry-cleaning and laundry service, Filippo Drycleaners. 84 Woodstock Avenue has been used as a laundry since before 1951. The parcel was also used as a gasoline service station between 1936 and 1951. At least one UST is suspected on the Filippo Cleaners property based on typical dry-cleaning operational practices.

Also across the street from the Site, at 86 Woodstock Avenue, is the H. A. Eddy filling station and convenience store. This property has been used as a filling station since 1982. The property was used as a restaurant prior to 1982. The Eddy property is currently listed as Vermont Hazardous Materials Release Site #93-1413. A subsurface investigation of the Eddy Site revealed extensive groundwater contamination. The contamination included benzene, toluene, ethylbenzene, xylenes (BTEX), and methyl-tert-butyl-ether (MTBE). 1,2-dichloroethylene (1,2-DCE) and perchloroethylene (PCE) have also been detected next to the Filippo Drycleaners at low concentrations in a groundwater monitoring well. The Remedial Investigation Report for the Eddy Site concludes that the source(s) of the contamination are off-site. The implication is that the contamination has migrated by preferential flow in utility trenches and conduits below Woodstock Avenue.

There are eight identified underground storage tanks (USTs) within 1,000 feet of the Foto-Hut Site. Five of these are on the Eddy Site, and are used for storage of kerosine, gasoline, and diesel. Three USTs are located at Bob's Texaco Station (93 Woodstock Avenue), about 300 feet west of the Foto-Hut building. The tanks at the Texaco station are replacements for four tanks removed in 1989. During the removal and replacement work, 120-150 cubic yards of petroleum contaminated soils were excavated from

93 Woodstock Avenue. The Texaco Site has been used as a Texaco Station since 1947.

In 1977 the Chittenden Bank purchased the Foto-Hut Site. In 1990 an inspection of the structure was performed by contractors hired by potential buyers of the property. During the inspection unpleasant odors were reported by the contractors. Samples of soils and the contents of pipes in the building were collected and analyzed in August 1990 by Scitest Laboratories of Randolph, Vermont. The samples contained toluene, ethylbenzene, xylenes, and perchlorethylene (TEX and PCE). The concrete floor of the unused portion of the building was partially demolished during sampling. An investigation of the piping was performed by The Johnson Company, Inc. in November 1990. The investigation confirmed the presence of PCE and TEX contamination in the soils west of and below the building. Numerous pipes outside the western wall of the building were traced and removed during the investigation. An abandoned UST (Tank #1, See Attachment 1) containing TEX and PCE contaminated fill was discovered during the investigation. The HMMD determined that contamination attributable to the UST was eligible for reimbursement by the Vermont Petroleum Cleanup Fund (PCF). Additional soil samples were collected by The Johnson Company on January 15, 1992. Between March 5 and 12, 1992 the UST was removed. During removal, two additional USTs (Tanks #2 & #3) full of TEX and PCE were discovered and removed. Contaminated soils, pipes, and sludge were transported off-site.

In December 1992, a preliminary assessment (PA) of the Site was prepared by the HMMD and submitted to the Environmental Protection Agency (EPA). On July 12, 1993 a second PA was prepared by the HMMD and submitted to the EPA. The July 12, 1993 PA was inaccurate in regards to the number of water supply wells within 0.25 and 0.5 miles of the Site. Two wells have been incorrectly mapped on Harrington Avenue, and the Site location is incorrect (See Attachment F). The locations of these wells were presumably based on unconfirmed well completion files maintained by the Vermont Water Supply Division. Telephone interviews with the well driller, Ottauquechee Drilling of West Bridgewater, Vermont, indicate that the wells were actually installed on Gleason Road, over one mile west of the Site. Therefore, there are no water supply wells identified within one half mile of the Site.

A telephone interview was conducted on November 23, 1993 with Ken Faig, Technical Support person for the International Fabric Care Institute. Mr. Faig provided information on typical machinery and historical operating practices based on descriptions of the tanks, piping, belt drive axle, and other appurtenances on the Site.

Mr. Faig mentioned that petroleum solvents were used exclusively for dry cleaning before 1933. The original use of the tanks was therefore petroleum solvents, since they are hooked to piping which was installed below the concrete floor, which was described on the 1925 Sanborn Maps. After 1933, both PCE and carbon-tetrachloride were typically used in dry cleaning, but petroleum is still being used by many operations today. Mr. Faig thought it very unlikely that PCE was deliberately mixed with the petroleum. He believes that the PCE was hand applied to spots, before the garment was dry cleaned. The PCE would then be extracted from the garment during the cleaning, and end up as contamination in the petroleum tanks. Storage of the PCE would typically be in drums or smaller containers within the building on the concrete floor.

The belt driven petroleum operations typically had four pieces of machinery: A washer, where the petroleum was mixed with the clothes; a centrifugal extractor, where the petroleum was removed from the clothes and sent to a "dirty" tank (note that the extractor needed to be bolted down and that 3/4" bolts were found in the building floor); and a tumbler, where the remainder of the petroleum was removed from the clothes by volatilization (the VOCs were vented to the outside air). The fourth piece of machinery was the vacuum still. The vacuum still was used to recycle the petroleum. Dirty petroleum (containing trace amounts of PCE) from the washers and extractors was piped to the dirty tank. A vacuum was then placed on the entire system, and steam was used to volatilize the petroleum. The volatilized petroleum was collected and returned to a "clean" tank, to be reused in the washer. Note that any leak in the vacuum rendered this system inoperative. The third pipe found in each UST was for drawing the vacuum. Mr. Faig could not think of any other use of a three pipe system other than vacuum still recovery for a petroleum based system. All the piping had to be maintained in a non-leaking condition. The vacuum still also contained a rag separator (water separators had not been invented). The rag separator was filled with rags which collected water and solids from the still. The rags were replaced daily, and were probably washed, dried, and returned to use.

It should be noted that all wiring, machinery etc. needed to be explosion proof inside the building, and therefore, the dry cleaning operation was probably limited to the back room. The steam was probably originally generated using a coal fired furnace, but this may have been upgraded to fuel oil later on. No fuel oil USTs have been discovered at the Site.

3.0 METHODOLOGY AND ACCOMPLISHMENTS OF THE INVESTIGATION

This section describes specific tasks which were performed during the investigation. It also includes detailed descriptions of the methods used, and presents the data collected.

A background investigation was performed which included research of the sources described above in Section 2.0. The results of this investigation are presented in appropriate sections throughout this report. Dig-Safe was contacted prior to initiating any intrusive work on the Site. The existing site-specific health and safety plan (HASP) from the March 1992 UST removal was revised. The HASP complies with the requirements of OSHA regulations 29CFR 1910.120.

The Johnson Company uses Standard Operating Procedures including specific steps for many types of data collection. These procedures have been developed over many years based upon field experience with the instruments and techniques. All field work was performed in accordance with the appropriate standard operating procedure.

3.1 SITE INVESTIGATION

During the Site investigation, potential receptors of atmospheric contamination were identified and evaluated. Currently, the unused portion of the Foto-Hut building is the only identified receptor of atmospheric contamination from the Foto-Hut Site. Volatile organic compound vapor concentrations between 0.2 and 0.4 parts per million (ppm) were measured in the breathing zone with a photoionization detector (PID) in the building on October 7 and 11, and on November 5, 1993. The likely source of these vapors is the contaminated soils exposed by partial demolition of the concrete floor. Given the chemicals present in the soils and groundwater, and the vacancy of the affected portion of the building, these concentrations do not pose an unacceptable risk to human health. Potential receptors of atmospheric contamination include construction workers if the building or asphalt east of the building are excavated. Breathing zone vapor concentrations up to 3 ppm were measured with the PID during drilling east of the building. These concentrations are below the permissible exposure limits for the compounds detected in soil and water samples.

The Site was screened using a metal detector to identify any previously unidentified USTs. Three areas were identified which had positive responses for underground metal objects. In each case, the apparent size of the object was four to six feet in diameter. Two areas with positive responses were in the parking lot behind the Foto-Hut building, and the third was between the Foto-Hut building and the neighboring antique store (See Attachment #1). This third location coincides with the capped termination

of three pipes removed in 1991.

A total of eight soil borings were drilled, and seven monitoring wells were installed on the Site. The boring locations are displayed on Attachment #1 as MW-1 through MW-8 and PZ-1. One piezometer was installed as well. Soil samples were collected continuously during drilling and screened in the field with a PID using the headspace method. Soil samples were collected from the auger blades during drilling to three feet below ground surface (bgs). With the exception of MW-8 and PZ-1, soil samples were collected by split spoon from three feet bgs to the total hole depth. Split spoon samples were collected with a 24" long spoon driven by a 140 pound hammer with a drop of 30 inches. MW-8 and PZ-1 soil samples were collected from the auger flights and by hand auger. A monitoring well was not installed in the MW-6 borehole due to refusal above the apparent water table. Each of the seven wells is between 15 and 20 feet deep. A shallow piezometer, PZ-1, was installed to six feet below ground surface next to MW-1. Deep wells beyond 20 feet bgs were not drilled due to high PID measurements of the soil samples collected during drilling. It was decided in the field that there was a high danger of penetrating a confining layer, and potentially spreading the contamination to an underlying aquifer. A geologic log of each well and boring is provided in Appendix B.

Contaminated soil from drilling with PID headspace measurements above 150 ppm were drummed and temporarily stored on-site. Soil from drilling with PID headspace measurements below 150 ppm was buried on-site near observation well OB-2 which was installed during the UST removal discussed in Section 2.0 (see Attachment #1). Waste water from drilling and well development was discharged to the ground on-site.

All the monitoring wells are constructed of PVC with 5 foot long factory-slotted screens, except the upgradient well MW-4, which has a 10 foot long screen. All the wells are constructed with a locking cap and flush mounted well guard, except MW-8, which is located inside the Foto-Hut building. The annulus of each well was sealed with hydrated bentonite from the top of the sand pack to two feet or less below ground surface. Monitoring wells MW-5 and MW-7 are screened in the upper portion of the surficial aquifer, so that the groundwater level measured on November 8, 1993 intersected the screen. Each well was developed by bailing until dry, or until five well volumes were removed. With the exception of MW-8 and PZ-1, the wells were installed by Tristate Drilling and Boring of Lyndonville, Vermont using an eight inch diameter hollow stem auger. MW-8 and PZ-1 were installed by The Johnson Company using a four inch diameter solid stem auger.

The well locations and elevations were surveyed by The Johnson Company using an autolevel, compass, and tape. The elevations are correlated to an approximate USGS national geodetic vertical datum (NGVD). A site map was prepared on our computer AUTOCAD system which includes a contour map of relative water elevations, site buildings and relevant features, and potential contamination sources and receptors (Attachment #1). Delineations of the contamination plumes are portrayed on Attachments #2, #3, #4, #5, and #6.

3.2 SAMPLING AND CHEMICAL ANALYSIS

3.2.1 Soils

Seven soil samples were collected for volatile organic compound (VOC) analysis by EPA Methods 8010 and 8020. The samples collected for laboratory analysis were those with the highest PID headspace measurements in each boring. A soil sample for laboratory analysis was not collected from MW-2 during this investigation. Numerous soil and tank sludge samples were collected at the Site during previous investigations as well. The soils analytical results are including in Appendix D, and are summarized below in Table 1.

Soils are relatively uniform where undisturbed. The native soil encountered during drilling is primarily a fine sand with 20-30% silt and subangular gravel. This soil has been interpreted to be a native ablation till deposit. A soil with similar grain size characteristics, but containing bricks and debris typically overlies the native material. A clean sand horizon was encountered at depth in well MW-4, and below Tanks #1, #2, and #3. The lateral and vertical extent of this layer has not been determined.

TABLE 1 - ANALYTICAL RESULTS OF SOIL ANALYSIS IN REVERSE CHRONOLOGICAL ORDER

Sample Name	Sample Date	Depth/ Elevation (ft bgs/ FNGVD)	Soil Type/ PID (ppm)	EPA Analytical Method	Toluene (ppb)	Ethyl benzene (ppb)	Total Xylene (ppb)	Other Detected Compounds (ppb)
MW-1	9-30-93	11.5-13.5/ 678.4-676.4	fs,ss,lg /20	8010/8020	<1	<1	2	DL<1
MW-3	9-30-93	6-8/ 683.6-681.6	fs,ss,sg /115	8010/8020	<2	18	29	DL<2
MW-4	10-1-93	14.5-16.5/ 675.4-673.4	fs,lg /7.7	8010/8020	<1.1	<1.1	1	DL<1.1
MW-5	10-1-93	8-9/ 680.6-679.6	fs,as /155	8010/8020	67	560	3,200	DL<56
MW-6	10-1-93	3-5/ 685.5-683.5	fs,ss /250	8010/8020	<66	930	7,200	DL<66
MW-7	10-1-93	7-9/ 681.5-679.5	fs,as, lg /0.6	8010/8020	<1	<1	<1	DL<1
MW-8	10/11/93	5/683.4	ss/250	8010/8020	270	3,800	39,000	DL<270
X1 Tank 1 Contents	3-17-92	10.3-13.8/ 680.7-677.2	fs	8270 8100 8240 8080 8150	ND <500	<500	3,824 m 1,734 o,p 2,090	343 Chrysene 335 Pyrene 1,064 2-Methylnaphthalene 3,321 Naphthalene 335 Phenanthrene 230 ppm TPH <500 Perchlorethylene DL<100 Pest&PCB DL<100 Herbicides
X4 Tank 2&3 Contents	3-17-92	8.6-12/ 682.4-679	sludge	8240	ND <1.26 ppm	ND <1.26 ppm	<1.26 ppm	DL<1.26 ppm
X2	3-17-92	5.8-13/ 685.2-678	fs,ls /101	8240 8080	ND<500	7,831	91,878 m 39,365 o,p 52,513	DL<100 Pest&PCB
Soil #1 Tank #1	3-5-92	3-5/688-686	fs, ss /33	8240	3,490	8,780	58,500 m 23,000 o,p 35,500	6,820 Perchlorethylene DL<1,500

TABLE 1 - ANALYTICAL RESULTS OF SOIL ANALYSIS IN REVERSE CHRONOLOGICAL ORDER

Sample Name	Sample Date	Depth/ Elevation (ft bgs/ FNGVD)	Soil Type/ PID (ppm)	EPA Analytical Method	Toluene (ppb)	Ethyl benzene (ppb)	Total Xylene (ppb)	Other Detected Compounds (ppb)
Soil #1 Duplicate	3-5-92	3-5/688-686	fs, ss /33	8240	4,160	8,840	58,900 m 26,800 o,p 32,100	7,720 Perchlorethylene DL<1,500
Soil #2 Tank #1	3-6-93	7/684	fs, ss	8240	<1,500	1,569	7,660 m 3,360 o,p 4,300	DL<1,500
Soil #3 Tank#1	3-6-93	9/682	fs, ls	8240	<1,500	1,850	10,840 m 6,540 o,p 4,300	DL<1,500
S 1	1-15-92	0-1/ 688.0-687.0	200	8240 418.1	48	<40	<40	423 Perchlorethylene DL<20 1,000 ppm TPH as Oil & Grease
S 1	1-15-92	2-3/ 686.0-685.0	260	8240 418.1	1,500	5,160	52,600 m 24,700 o,p 27,900	3,550 Perchlorethylene DL<1,000 13,000 ppm TPH
S 2	1-15-92	0-1/ 688.0-687.0	250	8240 418.1	<1,000	<1,000	<2,000	DL<1,000 860 ppm TPH
S 2	1-15-92	1.1-2.2/ 686.9-685.8	285	8240 418.1	<1,000	<1,000	<2,000	DL<1,000 580 ppm TPH
S 3	1-15-92	0-0.92/ 688.0-687.1	210	8240 418.1	<1,000	<1,000	<2,000	DL<1,000 1,500 ppm TPH
S 3	1-15-92	0.92-1/ 687.1-687.0	75	8240 418.1	<1,000	<1,000	<2,000	DL<1,000 <30 ppm TPH
Near Hole (NH)	11-29-90	≈5-6/ 686-685		8010/ 8020	2,120	3,850	15,700	420,000 Total Aromatics as Xylene DL<525
B 1	11-29-90	0.58-0.92/ 687.4-687.1		8010/ 8020	4	<2.5	80	1,518 Total Aromatics DL<2.5
B 2	11-29-90	0 -0.33/ 688.0-687.7		8010/ 8020	5	<1.9	26	296 Total Aromatics DL<1.9

TABLE 1 - ANALYTICAL RESULTS OF SOIL ANALYSIS IN REVERSE CHRONOLOGICAL ORDER

Sample Name	Sample Date	Depth/ Elevation (ft bgs/ FNGVD)	Soil Type/ PID (ppm)	EPA Analytical Method	Toluene (ppb)	Ethyl benzene (ppb)	Total Xylene (ppb)	Other Detected Compounds (ppb)
B 3	11-29-90	0 -0.33/ 688.0-687.7		8010/ 8020	112	<1.8	110	3,335 Total Aromatics DL<1.8
B 4	11-29-90	0 -0.33/ 688.0-687.7		8010/ 8020	<3.1	<3.1	<3.1	<31 Total Aromatics DL<3.1
B 5	11-29-90	0 -0.33/ 688.0-687.7		8010/ 8020	10	11	61	436 Total Aromatics DL<2.1
B 5	11-29-90	2.33-2.67/ 685.7-685.3		8010/ 8020	2,073	1,590	2,410	115,000 Total Aromatics DL<691
B 6	11-29-90	0 -0.33/ 688.0-687.7		8010/ 8020	<2.7	<2.7	<2.7	<27 Total Aromatics DL<2.7
B 7	11-29-90	0 -0.33/ 688.0-687.7		8010/ 8020	12,300	1,400	31,900	351,000 Total Aromatics DL<139
B 7	11-29-90	1.67-2.0/ 686.3-686.0		8010/ 8020	3,170	2,500	54,100	359,000 Total Aromatics DL<265
B 8	11-29-90	0 -0.33/ 688.0-687.7		8010/ 8020	211	<178	<178	3,140 Total Aromatics DL<178
B 8	11-29-90	0.58-0.83/ 687.4-687.2		8010/ 8020	<2	<2	<2	<20 Total Aromatics DL<2
O 1	11-29-90	≈3/688		8010/ 8020	32,700	69,500	189,000	4,030,000 Total Aromatics 4,350 1,2 Dichlorethylene 742 Benzene DL<219
O 2	11-29-90	0.5/690.5		8010/ 8020	1,408	<179	1,530	36,300 Total Aromatics DL<179
O 3	11-29-90	≈2/689		8010/ 8020	16,800	56,300	199,000	4,790,000 Total Aromatics DL<1,400
O 4	11-29-90	2/689		8010/ 8020	<2.6	<2.6	<2.6	<26 Total Aromatics DL<2.6
O 5	11-29-90	≈2.5/688.5		8010/ 8020	<2.7	<2.7	<2.7	<27 Total Aromatics DL<2.7

TABLE 1 - ANALYTICAL RESULTS OF SOIL ANALYSIS IN REVERSE CHRONOLOGICAL ORDER

Sample Name	Sample Date	Depth/ Elevation (ft bgs/ FNGVD)	Soil Type/ PID (ppm)	EPA Analytical Method	Toluene (ppb)	Ethyl benzene (ppb)	Total Xylene (ppb)	Other Detected Compounds (ppb)
O 6	11-29-90	≈4/687		8010/ 8020	3	<2.4	10	192 Total Aromatics DL<2.4
Soil F	8-15-90			8010/ 8020	Inter-ference	Inter-ference	Inter-ference	>143 ppm Total Aromatics 238 Perchlorethylene DL<5
Soil C	8-15-90			8010/ 8020	<3	<3	<3	DL<3

Key: fs = fine sand, ss = some silt, lg = little gravel, as = and silt, ls = little silt, DL = detection limit for PCE.
TPH = total petroleum hydrocarbons as oil and grease.

3.2.2 *Water*

One round of water samples was collected from all of the monitoring wells, including one existing observation well (OB-1) installed during the UST removal. The samples were analyzed using EPA Methods 601 and 602, or 8240 for VOCs. Groundwater samples were collected by a qualified Johnson Company Site Technician and analyzed at Industrial and Environmental Analysts (IEA) in North Billerica, Massachusetts. All sampling was performed in accordance with EPA's "RCRA Groundwater Monitoring Technical Enforcement Guidance Document". Sample collection included preparation of a trip blank, a field blank, and a duplicate of the MW-3 sample. These three samples were used for quality control and quality assurance (QA/QC) purposes. Due to refusal above groundwater, no sample is available for MW-6. Water samples and product samples have been collected from the Site in the past. The analytical results are included in Appendix D, and a summary is provided in Table 2 below.

The enforcement standards for 1,2 DCE and xylenes were exceeded in the groundwater based on the analytical results of sample from wells MW-8 and OB-1. No groundwater contamination was detected in any other well except 5 ppb of 1,1,1-Trichloroethane (TCA) in well MW-4. This concentration is at the method detection limit, and is the only documented occurrence of TCA on the Site.

TABLE 2 - ANALYTICAL RESULTS OF GROUNDWATER AND PRODUCT SAMPLES AND WATER ELEVATIONS IN REVERSE CHRONOLOGICAL ORDER

Well Name	Sample Date	Water Level (feet below top of casing)	Method	Toluene (ppb)	Ethyl benzene (ppb)	Total Xylene (ppb)	Other Detected Compounds (ppb)
MW-1	10-12-93	4.86	601/602	<1	<1	<1	DL<1
MW-2	10-12-93	3.84	601/602	<1	<1	<1	DL<1
MW-3	10-12-93	4.97	601/602	<1	<1	<1	DL<1
MW-3 Dup.	10-12-93	4.97	601/602	<1	<1	<1	DL<1
MW-4	10-12-93	4.39	8240	<5	<5	<5	5 1,1,1-Trichloroethane DL<5
MW-5	10-12-93	4.98	8240	<10	<10	<10	DL<10
MW-7	10-12-93	4.84	601/602 8240	<1 <5	<1 <5	<1 <5	DL<1 DL<5
MW-8	10-12-93	5.47	8240	<100	<100 (Est.80)	620	430 1,2 Dichloroethene DL<100
OB-1	10-12-93	6.78	601/602	8	60	560	61 cis-1,2-Dichloroethene DL<5
OB-1	9-21-92		601/602	59	144	1,240	268 cis-1,2-Dichloroethylene
Tank #2 Contents	3-6-92		8240	643ppm	985ppm	5,100ppm m 2,290ppm o,p 2,810ppm	1,030 ppm Perchlorethylene DL<1,250
Tank #3 Contents	3-6-92		8240	570ppm	908ppm	4,810ppm m 2,280ppm o,p 2,530ppm	848 ppm Perchlorethylene DL<1,250
Tank #1 Contents	11-29-90		601/602	384	241	5,900	DL<10
Tank #1 Excavation	1-15-92	≈4.5	8240	<150	<150	1,256 m 686 o,p 570	DL<150
Pipe H	8-15-90		8010/8020	Inter-ference	Inter-ference	Inter-ference	137 ppm Perchloroethylene
Pipe I	8-15-90		8010/8020	Inter-ference	Inter-ference	Inter-ference	<50 ppm Perchloroethylene

Key: DL indicates the practical method detection limit for PCE after dilution of the sample.

Subsurface mobility characteristics of the five major contaminant constituents have been evaluated. The non-aqueous phase liquid (NAPL) mobility is controlled by a number of factors including: sorption to organic carbon, dispersion, viscosity, porosity, biodegradation, groundwater velocity, solubility, and volatilization. Presented in Table 3 below are relative comparisons of mobility factors between benzene, toluene, ethylbenzene, xylenes, perchlorethylene, and 1,2-dichloroethylene.

Typical biodegradation of PCE occurs in a six step process. PCE degrades slowly to Trichloroethylene (TCE), which quickly degrades to cis-1,2-Dichloroethene (cis-1,2-DCE), which degrades to trans-1,2-Dichloroethene (trans-1,2-DCE), which degrades to 1,1-Dichlorethylene (1,1-DCE), which degrades to vinyl chloride. PCE was detected in the product samples from tanks 2 & 3, as well as in the soils from tank #1, and in soils and pipes inside the building. However, TCE and 1,2-DCE were not detected in these samples. TCE has not been detected on-site. Cis and Trans-1,2-DCE have been detected in soils and groundwater downgradient of the tanks (Out-1, OB-1 and MW-8).

The non-detection of VOCs reported in the analytical results of the MW-5 water sample are not as expected. The analytical and PID measurements of the soils at the bottom of the boring showed significant VOC contamination (3,200 ppb xylenes, 560 ppb ethylbenzene, 67 ppb toluene, and 155 ppm PID soils headspace). A PID headspace measurement of the well on November 5, 1993 showed 35 ppm VOCs in the well annulus. The water quality results were double checked by IEA upon the request of The Johnson Company.

One explanation for the absence of any detectable VOCs in the sample is that water from the overlying gravel layer flowed into MW-5 after purging. However, if this were the case, one would expect the water level in MW-5 to be somewhere within the gravel layer. The water level in MW-5 has been continuously observed to be about two feet below the base of the gravel, and has been bailed dry on two occasions. A second hypothetical explanation is a preferential pathway, possibly a coarse grained lens, which is supplying water to MW-5. This water presumably would not have sufficient contact time with contaminated soils to dissolve the contaminants. If this were the case, we would have seen the lens during the continuous split spoon sampling. In addition, this would imply that the contaminant transport leading to the contaminated soils was not through groundwater. A third possibility is that recharge to the well is from a lower aquifer through the bottom of the sand-pack. This recharge would occur preferentially through a thin aquitard below the bottom of the well after purging, rather than from the contaminated soils around the well annulus. This hypothesis is supported by the observed presence of a lower sandy

aquifer in monitoring well MW-4. The recharge would presumably be fast enough that the relatively insoluble compounds such as xylenes would not be dissolved into the recharging groundwater.

We cannot discount the existence of perchlorethylene DNAPL pools. However, observations of the free product in tanks #2 & #3, and free product removed from MW-6 soil samples, did not show a sinking portion. Preferential enrichment of unsaturated soils below the building by PCE can be expected due to volatility differences in the compounds. Stripping of toluene by dissolution into groundwater can be expected to cause relative depletion of toluene in saturated soils. Continuous bleeding of 1,2-DCE into the aquifer from PCE contaminated soils is expected.

TABLE 3 - RELATIVE MOBILITY OF VARIOUS COMPOUNDS

Compound	Molecular Weight	Specific Gravity (@ 20°C)	Viscosity (cp @55°F)	Solubility of pure product in Water (mg/l @20°C)	Sorption (log KOW/KOC)	Volatility Henry's Law Constant (atm-m^3/mole)	Bio-degradation Potential	Relative Mobility of NAPL	Relative Mobility by Vapor Phase	Relative Mobility by Dissolved Phase
Benzene	78.11	0.8786	0.724	1780 Most soluble	2.12/1.69 Low Sorption	0.00555	Slow	Mobile	Mobile	Highly Mobile
Ethylbenzene	106.17	0.867	0.746	152	3.15/--- High sorption	0.00644	Rapid	Second Least Mobile	Second Least Mobile	Second Least Mobile
Toluene	92.1	0.867	0.649	515	2.56/2.06	0.00664	Rapid	Mobile	Mobile	Mobile
Xylenes ortho meta para	106.17 106.16 106.17	0.88 0.864 0.86	0.682	175 --- ---	2.95/2.11 --- --- High sorption	0.00527 0.00255 0.00251 Least Volatile	Rapid	Mobile	Least Mobile	Mobile
Perchlorethylene	165.8	1.626 Most Dense	0.958 Most Viscous	150 Least Soluble	2.6/2.42	0.0287 Most Volatile	Slow	Least Mobile	Highly Mobile	Least Mobile
1,2-Dichloroethene	96.95	1.26-1.28 Dense	0.40 @20°C Least Viscous	700-800 Second Most soluble	--/0.70-0.48 Least sorption	0.00532-0.0066	Slow	Highly Mobile	Mobile	Highly Mobile

Log KOW/KOC from Montgomery J. H. and Welkom L. M. 1990; "Chemical Desk Reference"
Henry's law Constant from Appendix A EPA 450/3-85-007
Biodegradation susceptibility from Howard, P. H., 1990; "Handbook of Environmental Fate and Exposure Data for Organic Chemicals"
All other data from Verschueren, Karel, 1983; "Handbook of Environmental Data on Organic Chemicals"
Key: cp = centipoise. KOW = octanol water partitioning coefficient. KOC = Carbon Absorption Isotherm Slope

3.3 WATER ELEVATIONS

Groundwater levels in the wells were measured on several occasions. Water level data is presented in Appendix E, and a contour map of adjusted water elevations is included as Attachment 1. Water level measurements were performed using a Solinst water marker. One round of measurements on October 11, 1993 was performed using an interface probe. No NAPLs were detected in any of the wells. Measurements are made in reference to the top of PVC casing in each well. The water markers were decontaminated with a soapy wash and rinse between wells.

It rained on-site on November 5, 1993. There was an increase in the water elevations in nearly all the wells between November 5 and November 8 by 0.1 to 0.2 feet. The water level in OB-1 remained level over that period, and in MW-8 the water level increased by a foot. This may have been due to a slug of rainwater infiltrating west of the Foto-Hut building, and migrating eastward under the building. If this is the case, two characteristic effects should be observable:

- Temporal changes in water quality due to changes in residence time
- Highest contaminant concentrations in groundwater after a long dry period

A downward vertical hydraulic gradient has been measured at the Site. The vertical hydraulic gradient between wells MW-1 and PZ-1 was 0.052 ft/ft downward on November 8, 1993. A similar downward gradient has been measured in a well nest located on the Eddy Property, south of the Site. All water level measurements were normalized to a 680 foot elevation prior to preparing a contour map. Calculations of the normalization procedure are included in Appendix E.

Groundwater flow in the surficial aquifer below the Site is primarily towards the south and east. The gradient and flow direction is strongly controlled by the availability of recharge from precipitation, as well as by the hydraulic conductivity of the aquifer. Low hydraulic gradients are observed beneath the asphalt parking lots due to a gravel sub-base and the absence of infiltration. A groundwater high is observed northwest of the Foto-Hut building due to recharge through the lawn from infiltration. A high hydraulic gradient is observed on the western edge of the Foto-Hut building due to "ponding" of the infiltration water behind the frost walls and to the lack of infiltration below the building. Local depressions in the groundwater table are observed near storm drains, even though the drains do not appear to intersect the groundwater table.

3.4 CONTAMINANT MIGRATION

Observed contaminant distributions in the soils and groundwater appear to correlate generally with a hypothetical logarithmic distribution. A logarithmic elliptical decrease in concentration is generally correlated with an increase in distance from the sources. The length and breadth of the ellipse is dependant on groundwater velocity and chemical specific transport characteristics.

Pipe sources have probable leakage locations at knuckles and junctions. This will generate characteristic patterns of isolated pockets of contamination. Due to relative volumes of contaminants released, contamination generated from a leaky pipe is likely to be much smaller in areal extent than that generated by the tanks.

The measured concentration of contaminants in soils samples is highly variable. Samples from the same location, but collected at different times, sometimes have different concentrations. Samples taken at different depths at the same location may give widely different contaminant concentrations. Therefore, considerable judgement was required in preparing the isopleth contour maps presented in Attachments 2 through 6. The Cross Section, Figure 2, also displays some isopleths. The section and maps are based on arbitrary judgements of the representativeness of each data point and application of the hypothetical distribution described above. For instance, the maps of toluene, xylene, and ethylbenzene soil concentrations were based on data excluding points less than one foot deep. It was determined that the shallow soil samples (less than 1 foot bgs) were typically much less contaminated than deeper samples (1-3 feet bgs) at the same location. A map based on the shallow clean samples would be inaccurate in assessing the probable extent of maximum soil contamination. Similar judgement used in other aspects of mapping are included on the appropriate maps.

Soil contamination east of the building appears to be limited to below 3 feet bgs. The upper three feet of soil is a coarse grained sub-base for the parking lot. PID headspace measurements of the coarse grained soils did not detect VOC contamination. This phenomena is probably due to the low residual saturation capacity of the gravels, and possible to passive venting of the gravels by the storm drain network and trenches.

FIGURE 2.
EXTENT OF PCE, ETHYLBENZENE, AND 1,2 DCE IN SOILS
FOTOHUT PROPERTY
RUTLAND, VERMONT



LEGEND

- ETHYLBENZENE ISOPLETH (IN PPB) IN SOILS
- EXTENT OF PCE CONTAMINATION IN SOILS
- EXTENT OF 1,2 DCE CONTAMINATION IN GROUNDWATER

CROSS SECTION

FOTOHUT CROSS SECTION A–A'

1 / A–A'

SCALE: 1"=5'

DATE: 11/15/93 DRAWN BY: LRH CHECKED BY: DMM

THE JOHNSON COMPANY, INC.
Environmental Sciences and Engineering
MONTPELIER, VERMONT

1-0342-2\SECTION

Soils inside the building are contaminated with VOCs above the apparent seasonal high groundwater table (SHGW). One probable migration mechanism is volatilization from a NAPL pool. The concrete floor and frost walls of the building act as a trap for VOC vapors. The vapors probably condense below the frozen soils and unheated floor during the winter time, and drip back down to groundwater. This percolation has left a residual saturation of contaminants above the SHGW. If this scenario is correct, the soils contamination will be relatively evenly spread in the soils above the NAPL.

A second probable mechanism of contamination migration is long term slow leakage from the process pipes. This mechanism is supported in specific locations by "hot spots" in the shallow soils. Migration through subsurface pipes and preferential conduits is another potential pathway. The storm drains are a potential receptor of any contaminated groundwater migrating below the Foto-Hut building. The storm drain system was installed prior to 1959, and empties into the Rutland sanitary sewer.

A four inch diameter iron pipe was discovered in the floor of the Foto-Hut building. The top of the pipe was flush with the floor, and there was no evidence of grates or other construction typical of a floor drain. The four inch pipe makes a right angle bend immediately below the concrete floor. The iron pipe is then connected to a four inch clay or concrete pipe which travels horizontally below the floor in a southeast direction. The connection is loose, and soil has entered the pipe. A PID measurement performed on November 5 gave a 42 ppm headspace in the pipe. The flush geometry of the pipe penetration is not typical of either a sanitary sewer connection or a floor drain. The most likely use of the pipe would be a drain from a specific piece of equipment.

Piping inside the Foto-Hut building is primarily placed directly below the concrete floor. The floor thickness varies from 4 inches to one foot. The 1 to 2" diameter pipes typically have threaded couplings, bushings, etc. where they penetrate the floor. The concrete floor was in place prior to 1925 per the Sanborn insurance maps.

Some chemical specific observations are provided below:

PCE and 1,2 DCE

There has been limited migration of NAPL/Dissolved PCE.
1,2-DCE may be a daughter or a contaminant of the original solvent.
PCE concentrations in soils exceed Interim Soil Cleanup Guidance (ISCG) levels of 20 times the Enforcement Standards (ES = 0.7 ppb) in groundwater.

PCE has not been detected in groundwater on-site.

1,2-DCE concentrations in groundwater are above the ES of 70 ppb below the Foto-Hut building.

Widely disparate soil concentrations are reported for MW-8 and S-1 samples. This may be due to natural soil and sampling variability, or to volatilization after penetration of concrete.

The PCE plume in soils appears to have moved slightly downgradient from the tanks.

Migration of PCE and 1,2-DCE is primarily by volatilization/condensation over NAPL pool.

TOLUENE

Apparently there are two sources: Pipe I, and the USTs.

Migration is probable by all three phases.

The ES and ISCG level are not exceeded in water or soils respectively.

ETHYLBENZENE

The ES has not been exceeded in groundwater.

The ISCG level is exceeded in soils in the UST area and under the building.

XYLENES

The ES of 400 is exceeded inside building and at former UST locations.

The ISCG level of 8000 is exceeded near the UST area and under the Foto-Hut building.

There appear to be two sources: Pipe I, and the USTs.

Water quality results at MW-5 are questionable.

Migration is primarily by free product phase, and less by dissolved or vapor phases.

Based on only two measurements, the xylene concentration in groundwater has decreased in OB1 in 11 months, as have ethylbenzene and toluene concentrations. This is probably due to removal of the source, or could be seasonal (or precipitation related).

3.5 SOURCES OF CONTAMINATION

A list of proven and suspected sources is provided in this Section. Proven sources are documented by laboratory analysis of contaminated soils and product samples. Suspected sources are based on PID measurements and association with proven sources.

Five primary sources have been demonstrated to have caused a release of hazardous materials to the Site:

1. Leaks from pipes - at soil sample B5 by toluene concentration in soils.
2. Tank #1 by PCE/TEX in soils and contents. No lid to tank.
3. Tanks 2 and 3 by Ethylbenzene, xylenes and PCE in soils and contents. Holes in tank lids.
4. Capped pipes 1, 2 and 3 by TEX in Soils (sample O1) (Pipe locations included in Appendix 1).
5. Pipes I & J - PID 19.5/7 - Pipe sample and B3 soil sample confirms release of PCE and TEX.

Suspected sources of additional releases are listed below:

1. Suspected UST near end of Pipes 1,2 and 3.
2. 4" drain - PID of 42 ppm.
3. Pipes A & K - PID 42 ppm.
4. Pipe C - PID 16 ppm.
5. Pipes F, G, & E - 10 ppm.

3.6 CONCEPTUAL REMEDIAL DESIGN

Numerous remedial options were considered for this Site. Remediation of the Site at this time will concentrate on soils contaminated above regulatory guidelines. There are no documented enforcement standard exceedances beyond the property line which are attributable to the Foto-Hut Site. Therefore design of a groundwater treatment system should not occur at this time.

Soil remedial measures may be warranted due to the risk of contamination of groundwater from the residual levels of contamination in the soils. Soil contamination above Interim Soil Cleanup Guidance limits has been demonstrated in the vicinity of the removed USTs and under the un-used portion of the Foto-Hut building.

Vapor extraction and treatment can be an effective method of soil remediation. In-situ treatment would use vapor extraction with activated carbon adsorption on the vapor phase end of the system. Activated carbon which becomes saturated with contaminants removed from the soil vapors could then be "reactivated" or recycled, thus provided a "closed loop" remedial system with the added benefit of incineration for the final disposition of the collected contaminants. Vapor extraction is most effective with highly volatile compounds and permeable soils. The low permeability soils below the Foto-Hut site, combined with the shallow depth to groundwater, may limit the effectiveness of vapor extraction. Vapor extraction technology should be investigated further if additional data indicates that the soils below the southern portion are the Foto-Hut building are contaminated above regulatory guidelines.

Natural or enhanced biodegradation is sometimes used for in-situ treatment of contaminated soils. However, biodegradation of PCE often creates daughter products which are lethal to the degrading organisms. In addition, enhancement of biodegradation requires "feeding" of the degrading organisms. This feeding requires injection and adequate dispersal of nutrients into the soil. Adequate dispersal of the nutrients is not likely given the low permeability of the soils on-site.

Removal of contaminated soils by excavation, and transport off-site for disposal appears to be the most feasible option for soils remediation. Air quality standards could be maintained during removal by adequate ventilation of the existing un-used Foto-Hut building. Treatment of the collected vapors by carbon absorption may be necessary. The removal could coincide with excavations of contaminated piping and suspected USTs. It may be feasible to dispose of the excavated soils at an asphalt batch plant. Otherwise, soil disposal will be in a certified landfill. It may be necessary to install slurry walls to contain inaccessible pockets of residual contamination.

In conjunction with soil removal, we recommend the placement of a barrier against physical contact and infiltration. This would consist of backfilling and paving the areas from which contaminated soils were removed. Demolition of the un-used portion of the building and paving the area could be performed by non-OSHA trained personnel after the soil excavation was complete.

4.0 RESULTS, CONCLUSIONS, AND INTERPRETATIONS

Most of the interpretations in this report should be treated as current working hypothesis, which will be confirmed based on data collected during the detailed remedial investigation and action design.

Groundwater flow in the surficial aquifer is towards the south and southeast. Groundwater flow directions and gradients are strongly influenced by infiltration in un-paved areas. The vertical gradient in the surficial aquifer is downwards.

Soils are typically low permeability sands with a large percentage of silt and gravel. Numerous preferential migration pathways may exist. These pathways may include the storm drain system and process pipes below the concrete floor of the building.

Five contaminant release sources have been confirmed at the Site. These source locations include three former USTs and two pipe locations. A large proportion, if not all of the contaminated soils and

groundwater on-site is due to releases from the USTs and their associated piping. Observations of NAPL collected in tanks indicate that it is less dense than water.

Based on the data provided by the International Fabric Care Institute, and on the geometry of the USTs and piping, the remedial costs associated with this site are eligible for reimbursement through the Vermont Petroleum Cleanup Fund (PCF). The dry cleaning operation was primarily a petroleum based technology. Perchloroethylene was probably only used for cleansing spots, and is a contaminant, rather than a primary constituent of the tank and pipe contents. VSA Title 10, Chapter 59, §1922(10) defines an underground storage tank. This definition states that the underground pipes connected to the tanks are included in as part of the UST. VSA Title 10, Chapter 59, §1926 authorizes reimbursement of abandoned UST closure under certain conditions. These conditions have been met, as documented in Charles Schwer's October 28, 1991 letter to Michael Pottinger of The Johnson Company. All tank removal, and sludge and soil disposal actions have been pre-approved by the Sites Management Section (SMS), and are eligible for reimbursement by the PCF. This investigation and its associated work plan were also approved by the SMS and are eligible for reimbursement.

The groundwater is locally contaminated at wells MW-8 and OB-1 above enforcement standards by xylenes and 1,2-dichloroethylene. There is no evidence that enforcement standards have been exceeded beyond the property line due to releases on-site.

The soils are contaminated above Vermont Interim Soil Cleanup Guidance (VISCG) limits by ethylbenzene, xylenes, perchlorethylene, and probably 1,2-dichloroethylene. With the exception of the xylenes, this contamination above the ISCG limits is only in the vicinity of the former USTs and the western section of the Foto-Hut building. Toluene is also present in the soils at relatively low concentrations.

High benzene and MTBE concentrations in groundwater at the Eddy Site, and the lack of these compounds at the Foto-Hut Site indicate that the Foto-Hut Site is not the source of the contamination below the Eddy Site. The two Sites exhibit different chemical signatures. Xylene in groundwater at the Eddy Site is always associated with MTBE and Benzene, which are not found at the Foto-Hut Site. Very low concentrations, 1 ppb of 1,2 DCE, and 2 ppb of PCE were measured in water samples from MW-102 on the Eddy Site. These compounds are probably due to a nearby source, rather than the Foto-Hut Site. Monitoring wells MW-7 and MW-103 are both between known Foto-Hut sources and well MW-102. A water sample collected from MW-7 is clean, and samples from MW-103 did not have detectable levels of

PCE or 1,2 DCE.

The Johnson Company recommends preparation of a remedial investigation and design work plan. The work plan should include the following tasks:

- Determine temporal changes in water quality by monitoring groundwater and storm drains quarterly for at least one year. Laboratory analysis should be by EPA Method 8240 with 5 ppb detection limits.

- Determine extent of xylene contamination in soils and groundwater by the installation of additional wells, and collection of additional soils samples.

- Evaluate suspected sources by removal of interior pipes with concurrent soil analysis by PID.

- Evaluate suspected UST locations by excavation.

- Remove contaminated soils below and west of un-used portion of Foto-Hut building and treat off-site. Presumed UST location

- Evaluate in-situ soil venting below used portion of Foto-Hut building if soils sample analysis indicates exceedances of VISCG limits.

- Demolish un-used portion of Foto-Hut building and pave former UST and building locations to prevent infiltration and physical contact with residual contamination.

- Interview previous employees of Rutland Cleaners and Dyers

APPENDIX A

Property Ownership Records

PHOTOGRAMMETRIC TOPOGRAPHIC MAP
VERMONT AGENCY OF TRANSPORTATION
1958 1"=200' 5' CI.
#213 3OF3

APPROX M NORTH

77 WOODSTOCK AVE TOWN AND CITY PROPERTY OWNERSHIP RECORDS			
BOOK	PAGE	DATE	TRANSFER NOTES
189	501-503	10-14-76	Rutland Savings Bank to The Daniels Corp.
188	149	10-14-76	First VT Bank to Rutland Savings Bank (A parcel of land on NW corner, Woodstock Ave. and Tremont)
176	410-411	12-16-74	Bratco, Inc. to First Vermont Bank & Trust Co.
147	321	5-15-69	Saverio J. Garafano etal to Bratco Inc. (Lots 43,44,45,46 on Montvert Park), Saverio J. Garafano and Pasquale J. Garafano
113	75	2-8-62	Register New Business - Garos Cleaning & Laundering Center (Cleaning & Laundering)
131	339-340	6-2-60	Pasquale J. & Saurio S. Garofano to Rutland Housing Authority (Lots 47, 48 & 49 as shown on Map of Montvert Park) and land sold to Garafano's by Marie T. Pate
112	320	6-2-60	Marie T. Pate to Garafano's (property bounds Briggs Autobody Shop) Lots 46 & 54 Montvert Park, etc. made by A.C. Grover, C.E.
107	161	5-7-57	Guardian's Deed - Frank P. Garofano, guardian of Luigia Garafano to Pasquale & Saverio J. Garafano

77 WOODSTOCK AVE TOWN AND CITY PROPERTY OWNERSHIP RECORDS			
BOOK	PAGE	DATE	TRANSFER NOTES
99	454	6-16-55	Antonio & Luigia Garafano to Saverio J. & Pasquale J. Garafano - Property bounds south - Woodstock Ave. east - Tremont St., north land of Lonis M. Gagnon, west property of Frank E. Briggs and land of Marie T. Pate
55	290	7-17-31	Lease between Antonia Garofano & Shell Eastern Petroleum Corp. - 5 year lease - Begin 40 ft. west of Tremont & Woodstock (essentially appears on western corner of Woodstock & Tremont) Rent is 1 cent per gallon gasoline delivered to storage tanks on leased property.
45	143	7-12-26	Antonia, Ralph & Joseph Jennings to Antonia * Louise Garafano (Lots 47, 48, 49 - Lots 45,46 of Montvert Park)
36	306	11-20-19	Henry D. Whitney to Antonio Garofano (Lots 43 & 44 Montvert Park)
Hanging Map 215	37	8-15-13	Monvert Park Building Lots Aug. 1913 Harry D. Whitney Owner, The Foto Hut site appears to be Lots 43, 44, 45 and possibly 46

84 WOODSTOCK AVE TOWN AND CITY PROPERTY OWNERSHIP RECORDS			
BOOK	PAGE	DATE	TRANSFER NOTES
286	341	6-30-89	Page 343 Mortgage Deed - Alan H. Perry & Ann Perry to John F. & Donna Haynes - Lots 3 & 4
151	573	5-8-70	Axel J. & Jane O. Anderson to Alan H. Perry & Ann Perry
90	1	9-17-49	Fred R. & Marjorie E. Hudson to Axel & Jane Anderson
73	395-396	1-10-46	Lot 3 & 4 of Harris Property Building Lots of H.D. Whitney, October 1913 - Ward Baking Company to Fred R. Hudson, Parcel is a part of the land conveyed by Grace O. Brien to Vermont Banking Co. (9-10-41) Book 66, page 67 - subsequently granted from Vermont Baking to Ward Baking, Book 73, page 201
60	179	4-16-35 to 12-15-45	Land leased by Sinclair Refining Co.
73	201	6-7-45	Vermont Baking to Ward Baking - Lots 3 & 4
66	467	9-19-41	Grace O'Brien Coughlin to Vermont Baking Company - Lots 3 & 4 - Subject to a certain lease between Grace O'Brien Coughlin and Sinclair Refining Co.
60		4-16-35	Service Station Lease between Frederick E. Coughlin & Grace E. Coughlin of 82 Woodstock Avenue & Sinclair Refining Co. - Oil and gasoline station
52	431	7-6-33	Raffael Abatiell to Frederick & Grace O'Brien - Lots 3 & 4
45	337	5-7-27	Lucy E. Alberico to Raffael Abatiell
36	309	12-13-19	Henry D. Whitney to Lucy F. Alberico

1991 JOHNSON CITY DIRECTORY
US WEST MARKETING RESOURCES
JOHNSON DIRECTORY DIVISION

DATE	ADDRESS	OCCUPANT
1991	75 Woodstock Ave.	Park Antiques
	76 Woodstock Ave.	Sherwin Williams
	77 Woodstock Ave.	Foto Hut - also
		The Stitchery
		Brownsville Girl Shoe Repair
	84 Woodstock Ave.	Filippo Cleaners & Taylors
	86 Woodstock Ave.	H.A. Eddy
	87 Woodstock Ave.	Chittenden Bank
		Cinema North Group
		Couture & Co.
	93 Woodstock Ave.	Bob's Texaco
1987	75 Woodstock Ave.	Curious Eye World of Sweaters
		Park Antiques
	77 Woodstock Ave.	Foto Hut
	84 Woodstock Ave	Automatic Laundry & Dry Cleaners
		Diamond Uniform
		Snow White Linens
	86 Woodstock Ave.	Eddy
		Niko's Restaurant
		US Post Office
	87 Woodstock Ave	Chittenden Bank
		Cinema North
		Couture Co.
	93 Woodstock Ave	Bob's Sunoco
1986	77 Woodstock Ave.	Mannings
	87 Woodstock Ave	Chittenden Bank
1985	77 Woodstock Ave.	Mannings
	75 Woodstock Ave.	Same as 1987
	84 Woodstock Ave.	Automatic Dry Cleaner
	86 Woodstock Ave	H.A. Eddy
	87 Woodstock Ave.	Chittenden Bank
	93 Woodstock Ave	Bob's Sunoco
1984	77 Woodstock Ave.	Same as 1985
	75 Woodstock Ave.	Brigg's Autobody Shop
	84 Woodstock Ave	Automatic Dry Cleaners
	86 Woodstock Ave	H.A. Eddy
	87 Woodstock Ave	Same as 1985
	93 Woodstock Ave	Bob's Texaco

1991 JOHNSON CITY DIRECTORY
US WEST MARKETING RESOURCES
JOHNSON DIRECTORY DIVISION

DATE	ADDRESS	OCCUPANT
1983	75 Woodstock Ave. ..... 77 Woodstock Ave. ..... 84 Woodstock Ave. ..... 86 Woodstock Ave. ..... 87 Woodstock Ave ..... 93 Woodstock Ave.	Brigg's Autobody Shop Grace A Land Office Automatic Dry Cleaners H.A. Eddy Rutland Bank Bob's Sunoco
1982	75 Woodstock Ave. ..... 77 Woodstock Ave. ..... 84 Woodstock Ave. ..... 86 Woodstock Ave. ..... 87 Woodstock Ave ..... 93 Woodstock Ave.	Same Vacant Perry's Automatic Laundry & Dry Cleaners H.A. Eddy (Under Construction) Rutland Savings Bank, Real Estate Bob's Texaco
1981	75 Woodstock Ave. ..... 77 Woodstock Ave. ..... 84 Woodstock Ave. ..... 86 Woodstock Ave. ..... 87 Woodstock Ave ..... 93 Woodstock Ave.	Same Same Same No Report Same Same
1980	Same except 86 Woodstock Ave. is a residence	
1979	Same	
1978	Same except 87 Woodstock Ave.	Vacant
1977	Same except 77 Woodstock Ave. ..... 86 Woodstock Ave.	Vermont Cycle Residence and Vandy's Steak House
1976	Same except 93 Woodstock Ave.	Tony's Texaco
1973-1974	75 Woodstock Ave. ..... 77 Woodstock Ave. ..... 84 Woodstock Ave. ..... 86 Woodstock Ave. ..... 93 Woodstock Ave.	Same Same Automatic Dry Cleaning Center Smiley's Steak House Tony's Texaco
1972	75 Woodstock Ave. ..... 77 Woodstock Ave. ..... 84 Woodstock Ave. ..... 86 Woodstock Ave. ..... 93 Woodstock Ave.	Same Vacant Same Residence and Vacant Same

1991 JOHNSON CITY DIRECTORY
US WEST MARKETING RESOURCES
JOHNSON DIRECTORY DIVISION

DATE	ADDRESS	OCCUPANT
1971	75 Woodstock Ave.	Same
	77 Woodstock Ave.	Not Listed
	82 Woodstock Ave.	Automatic Laundry & Dry Cleaners
	84 Woodstock Ave.	Automatic Laundry
	86 Woodstock Ave.	Vincent's Restaurant
	93 Woodstock Ave.	Same
1970	75 Woodstock Ave.	Same
	77 Woodstock Ave.	Rutland Cleaners & Dyers
	82 Woodstock Ave.	Dry Cleaning Center
	84 Woodstock Ave.	Three-D Chemical Co. Automatic Laundry
	86 Woodstock Ave.	Restaurant
	93 Woodstock Ave.	Ben's Texaco
1968	75 Woodstock Ave.	Same
	77 Woodstock Ave.	Same
	82 Woodstock Ave.	Same
	84 Woodstock Ave.	United Chemical Co. Automatic Laundry
	86 Woodstock Ave.	Same
	93 Woodstock Ave.	Same
1966	Same except 86 Woodstock Ave.	No restaurant
1964	Same	
1961	Same except 77 Woodstock Ave.	Rutland Cleaners & Dyers Plant
	86 Woodstock Ave.	Restaurant
	93 Woodstock Ave.	Johnson's Texaco
1960 & 1958	75 Woodstock Ave.	Briggs Autobody
	77 Woodstock Ave.	Rutland Cleaners & Dyers Plant
	82 Woodstock Ave.	Rutland Upholsteries
	84 Woodstock Ave.	United Chemical Automatic Laundry
	86 Woodstock Ave.	Restaurant
	93 Woodstock Ave.	Fletcher's Texaco
1955	75 Woodstock Ave.	Same
	77 Woodstock Ave.	Same
	82 Woodstock Ave.	Non Hazardous
	84 Woodstock Ave.	Same
	86 Woodstock Ave.	Restaurant
	93 Woodstock Ave.	Same
1951	Same except 86 Woodstock Ave	No restaurant

1991 JOHNSON CITY DIRECTORY
US WEST MARKETING RESOURCES
JOHNSON DIRECTORY DIVISION

DATE	ADDRESS	OCCUPANT
1947	75 Woodstock Ave. ..... 77 Woodstock Ave. ..... 84 Woodstock Ave. ..... 86 Woodstock Ave. ..... 93 Woodstock Ave.	Same Same Vacant & Frederick Hudson, Auto Electrician Residence Same
1944	75 Woodstock Ave. ..... 77 Woodstock Ave. ..... 84 Woodstock Ave. ..... 86 Woodstock Ave. ..... 93 Woodstock Ave.	Same Same Vacant gas station Residence Dept. of Justice Immigration, Naturalization
1942	75 Woodstock Ave. ..... 77 Woodstock Ave. ..... 84 Woodstock Ave. ..... 86 Woodstock Ave. ..... 93 Woodstock Ave.	Same Same Same Same Texaco Service Station
1940	75 Woodstock Ave. ..... 77 Woodstock Ave. ..... 84 Woodstock Ave. ..... 86 Woodstock Ave. ..... 93 Woodstock Ave.	Not Listed Same Sinclair Service Station Same Texaco Station
1937	77 Woodstock Ave. ..... 84 Woodstock Ave. ..... 86 Woodstock Ave. ..... 87 Woodstock Ave. ..... 93 Woodstock Ave.	Same Sinclair Service Station Residence Rutland Cleaners & Dyers Not listed
1936	77 Woodstock Ave. ..... 87 Woodstock Ave.	Rutland Cleaners & Dyers Plant Rutland Cleaners & Dyers
1935	77 Woodstock Ave. ..... 86 Woodstock Ave. ..... 87 Woodstock Ave. ..... 93 Woodstock Ave.	Same Residence Woodstock Ave. Filling Station Not Listed
1933	77 Woodstock Ave. ..... 86 Woodstock Ave. ..... No listing for 84, 87 or 93 Woodstock Ave.	Same Same
1936	84 Woodstock Ave.	Sinclair Service Station

1991 JOHNSON CITY DIRECTORY
US WEST MARKETING RESOURCES
JOHNSON DIRECTORY DIVISION

DATE	ADDRESS	OCCUPANT
1934	77 Woodstock Ave.	Same
	84 Woodstock Ave.	No Listing
	86 Woodstock Ave.	Same
	87 Woodstock Ave.	Vacant
	93 Woodstock Ave.	No Listing
1930	77 Woodstock Ave.	Rutland Cleaners
	82 Woodstock Ave.	No Listing
	84 Woodstock Ave.	No Listing
	86 Woodstock Ave.	Same
	87 Woodstock Ave.	No Listing
	93 Woodstock Ave.	Residence
1928	All same, 93 now 97 Woodstock Ave.	
1927	No 77, 82, 84 87 Woodstock Ave. 86 - same	
1924	Same	
1919	Same	

CHITTENDEN BANK
ENVIRONMENTAL SITE ASSESSMENT
FOTO-HUT PROPERTY, REAR BUILDING
RUTLAND, VERMONT



KEY

SOIL SAMPLE LOCATION
PIPE END, SEE BELOW

PIPE	DIAMETER	PID (ppm)
A	1-1/4"	42
B	1-1/2"	0
C	1-1/2"	16
D	3/4"	0
E	2"	0.7
F	1-1/4"	10
G	2"	0
H	1-1/2"	2
I	1-1/2"	19.5
J	1-1/2"	7
K	1-1/2"	

THE JOHNSON COMPANY, INC.
Environmental Sciences and Engineering
MONTPELIER, VERMONT 1991

APPENDIX B

Well Logs

The Johnson Company, Inc.
Environmental Sciences and Engineering
5 State Street
Montpelier, Vermont 05602

DRILLING LOG
WELL # PZ-1

Project: Fatchat Property
Location: Rutland, Vermont
Job # 1-0342-2
Logged By: DMM/LRH
Date Drilled: 11/05/93
Driller: The Johnson Company
Drill Method: 4" Solid Stem Auger

Casing Type: PVC
Casing Diameter: 1.5 in.
Casing Length: 4.9 ft.
Screen Type: Factory slotted
Screen Diameter: 1.5 in.
Screen Length: 0.9 ft.
Slot Size: .010

Total Pipe: 5.9 ft.
Stick Up: 0.0 ft.
Total Hole Depth: 5.9 ft.
Well Guard Length: 0.0 ft.
Initial Water Level: None
Surface Elevation: –
T.O.C. Elevation: –

▌ = Sampled interval

Sheet 1 of 0



The Johnson Company, Inc.
Environmental Sciences and Engineering
5 State Street
Montpelier, Vermont 05602

DRILLING LOG
WELL # OB-1

Project: Chittenden Bank-Fotohut
Location: 77A Woodstock, Rutland Vt
Job # 1-0342-2
Logged By: D. Maynard
Date Drilled: 3/12/92
Driller: N/A
Drill Method: Excavator

Casing Type: PVC
Casing Diameter: 2.0 in.
Casing Length: 8.0 ft.
Screen Type: Factory slotted
Screen Diameter: 2.0 in.
Screen Length: 5.0 ft.
Slot Size: 0.010

Total Pipe: 13.0 ft.
Stick Up: 2.0 ft.
Total Hole Depth: 11.0 ft.
Well Guard Length: 5.0 ft.
Initial Water Level: 4.9 ft.
Surface Elevation: 690.25
T.O.C. Elevation: 692.25

▌ = Sampled Interval

Sheet 1 of 1



The Johnson Company, Inc.
Environmental Sciences and Engineering
5 State Street
Montpelier, Vermont 05602

DRILLING LOG
WELL # MW-1

Project: Fotohut
Location: 77A Woodstock, Rutland
Job # 1-0342-2
Logged By: D. Maynard
Date Drilled: 9/30/93
Driller: Tristate
Drill Method: Hollow Stem

Casing Type: PVC
Casing Diameter: 2.0 in.
Casing Length: 10.8 ft.
Screen Type: Factory slotted
Screen Diameter: 2.0 in.
Screen Length: 4.8 ft.
Slot Size: .010"

Total Pipe: 15.8 ft.
Stick Up: -0.2 ft.
Total Hole Depth: 16.0 ft.
Well Guard Length: 0.0 ft.
Initial Water Level: 5.7 ft.
Surface Elevation: 689.90
T.O.C. Elevation: 689.70

▌ = Sampled Interval

Sheet 1 of 1



The Johnson Company, Inc.
Environmental Sciences and Engineering
5 State Street
Montpelier, Vermont 05602

DRILLING LOG
WELL # MW-2

Project: Fotohut
Location: 77A Woodstock, Rutland
Job # 1-0342-2
Logged By: D. Maynard
Date Drilled: 9/30/93
Driller: Tristate
Drill Method: Hollow Stem

Casing Type: PVC
Casing Diameter: 2.0 in.
Casing Length: 4.6 ft.
Screen Type: Factory slotted
Screen Diameter: 2.0 in.
Screen Length: 4.6 ft.
Slot Size: .010"

Total Pipe: 9.3 ft.
Stick Up: -0.5 ft.
Total Hole Depth: 10.0 ft.
Well Guard Length: 0.0 ft.
Initial Water Level: 4.0 ft.
Surface Elevation: 689.76
T.O.C. Elevation: 689.26

▮ = Sampled Interval

Sheet 1 of 1



PID Reading	Description
1.8	0-3' off auger flights. Dark brown humid fine sand, some silt, organics. Hard drilling 2-3'.
1.8	3-5' 3,1,1,5 22" recovery. 0-6" Light brown damp coarse and medium sand grading down to fine and medium sand. Sharp horizontal contacts and many distinct fine orange mottles.
2.2	6-18" Black damp silt, little fine sand. many prominant fine orange mottles. Sharp steeply dipping contact. 18-22" Light brown moist fine sand, some silt. Many fine distinct orange mottles.
26	5-7' 5,11,18,30 12" recovery. Light brown fine sand , some silt, angular pebbles. Moist at top and humid at base. Few faint fine orange/olive mottles. Rocky drilling 6-7'
	7-9' 9,8,10,5 14" recovery. Light grey saturated fine sand, little site, angular gravel. Black stains in upper 6". PID 90ppm in hole. Auger tip at 9.75' same as above.

The Johnson Company, Inc.
Environmental Sciences and Engineering
5 State Street
Montpelier, Vermont 05602

DRILLING LOG
WELL # MW-3

Project: Fotohut
Location: 77A Woodstock, Rutland
Job # 1-0342-2
Logged By: D. Maynard
Date Drilled: 9/30/93
Driller: Tristate
Drill Method: Hollow Stem

Casing Type: PVC
Casing Diameter: 2.0 in.
Casing Length: 4.7 ft.
Screen Type: Factory slotted
Screen Diameter: 2.0 in.
Screen Length: 4.8 ft.
Slot Size: .010"

Total Pipe: 9.7 ft.
Stick Up: -0.2 ft.
Total Hole Depth: 9.8 ft.
Well Guard Length: 0.0 ft.
Initial Water Level: 5.6 ft.
Surface Elevation: 689.59
T.O.C. Elevation: 689.44

▌ = Sampled Interval

Sheet 1 of 1



The Johnson Company, Inc.
Environmental Sciences and Engineering
5 State Street
Montpelier, Vermont 05602

DRILLING LOG
WELL # MW-4

Project: Fotohut
Location: 77A Woodstock, Rutland
Job # 1-0342-2
Logged By: D. Maynard
Date Drilled: 10/01/93
Driller: Tristate
Drill Method: Hollow stem

Casing Type: PVC
Casing Diameter: 2.0 in.
Casing Length: 4.3 ft.
Screen Type: Factory slotted
Screen Diameter: 2.0 in.
Screen Length: 9.7 ft.
Slot Size: .010"

Total Pipe: 14.1 ft.
Stick Up: -0.5 ft.
Total Hole Depth: 14.6 ft.
Well Guard Length: 0.0 ft.
Initial Water Level: 5.9 ft.
Surface Elevation: 689.87
T.O.C. Elevation: 689.37

▌ = Sampled Interval

Sheet 1 of 1



The Johnson Company, Inc.
Environmental Sciences and Engineering
5 State Street
Montpelier, Vermont 05602

DRILLING LOG
WELL # MW-5

Project: Fotohut
Location: 77A Woodstock, Rutland
Job # 1-0342-2
Logged By: D. Maynard
Date Drilled: 10/01/93
Driller: Tristate
Drill Method: Hollow stem

Casing Type: PVC
Casing Diameter: 2.0 in.
Casing Length: 3.8 ft.
Screen Type: Factory slotted
Screen Diameter: 2.0 in.
Screen Length: 4.6 ft.
Slot Size: .010"

Total Pipe: 8.5 ft.
Stick Up: -0.5 ft.
Total Hole Depth: 9.0 ft.
Well Guard Length: 0.0 ft.
Initial Water Level: 7.4 ft.
Surface Elevation: 688.55
T.O.C. Elevation: 688.05

▌ = Sampled Interval

Sheet 1 of 1



The Johnson Company, Inc.
Environmental Sciences and Engineering
5 State Street
Montpelier, Vermont 05602

DRILLING LOG
WELL # MW-6

Project: Fotohut
Location: 77A Woodstock, Rutland
Job # 1-0342-2
Logged By: D. Maynard
Date Drilled: 10/01/93
Driller: Tristate
Drill Method: Hollow stem

Casing Type:
Casing Diameter:
Casing Length:
Screen Type:
Screen Diameter:
Screen Length:
Slot Size:

Total Pipe: 0.0 ft.
Stick Up: 0.0 ft.
Total Hole Depth: 4.5 ft.
Well Guard Length: 0.0 ft.
Initial Water Level: 4.7 ft.
Surface Elevation: 688.48
T.O.C. Elevation: N/A

▌ = Sampled Interval

Sheet 1 of 1



The Johnson Company, Inc.
Environmental Sciences and Engineering
5 State Street
Montpelier, Vermont 05602

DRILLING LOG
WELL # MW-7

Project: Fotohut
Location: 77A Woodstock, Rutland
Job # 1-0342-2
Logged By: D. Maynard
Date Drilled: 10/01/93
Driller: Tristate
Drill Method: Hollow stem

Casing Type: PVC
Casing Diameter: 2.0 in.
Casing Length: 3.6 ft.
Screen Type: Factory slotted
Screen Diameter: 2.0 in.
Screen Length: 4.6 ft.
Slot Size: .010"

Total Pipe: 8.4 ft.
Stick Up: -0.6 ft.
Total Hole Depth: 9.0 ft.
Well Guard Length: [illegible] ft.
Initial Water Level: [illegible] ft.
Surface Elevation: [illegible]
T.O.C. Elevation: [illegible]

▌ = Sampled Interval

Sheet 1 of 1



The Johnson Company, Inc.
Environmental Sciences and Engineering
5 State Street
Montpelier, Vermont 05602

DRILLING LOG
WELL # MW-8

Project: Chittenden Bank–Fotohut
Location: 77A Woodstock, Rutland Vt
Job # 1-0342-2
Logged By: E. Hanson
Date Drilled: 10/11/93
Driller: JCO
Drill Method: Solid Stem Auger

Casing Type: PVC
Casing Diameter: 1.5 in.
Casing Length: 4.9 ft.
Screen Type: Factory slotted
Screen Diameter: 1.5 in.
Screen Length: 4.6 ft.
Slot Size: 0.010

Total Pipe: 9.7 ft.
Stick Up: 1.9 ft.
Total Hole Depth: 8.0 ft.
Well Guard Length: 0.0 ft.
Initial Water Level: 5.5 ft.
Surface Elevation: 688.43
T.O.C. Elevation: 690.31

▌ = Sampled Interval

Sheet 1 of 1



APPENDIX C

SCS Soil Maps



U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
COOPERATING WITH
STATE AGRICULTURAL EXPERIMENT STATION

APPROX. SCALE 1" = 1500'

USDA-SCS-FORT WORTH, TEXAS

SOIL SURVEY FIELD SHEET
RUTLAND COUNTY, VERMONT
ADVANCE COPY - SUBJECT TO CHANGE

SURVEY HAS NOT BEEN COMPILED NOR CORRELATED. NAMES MAY BE CHANGED AND AREAS MAY BE COMBINED

5-19-62 FH-9000 11:29 VT-62-H 31-68



U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
COOPERATING WITH
STATE AGRICULTURAL EXPERIMENT STATION

APPROX. SCALE 1" = 1500'

USDA SCS FORT WORTH TEXAS

SOIL SURVEY FIELD SHEET
RUTLAND COUNTY, VERMONT
ADVANCE COPY - SUBJECT TO CHANGE
SURVEY HAS NOT BEEN COMPLETE NOR CORRELATED. NAMES MAY BE CHANGED AND AREAS MAY BE COMBINED



U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
COOPERATING WITH
STATE AGRICULTURAL EXPERIMENT STATION

APPROX. SCALE 1" = 1500'

USDA SCS FORT WORTH TEXAS

SOIL SURVEY FIELD SHEET
RUTLAND COUNTY, VERMONT
ADVANCE COPY - SUBJECT TO CHANGE

SURVEY HAS NOT BEEN COMPILED NOR CORRELATED. NAMES MAY BE CHANGED AND AREAS MAY BE COMBINED

5-10-62

VT-62-H 18-5



U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
COOPERATING WITH
STATE AGRICULTURAL EXPERIMENT STATION

APPROX. SCALE 1" = 1500'

USDA SCS FORT WORTH, TEXAS

SOIL SURVEY FIELD SHEET
RUTLAND COUNTY, VERMONT
ADVANCE COPY - SUBJECT TO CHANGE

SURVEY HAS NOT BEEN COMPILED NOR CORRELATED. NAMES MAY BE CHANGED AND AREAS MAY BE COMBINED.

SOIL SURVEY IDENTIFICATION LEGEND
RUTLAND COUNTY, VERMONT
NOVEMBER 1984

Mapping Symbol	Field Mapping Unit Name
1B	Marlow fine sandy loam, 3 to 8 percent slopes
1C	Marlow fine sandy loam, 8 to 15 percent slopes
1D	Marlow fine sandy loam, 15 to 25 percent slopes
1E	Combined with 1D
2B	Combined with 4B
2C	Marlow fine sandy loam, 8 to 15 percent slopes, very stony
2D	Marlow fine sandy loam, 15 to 35 percent slopes, very stony
2E	Marlow fine sandy loam, 35 to 60 percent slopes, very stony
3A	Combined with 3B
3B	Peru gravelly fine sandy loam, 3 to 8 percent slopes
3C	Peru gravelly fine sandy loam, 8 to 15 percent slopes
4A	Combined with 4B
4B	Peru gravelly fine sandy loam, 3 to 8 percent slopes, very stony
4C	Peru gravelly fine sandy loam, 8 to 15 percent slopes, very stony
4D	Peru gravelly fine sandy loam, 15 to 25 percent slopes, very stony
5A	Combined with 6A
5B	Combined with 6A
6A	Cabot gravelly fine sandy loam, 0 to 8 percent slopes, very stony
6B	Combined with 6A
6C	Brayton loam, 8 to 15 percent slopes, very stony
7A	Combined with 152 or 150A
8A	Combined with 152 or 150A
9	Pits-Dumps Complex
10C	Combined with 131D

Mapping Symbol	Field Mapping Unit Name
10D	Combined with 131D
10E	Combined with 131E
11	Combined with 11C or 11E
11C	Taconic-Hubbardton complex, 8 to 25 percent slopes, very rocky
11D	Combined with 11C
11E	Taconic-Hubbardton-Macomber complex, 25 to 80 percent slopes, very rocky
12D	Combined with 130D
12E	Combined with 130E
13A	Combined with 13B
13B	Hinckley gravelly loamy fine sand, 0 to 8 percent slopes
13C	Hinckley gravelly loamy fine sand, 8 to 15 percent slopes
13D	Hinckley gravelly loamy fine sand, 15 to 25 percent slopes
13E	Hinckley gravelly loamy fine sand, 25 to 40 percent slopes
14A	Sudbury fine sandy loam, 0 to 3 percent slopes
14B	Sudbury fine sandy loam, 3 to 8 percent slopes
15A	Walpole fine sandy loam, 0 to 5 percent slopes
16B	Combined with 130B
16C	Combined with 130C
16D	Combined with 130D
16E	Combined with 130E
17A	Combined with 18B
17B	Combined with 18B
17C	Combined with 18C
18A	Combined with 18B
18B	Windsor loamy sand, 3 to 8 percent slopes
18C	Windsor loamy sand, 8 to 15 percent slopes

Mapping Symbol	Field Mapping Unit Name
40D	Galway-Nellis-Farmington silt loams, 15 to 25 percent slopes, rocky
41B	Combined with 41C
41C	Farmington-Galway-Galoo silt loams, 5 to 25 percent slopes, very rocky
41D	Combined with 41C
41E	Farmington-Galway-Galoo silt loams, 25 to 50 percent slopes, very rocky
42B	Macomber-Dutchess complex, 3 to 8 percent slopes
42C	Macomber-Taconic complex, 8 to 15 percent slopes, rocky
42D	Macomber-Taconic complex, 15 to 25 percent slopes, rocky
42E	Macomber-Taconic complex, 25 to 80 percent slopes, rocky
43B	Combined with 43C
43C	Taconic-Macomber complex, 8 to 25 percent slopes, very rocky
43D	Combined with 43C
43E	Combined with 11E
44B	Dutchess silt loam, 3 to 8 percent slopes
44C	Dutchess silt loam, 8 to 15 percent slopes
44D	Dutchess silt loam, 15 to 25 percent slopes
45B	Combined with 148B
45C	Combined with 148C
45D	Combined with 148D
46B	Combined with 149B
46C	Combined with 149C
46D	Combined with 149D
46E	Combined with 149E
47B	Dutchess silt loam, 3 to 8 percent slopes, very stony
47C	Dutchess silt loam, 8 to 15 percent slopes, very stony
47D	Dutchess silt loam, 15 to 25 percent slopes, very stony

Mapping Symbol	Field Mapping Unit Name
47E	Dutchess silt loam, 25 to 60 percent slopes, very stony
48A	Combined with 148B
48B	Combined with 148B
48C	Combined with 148C
48D	Combined with 148D
49B	Combined with 149B
49C	Combined with 149C
49D	Combined with 149D
49E	Combined with 149E
50A	Massena silt loam, 0 to 8 percent slopes
50B	Combined with 50A
51A	Combined with 50A
51B	Combined with 50A
52	Combined with 152
52A	Combined with 152
53	Elvers silt loam
54A	Ninigret fine sandy loam, 0 to 4 percent slopes
55A	Combined with 6A
55B	Combined with 6A
56B	Colton-Duxbury complex, 2 to 8 percent slopes, very stony
56C	Colton-Duxbury complex, 8 to 15 percent slopes, very stony
56D	Colton-Duxbury complex, 15 to 25 percent slopes, very stony
56E	Colton-Duxbury complex, 25 to 50 percent slopes, very stony
57B	Duxbury-Colton complex, 2 to 8 percent slopes
57C	Colton-Duxbury complex, 8 to 15 percent slopes
57D	Colton-Duxbury complex, 15 to 25 percent slopes

Mapping Symbol	Field Mapping Unit Name
78A	Combined with 110
79	Combined with 110
79A	Combined with 110
80A	Kingsbury silty clay loam, 0 to 3 percent slopes
80B	Kingsbury silty clay loam, 3 to 8 percent slopes
81	Livingston silty clay loam
81A	Combined with 81
82A	Combined with 80A
82B	Vergennes clay, 3 to 8 percent slopes
82C	Vergennes clay, 8 to 15 percent slopes
82D	Vergennes clay, 15 to 25 percent slopes
82E	Vergennes clay, 25 to 50 percent slopes
83A	Combined with 61A
83B	Combined with 61B
83C	Combined with 61B
83D	Combined with 61B
84A	Combined with 161A
84B	Combined with 161B
84C	Combined with 161B
85A	Combined with 62
86	Linwood muck
86A	Combined with 86
87	Combined with 24
87A	Combined with 24
88	Birdsall muck
88A	Combined with 88

Mapping Symbol	Field Mapping Unit Name
90B	Hartland silt loam, 3 to 8 percent slopes
90C	Hartland silt loam, 8 to 15 percent slopes
90D	Hartland silt loam, 15 to 25 percent slopes
90E	Combined with 90D
91B	Combined with 30B
91C	Combined with 30C
91D	Combined with 30D
92B	Combined with 31B
92C	Combined with 31C
92D	Combined with 31D
92E	Combined with 31E
94B	Combined with 148B
94C	Combined with 148C
95	Udorthents, loamy
96	Udipsamments, nearly level
97A	Warwick-Quonset complex, 0 to 3 percent slopes
97B	Warwick-Quonset complex, 3 to 8 percent slopes
97C	Warwick-Quonset complex, 8 to 15 percent slopes
97D	Warwick-Quonset complex, 15 to 25 percent slopes
97E	Quonset-Warwick complex, 25 to 45 percent slopes
98C	Combined with 148C
98D	Combined with 148D
99B	Copake gravelly fine sandy loam, 2 to 8 percent slopes
99C	Combined with 13C
99D	Combined with 13D
100A	Combined with 18B

Mapping Symbol	Field Mapping Unit Name
135D	Mundal loam, 15 to 35 percent slopes, very stony
135E	Mundal loam, 35 to 60 percent slopes, very stony
138B	Combined with 1B
138C	Berkshire gravelly fine sandy loam, 8 to 15 percent slopes
139B	Sunapee gravelly fine sandy loam, 3 to 8 percent slopes
139C	Sunapee gravelly fine sandy loam, 8 to 15 percent slopes
140C	Benson very channery loam, 3 to 15 percent slopes
140D	Benson very channery loam, 15 to 25 percent slopes
140E	Benson very channery loam, 25 to 50 percent slopes
141C	Combined with 41C
141E	Combined with 41E
142B	Combined with 42B
142C	Combined with 42C
142D	Combined with 42D
142E	Combined with 42E
148B	Bomoseen and Pittstown soils, 2 to 8 percent slopes
148C	Bomoseen and Pittstown soils, 8 to 15 percent slopes
148D	Bomoseen and Pittstown soils, 15 to 25 percent slopes
149B	Bomoseen and Pittstown soils, 3 to 8 percent slopes, very stony
149C	Bomoseen and Pittstown soils, 8 to 15 percent slopes, very stony
149D	Bomoseen and Pittstown soils, 15 to 25 percent slopes, very stony
149E	Bomoseen and Pittstown soils, 25 to 40 percent slopes, very stony
150A	Peacham muck, 0 to 8 percent slopes
152	Lyons silt loam
158A	Combined with 58A
161A	Elmridge sandy loam, 0 to 3 percent slopes

Mapping Symbol	Field Mapping Unit Name
161B	Elmridge sandy loam, 3 to 8 percent slopes
162A	Combined with 62
163	Canandaigua silt loam
175	Wappinger silt loam
177	Pawling silt loam
179	Combined with 110
180B	Combined with 148B
180C	Combined with 148C
180D	Combined with 148D
182B	Combined with 148B
182C	Combined with 148C
182D	Combined with 148D
183B	Combined with 149B
183C	Combined with 149C
183D	Combined with 149D
183E	Combined with 149E
224B	Combined with 123B
224C	Combined with 123C
224D	Combined with 124D
224E	Combined with 124E

APPENDIX D

Analytical Results

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-031-10
Project:	1-0342-2(044), 77A Woodstock	Sample:	OB1
Report Date:	10/28/93	Type:	Water
Collected:	10/12/93	Container:	VOA
Received:	10/14/93		
Analyzed:	10/26/93	Dilution	
By:	GMT	Factor:	5

Priority Purgable Halocarbons

Number	Compound	PQL (ug/L)	Result (ug/L)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602
(PAGE 2 OF 2 PAGES)

Client: Johnson Company
Project: 1-0342-2(044), 77A Woodstock

IEA ID: J104-031-10
Sample: OB1

Priority Purgable Aromatics

Number	Compound	PQL (ug/L)	Result (ug/L)
30	Benzene	1	BQL
31	Ethylbenzene	1	60
32	Toluene	1	8

Other TCL Compounds *

33	Xylenes	1	560
34	Methyl-t-butylether	1	BQL
35	cis-1,2-Dichloroethene	1	61

Surrogate Standard Recovery:

1,4-Dichlorobutane	106 %
1,4-Difluorobenzene	95 %

Comment:

BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
* EPA Methods 601/602 do not specify other TCL compounds. Method analysis and QC for these parameters are laboratory derived.
Quantitation limit elevated due to sample dilution prior to analysis.
Sample diluted due to high concentration of target compounds present.

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-031-02
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW 1
Report Date:	10/28/93	Type:	Water
Collected:	10/12/93	Container:	VOA
Received:	10/14/93		
Analyzed:	10/26/93	Dilution	
By:	GMT	Factor:	1

Priority Purgable Halocarbons

Number	Compound	PQL (ug/L)	Result (ug/L)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602
(PAGE 2 OF 2 PAGES)

Client: Johnson Company
Project: 1-0342-2(044), 77A Woodstock

IEA ID: J104-031-02
Sample: MW 1

Priority Purgable Aromatics

Number	Compound	PQL (ug/L)	Result (ug/L)
30	Benzene	1	BQL
31	Ethylbenzene	1	BQL
32	Toluene	1	BQL

Other TCL Compounds *

33	Xylenes	1	BQL
34	Methyl-t-butylether	1	BQL
35	cis-1,2-Dichloroethene	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	97 %
1,4-Difluorobenzene	98 %

Comment:

BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
* EPA Methods 601/602 do not specify other TCL compounds. Method analysis and QC for these parameters are laboratory derived.

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602

Client:	Johnson Company	IEA ID:	J104-031-03
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW 2
Report Date:	10/28/93	Type:	Water
Collected:	10/12/93	Container:	VOA
Received:	10/14/93		
Analyzed:	10/26/93	Dilution	
By:	GMT	Factor:	1

Priority Purgable Halocarbons

Number	Compound	PQL (ug/L)	Result (ug/L)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602
(PAGE 2 OF 2 PAGES)

Client: Johnson Company
Project: 1-0342-2(044), 77A Woodstock

IEA ID: J104-031-03
Sample: MW 2

Priority Purgable Aromatics

Number	Compound	PQL (ug/L)	Result (ug/L)
30	Benzene	1	BQL
31	Ethylbenzene	1	BQL
32	Toluene	1	BQL

Other TCL Compounds *

33	Xylenes	1	BQL
34	Methyl-t-butylether	1	BQL
35	cis-1,2-Dichloroethene	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	100 %
1,4-Difluorobenzene	97 %

Comment:

BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
* EPA Methods 601/602 do not specify other TCL compounds. Method analysis and QC for these parameters are laboratory derived.

FORM 601/2cis Rev. 041493

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602

Client:	Johnson Company	IEA ID:	J104-031-04
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW 3
Report Date:	10/28/93	Type:	Water
Collected:	10/12/93	Container:	VOA
Received:	10/14/93		
Analyzed:	10/26/93	Dilution	
By:	GMT	Factor:	1

Priority Purgable Halocarbons

Number	Compound	PQL (ug/L)	Result (ug/L)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602
(PAGE 2 OF 2 PAGES)

Client: Johnson Company
Project: 1-0342-2(044), 77A Woodstock

IEA ID: J104-031-04
Sample: MW 3

Priority Purgable Aromatics

Number	Compound	PQL (ug/L)	Result (ug/L)
30	Benzene	1	BQL
31	Ethylbenzene	1	BQL
32	Toluene	1	BQL

Other TCL Compounds *

33	Xylenes	1	BQL
34	Methyl-t-butylether	1	BQL
35	cis-1,2-Dichloroethene	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	101 %
1,4-Difluorobenzene	100 %

Comment:

BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
* EPA Methods 601/602 do not specify other TCL compounds. Method analysis and QC for these parameters are laboratory derived.

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-031-09
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW3 DUP
Report Date:	10/28/93	Type:	Water
Collected:	10/12/93	Container:	VOA
Received:	10/14/93		
Analyzed:	10/26/93	Dilution	
By:	GMT	Factor:	1

Priority Purgable Halocarbons

Number	Compound	PQL (ug/L)	Result (ug/L)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602
(PAGE 2 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-031-09
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW3 DUP

Priority Purgable Aromatics

Number	Compound	PQL (ug/L)	Result (ug/L)
30	Benzene	1	BQL
31	Ethylbenzene	1	BQL
32	Toluene	1	BQL
	Other TCL Compounds *		
33	Xylenes	1	BQL
34	Methyl-t-butylether	1	BQL
35	cis-1,2-Dichloroethene	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	103 %
1,4-Difluorobenzene	103 %

Comment:

BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
* EPA Methods 601/602 do not specify other TCL compounds. Method analysis and QC for these parameters are laboratory derived.

IEA
An Aquarion Company

Analysis Report: EPA Method 8240

Client:	Johnson Company	IEA ID:	J104-031-05
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW 4
Report Date:	10/26/93	Type:	Water
Collected:	10/12/93	Container:	VOA
Received:	10/14/93		
Analyzed:	10/25/93	Dilution	
By:	JAG	Factor:	1

Priority Pollutant Compounds

Number	Compound	PQL (ug/L)	Result (ug/L)
1	Benzene	5	BQL
2	Bromodichloromethane	5	BQL
3	Bromoform	5	BQL
4	Bromomethane	10	BQL
5	Carbon tetrachloride	5	BQL
6	Chlorobenzene	5	BQL
7	Chloroethane	10	BQL
8	2-Chloroethylvinyl ether	5	BQL
9	Chloroform	5	BQL
10	Chloromethane	10	BQL
11	Dibromochloromethane	5	BQL
12	1,2-Dichlorobenzene	5	BQL
13	1,3-Dichlorobenzene	5	BQL
14	1,4-Dichlorobenzene	5	BQL
15	1,1-Dichloroethane	5	BQL
16	1,2-Dichloroethane	5	BQL
17	1,1-Dichloroethene	5	BQL
18	1,2-Dichloroethene (Total)	5	BQL
19	1,2-Dichloropropane	5	BQL
20	cis-1,3-Dichloropropene	5	BQL
21	trans-1,3-Dichloropropene	5	BQL
22	Ethylbenzene	5	BQL
23	Methylene chloride	5	BQL
24	1,1,2,2-Tetrachloroethane	5	BQL
25	Tetrachloroethene	5	BQL
26	Toluene	5	BQL
27	1,1,1-Trichloroethane	5	5
28	1,1,2-Trichloroethane	5	BQL
29	Trichloroethene	5	BQL
30	Trichlorofluoromethane	5	BQL
31	Vinyl chloride	10	BQL

IEA
An Aquarion Company

Analysis Report: EPA Method 8240
(PAGE 2 OF 2 PAGES)

Client: Johnson Company IEA ID: J104-031-05
Project: 1-0342-2(044), 77A Woodstock Sample: MW 4

Number	Compound	PQL (ug/L)	Result (ug/L)
Other TCL Compounds:			
32	Acetone	100	BQL
33	2-Butanone	100	BQL
34	Carbon disulfide	5	BQL
35	1,2-Dibromoethane	5	BQL
36	2-Hexanone	50	BQL
37	Methyl-t-butylether	5	BQL
38	4-Methyl-2-pentanone	50	BQL
39	Styrene	5	BQL
40	Vinyl Acetate	50	BQL
41	Xylenes (Total)	5	BQL

Surrogate Standard Recovery:

1,2-Dichloroethane-d4	110 %
Toluene-d8	102 %
Bromofluorobenzene	107 %

Comments:

BQL = Below Quantitation Limit.
PQL = Practical Quantitation Limit.
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.

IEA
An Aquarion Company

Analysis Report: EPA Method 8240
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-031-06
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW 5
Report Date:	10/26/93	Type:	Water
Collected:	10/12/93	Container:	VOA
Received:	10/14/93		
Analyzed:	10/19/93	Dilution	
By:	JAG	Factor:	2

Priority Pollutant Compounds

Number	Compound	PQL (ug/L)	Result (ug/L)
1	Benzene	5	BQL
2	Bromodichloromethane	5	BQL
3	Bromoform	5	BQL
4	Bromomethane	10	BQL
5	Carbon tetrachloride	5	BQL
6	Chlorobenzene	5	BQL
7	Chloroethane	10	BQL
8	2-Chloroethylvinyl ether	5	BQL
9	Chloroform	5	BQL
10	Chloromethane	10	BQL
11	Dibromochloromethane	5	BQL
12	1,2-Dichlorobenzene	5	BQL
13	1,3-Dichlorobenzene	5	BQL
14	1,4-Dichlorobenzene	5	BQL
15	1,1-Dichloroethane	5	BQL
16	1,2-Dichloroethane	5	BQL
17	1,1-Dichloroethene	5	BQL
18	1,2-Dichloroethene (Total)	5	BQL
19	1,2-Dichloropropane	5	BQL
20	cis-1,3-Dichloropropene	5	BQL
21	trans-1,3-Dichloropropene	5	BQL
22	Ethylbenzene	5	BQL
23	Methylene chloride	5	BQL
24	1,1,2,2-Tetrachloroethane	5	BQL
25	Tetrachloroethene	5	BQL
26	Toluene	5	BQL
27	1,1,1-Trichloroethane	5	BQL
28	1,1,2-Trichloroethane	5	BQL
29	Trichloroethene	5	BQL
30	Trichlorofluoromethane	5	BQL
31	Vinyl chloride	10	BQL

IEA
An Aquarion Company

Analysis Report: EPA Method 8240
(PAGE 2 OF 2 PAGES)

Client: Johnson Company IEA ID: J104-031-06
Project: 1-0342-2(044), 77A Woodstock Sample: MW 5

Number	Compound	PQL (ug/L)	Result (ug/L)
Other TCL Compounds:			
32	Acetone	100	BQL
33	2-Butanone	100	BQL
34	Carbon disulfide	5	BQL
35	1,2-Dibromoethane	5	BQL
36	2-Hexanone	50	BQL
37	Methyl-t-butylether	5	BQL
38	4-Methyl-2-pentanone	50	BQL
39	Styrene	5	BQL
40	Vinyl Acetate	50	BQL
41	Xylenes (Total)	5	BQL

Surrogate Standard Recovery:

1,2-Dichloroethane-d4	100 %
Toluene-d8	108 %
Bromofluorobenzene	110 %

Comments:

BQL = Below Quantitation Limit.
PQL = Practical Quantitation Limit.
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
Quantitation limit elevated due to sample dilution prior to analysis.
Sample diluted due to the presence of non-target compounds.

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-031-07
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW 7
Report Date:	10/28/93	Type:	Water
Collected:	10/12/93	Container:	VOA
Received:	10/14/93		
Analyzed:	10/26/93	Dilution	
By:	GMT	Factor:	1

Priority Purgable Halocarbons

Number	Compound	PQL (ug/L)	Result (ug/L)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602
(PAGE 2 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-031-07
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW 7

Priority Purgable Aromatics

Number	Compound	PQL (ug/L)	Result (ug/L)
30	Benzene	1	BQL
31	Ethylbenzene	1	BQL
32	Toluene	1	BQL
	Other TCL Compounds *		
33	Xylenes	1	BQL
34	Methyl-t-butylether	1	BQL
35	cis-1,2-Dichloroethene	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	92 %
1,4-Difluorobenzene	93 %

Comment:

BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
* EPA Methods 601/602 do not specify other TCL compounds. Method analysis and QC for these parameters are laboratory derived.

FORM 601/2cis Rev. 041493

IEA
An Aquarion Company

Analysis Report: EPA Method 8240

Client:	Johnson Company	IEA ID:	J104-031-07
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW 7
Report Date:	10/26/93	Type:	Water
Collected:	10/12/93	Container:	VOA
Received:	10/14/93		
Analyzed:	10/19/93	Dilution	
By:	JAG	Factor:	1

Priority Pollutant Compounds

Number	Compound	PQL (ug/L)	Result (ug/L)
1	Benzene	5	BQL
2	Bromodichloromethane	5	BQL
3	Bromoform	5	BQL
4	Bromomethane	10	BQL
5	Carbon tetrachloride	5	BQL
6	Chlorobenzene	5	BQL
7	Chloroethane	10	BQL
8	2-Chloroethylvinyl ether	5	BQL
9	Chloroform	5	BQL
10	Chloromethane	10	BQL
11	Dibromochloromethane	5	BQL
12	1,2-Dichlorobenzene	5	BQL
13	1,3-Dichlorobenzene	5	BQL
14	1,4-Dichlorobenzene	5	BQL
15	1,1-Dichloroethane	5	BQL
16	1,2-Dichloroethane	5	BQL
17	1,1-Dichloroethene	5	BQL
18	1,2-Dichloroethene (Total)	5	BQL
19	1,2-Dichloropropane	5	BQL
20	cis-1,3-Dichloropropene	5	BQL
21	trans-1,3-Dichloropropene	5	BQL
22	Ethylbenzene	5	BQL
23	Methylene chloride	5	BQL
24	1,1,2,2-Tetrachloroethane	5	BQL
25	Tetrachloroethene	5	BQL
26	Toluene	5	BQL
27	1,1,1-Trichloroethane	5	BQL
28	1,1,2-Trichloroethane	5	BQL
29	Trichloroethene	5	BQL
30	Trichlorofluoromethane	5	BQL
31	Vinyl chloride	10	BQL

IEA
An Aquarion Company

Analysis Report: EPA Method 8240
(PAGE 2 OF 2 PAGES)

Client: Johnson Company IEA ID: J104-031-07
Project: 1-0342-2(044), 77A Woodstock Sample: MW 7

Number	Compound	PQL (ug/L)	Result (ug/L)
Other TCL Compounds:			
32	Acetone	100	BQL
33	2-Butanone	100	BQL
34	Carbon disulfide	5	BQL
35	1,2-Dibromoethane	5	BQL
36	2-Hexanone	50	BQL
37	Methyl-t-butylether	5	BQL
38	4-Methyl-2-pentanone	50	BQL
39	Styrene	5	BQL
40	Vinyl Acetate	50	BQL
41	Xylenes (Total)	5	BQL

Surrogate Standard Recovery:

1,2-Dichloroethane-d4	100 %
Toluene-d8	109 %
Bromofluorobenzene	106 %

Comments:

BQL = Below Quantitation Limit.
PQL = Practical Quantitation Limit.
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.

IEA
An Aquarion Company

Analysis Report: EPA Method 8240
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-031-08
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW 8
Report Date:	10/26/93	Type:	Water
Collected:	10/12/93	Container:	VOA
Received:	10/14/93		
Analyzed:	10/19/93	Dilution	
By:	JAG	Factor:	20

Priority Pollutant Compounds

Number	Compound	PQL (ug/L)	Result (ug/L)
1	Benzene	5	BQL
2	Bromodichloromethane	5	BQL
3	Bromoform	5	BQL
4	Bromomethane	10	BQL
5	Carbon tetrachloride	5	BQL
6	Chlorobenzene	5	BQL
7	Chloroethane	10	BQL
8	2-Chloroethylvinyl ether	5	BQL
9	Chloroform	5	BQL
10	Chloromethane	10	BQL
11	Dibromochloromethane	5	BQL
12	1,2-Dichlorobenzene	5	BQL
13	1,3-Dichlorobenzene	5	BQL
14	1,4-Dichlorobenzene	5	BQL
15	1,1-Dichloroethane	5	BQL
16	1,2-Dichloroethane	5	BQL
17	1,1-Dichloroethene	5	BQL
18	1,2-Dichloroethene (Total)	5	430
19	1,2-Dichloropropane	5	BQL
20	cis-1,3-Dichloropropene	5	BQL
21	trans-1,3-Dichloropropene	5	BQL
22	Ethylbenzene	5	BQL
23	Methylene chloride	5	BQL
24	1,1,2,2-Tetrachloroethane	5	BQL
25	Tetrachloroethene	5	BQL
26	Toluene	5	BQL
27	1,1,1-Trichloroethane	5	BQL
28	1,1,2-Trichloroethane	5	BQL
29	Trichloroethene	5	BQL
30	Trichlorofluoromethane	5	BQL
31	Vinyl chloride	10	BQL

IEA
An Aquarion Company

Analysis Report: EPA Method 8240
(PAGE 2 OF 2 PAGES)

Client: Johnson Company IEA ID: J104-031-08
Project: 1-0342-2(044), 77A Woodstock Sample: MW 8

Number	Compound	PQL (ug/L)	Result (ug/L)
Other TCL Compounds:			
32	Acetone	100	BQL
33	2-Butanone	100	BQL
34	Carbon disulfide	5	BQL
35	1,2-Dibromoethane	5	BQL
36	2-Hexanone	50	BQL
37	Methyl-t-butylether	5	BQL
38	4-Methyl-2-pentanone	50	BQL
39	Styrene	5	BQL
40	Vinyl Acetate	50	BQL
41	Xylenes (Total)	5	620

Surrogate Standard Recovery:

1,2-Dichloroethane-d4	95 %
Toluene-d8	109 %
Bromofluorobenzene	111 %

Comments:

BQL = Below Quantitation Limit.
PQL = Practical Quantitation Limit.
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
Quantitation limit elevated due to sample dilution prior to analysis.
Sample diluted due to the presence of non-target compounds.

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-031-11
Project:	1-0342-2(044), 77A Woodstock	Sample:	Field Blank
Report Date:	10/28/93	Type:	Water
Collected:	10/12/93	Container:	VOA
Received:	10/14/93		
Analyzed:	10/26/93	Dilution	
By:	GMT	Factor:	1

Priority Purgable Halocarbons

Number	Compound	PQL (ug/L)	Result (ug/L)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 601/602
(PAGE 2 OF 2 PAGES)

Client: Johnson Company
Project: 1-0342-2(044), 77A Woodstock

IEA ID: J104-031-11
Sample: Field Blank

Priority Purgable Aromatics

Number	Compound	PQL (ug/L)	Result (ug/L)
30	Benzene	1	BQL
31	Ethylbenzene	1	BQL
32	Toluene	1	BQL
	Other TCL Compounds *		
33	Xylenes	1	BQL
34	Methyl-t-butylether	1	BQL
35	cis-1,2-Dichloroethene	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	87 %
1,4-Difluorobenzene	81 %

Comment:

BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
* EPA Methods 601/602 do not specify other TCL compounds. Method analysis and QC for these parameters are laboratory derived.

FORM 601/2cis Rev. 041493

CHAIN OF CUSTODY RECORD

№ 1006

Client/Project Name	Project Location
CHITTENDEN BANK - FOTO HUT	77A WOODSTOCK, RUTLAND VT
Project No.	**Field Logbook No.**
1-2342-2 (044)	OMNIA
Sampler: (Signature)	**Chain of Custody Tape No.**
Jammy Fortier	JCO-604

Sample No./ Identification	Date	Time	Lab Sample Number	Type of Sample	8010-8020	8240	601/602	REMARKS
MWB-5	10/11/93	10:00		SOIL - TWO GLASS	✓			PID 250 PPM
MW1	10/12/93	2:05pm		WATER TWO 40ML		✓		
MW2	10/12/93	1:50pm		↓		✓		
MW3	10/12/93	2:35pm				✓		
MW4	10/12/93	1:00pm			✓			
MW5	10/12/93	2:45pm			✓			
MW7	10/12/93	1:40 pm			✓	✓		
MW8	10/12/93	2:55pm				✓		

Relinquished by: (Signature)	Date	Time	Received by: (Signature)	Date	Time
	10/14/93		Jammy Fortier	10-14-93	1:00 pm
Jammy Fortier	10-13-93	9:30am			
Relinquished by: (Signature)	Date	Time	Received for Laboratory: (Signature)	Date	Time
				10/14/93	12:30
Sample Disposal Method:	Disposed of by: (Signature)			Date	Time

SAMPLE COLLECTOR

5 State Street
Montpelier, VT 05602
(802) 229-4600
Fax (802) 229-5876

THE JOHNSON COMPANY, INC.
Environmental Sciences and Engineering

ANALYTICAL LABORATORY
IEA

RESULTS TO DON MAYNARD
JOHNSON CO.

INVOICE TO CHRIS BISHOP
CHITTENDEN BANK
2 BURLINGTON SQUARE - PO BOX 820
BURLINGTON, VT 05402

1974 3 8-

WHITE - To accompany sample to the lab and returned to the Johnson Co. YELLOW - Lab copy PINK - Transporter copy ORANGE - Sampler copy

CHAIN OF CUSTODY RECORD

№ 1007

Client/Project Name	Project Location
CHITTENDEN BANK-FOOTHILL	FIA Woodstock, Rutland, VT
Project No.	**Field Logbook No.**
1-0342-2 (044)	TMF-2
Sampler: (Signature)	**Chain of Custody Tape No.**
Jammy Fortin	JCO-604

ANALYSES: 601-602

Sample No./ Identification	Date	Time	Lab Sample Number	Type of Sample							REMARKS
MW3 DUP.	10/12/93	2:35pm			✓						
OB1	10/12/93	2:15pm			✓						
FIELD BLNK	10/12/93	1:10pm			✓						

Relinquished by: (Signature)	Date	Time	Received by: (Signature)	Date	Time
Jammy Fortin	10-13-93	9:30am			
Relinquished by: (Signature)	Date	Time	Received by: (Signature)	Date	Time
Relinquished by: (Signature)	Date	Time	Received for Laboratory: (Signature)	Date	Time
				10/14/93	12:30
Sample Disposal Method:	Disposed of by: (Signature)			Date	Time

SAMPLE COLLECTOR

5 State Street
Montpelier, VT 05602
(802) 229-4600
Fax: (802) 229-5876

THE JOHNSON COMPANY, INC.
Environmental Sciences and Engineering

ANALYTICAL LABORATORY

IEA

1974-3-84

WHITE - To accompany sample to the lab and returned to the Johnson Co. YELLOW - Lab copy PINK - Transporter copy ORANGE - Sampler copy

LABORATORY REPORT

CLIENT NAME: The Johnson Company
SITE LOCATION: Fotohut- Rutland, Vt.
LABORATORY NO: 2-1638
PROJECT NO: 78611
ATTENTION: Don Maynard

DATE OF SAMPLE: 9/21/92
DATE OF RECEIPT: 9/30/92
DATE OF ANALYSIS: 10/2/92
DATE OF REPORT: 10/22/92

PARAMETER	OB - 1
Chloromethane	< 50
Bromoform	< 50
Bromomethane	< 50
Dibromochloromethane	< 50
Vinyl Chloride	< 50
2-Chloroethylvinyl Ether	< 50
Chloroethane	< 50
Methylene Chloride	< 50
Dichloroethylene	< 50
Trichlorofluoromethane	< 50
1,1-Dichloroethene	< 50
1,1-Dichloroethane	< 50
cis-1,2-Dichloroethylene	268
Chloroform	< 50
1,2-Dichloroethane	< 50
1,1,1-Trichloroethane	< 50
Carbon Tetrachloride	< 50
Bromodichloromethane	< 50
1,2-Dichloropropane	< 50
t-1,3-Dichloropropene	< 50
c-1,3-Dichloropropene	< 50
1,1,2,2-Tetrachloroethane	< 50
1,1,2-Trichloroethane	< 50
Tetrachloroethylene	< 50
Benzene	< 50
Toluene	59
Ethylbenzene	144
Chlorobenzene	< 50
1,1-Dichlorobenzene	< 50
1,3-Dichlorobenzene	< 50
1,2-Dichlorobenzene	< 50
Xylenes Xylenes	1240
Surrogate % Recovery 601/602	102/112

EPA Method 601 & 602; All results reported as ug/l or ppb.

NOTE: Many late eluting aromatic hydrocarbons present.

RECEIVED
OCT 26 1992
THE JOHNSON CO., INC.
MONTPELIER, VERMONT

Respectfully Submitted,
SCITEST, INC.

Roderick J. Lamothe
Laboratory Director

RJL/rcg

SCITEST
LABORATORY SERVICES

Nº 865

CHAIN OF CUSTODY RECORD

Client/Project Name	Project Location
Ch. Henden Bank - Foto Hut	Rutland, Vermont
Project No.	**Field Logbook No.**
1-0342-1	TMJ-2
Sampler: (Signature)	**Chain of Custody Tape No.**
Tammy Fortier	JCO 947

Sample No./ Identification	Date	Time	Lab Sample Number	Type of Sample	ANALYSES: 601,602	REMARKS
OB-1	9-21-92		2-1638	water		

RECEIVED EPA OCT 1992

Relinquished by: (Signature)	Date	Time	Received by: (Signature)	Date	Time
Tammy Fortier	9-30-92	8:15am			
Relinquished by: (Signature)	Date	Time	Received by: (Signature)	Date	Time
Relinquished by: (Signature)	Date	Time	Received for Laboratory: (Signature)	Date	Time
			Jim Morin	9/30/92	10:20 pm
Sample Disposal Method:			Disposed of by: (Signature)	Date	Time

SAMPLE COLLECTOR

5 State Street
Montpelier, VT 05602
(802) 229-4600
Fax: (802) 229-5876

THE JOHNSON COMPANY, INC.
Environmental Sciences and Engineering

ANALYTICAL LABORATORY

Sc. test
transported via VT Transit

SCITEST
LABORATORY SERVICES

P.O. Box 339
Randolph, Vermont 05060-0339
(802) 728-6313

78611
March 11, 1992

Mike Pottinger
The Johnson Company
5 State Street
Montpelier, VT 05602

RE: Fotohut Free Product Analysis Sample # 2-0367

Dear Mike:

I have attached copies of the hydrocarbon fingerprint for Tanks #2 & 3 solvents which we received on 3/6/92. Verbal results were given on 3/9/92.

All of the standards and samples were analyzed at a 1% dilution in Dichloromethane. The patterns for both tanks are quite similar, however, neither matched the patterns for the 3 petroleum products (gasoline, kerosene, diesel). The tank solvents have peaks in common with the latter portion of the gasoline chromatograph and the earlier portion of the kerosene chromatograph.

To further categorize the solvents an EPA Method 8240 analysis for purgeable organics was performed. Results showed the unknown solvent to be a mixture of Toluene, Xylenes, Ethylbenzene, and Tetrachloroethylene with other (higher boiling) compounds such as C_9H_{12} and $C_{10}H_{12}$ present in the mixture.

I hope with these combined analyses, you have sufficient information to categorize these unknown organic mixtures. Please call me if you have any further questions.

Sincerely,

Robert J. Shipman
Organic Chemist
RJS/cha

LABORATORY REPORT

CLIENT NAME:	The Johnson Company	LABORATORY NO.:	2-0367
ADDRESS:	5 State Street	PROJECT NO.:	78611
	Montpelier, VT 05602	DATE OF SAMPLE:	3/6/92
SITE LOCATION:	Fotohut, Rutland, VT	DATE OF ANALYSIS:	3/8/92
ATTENTION:	Mike Pottinger	DATE OF REPORT:	3/11/92

VOLATILE ORGANIC DATA FOR WASTE SOLVENT DILUTIONS
RESULTS IN PPM (volume/volume)
QUALITY CONTROL DATA

PARAMETER	Sample 4 Tank #2	Sample 5 Tank #3	PRACTICAL QUANTITATION LIMIT
Chloromethane	BPQL	BPQL	2500
Bromomethane	BPQL	BPQL	2500
Vinyl Chloride	BPQL	BPQL	2500
Chloroethane	BPQL	BPQL	2500
Methylene Chloride	BPQL	BPQL	2500
Acetone	BPQL	BPQL	2500
Trichlorofluoromethane	BPQL	BPQL	1250
Carbon Disulfide	BPQL	BPQL	1250
1,1-Dichloroethene	BPQL	BPQL	1250
1,1-Dichloroethane	BPQL	BPQL	1250
1,2-Dichloroethene(Total)	BPQL	BPQL	1250
Chloroform	BPQL	BPQL	1250
1,2-Dichloroethane	BPQL	BPQL	1250
2-Butanone (MEK)	BPQL	BPQL	5000
1,1,1-Trichloroethane	BPQL	BPQL	1250
Carbon Tetrachloride	BPQL	BPQL	1250
Vinyl Acetate	BPQL	BPQL	5000
Bromodichloromethane	BPQL	BPQL	1250
1,2-Dichloropropane	BPQL	BPQL	1250
c-1,3-Dichloropropene	BPQL	BPQL	1250
Trichloroethene	BPQL	BPQL	1250
Dibromochloromethane	BPQL	BPQL	1250
1,1,2-Trichloroethane	BPQL	BPQL	1250
Benzene	BPQL	BPQL	1250
t 1,3-Dichloropropene	BPQL	BPQL	1250
2 Chloroethylvinylether	BPQL	BPQL	1250
Bromoform	BPQL	BPQL	1250
4-Methyl-2-Pentanone (MIBK)	BPQL	BPQL	5000
2 Hexanone	BPQL	BPQL	5000
Tetrachloroethene	1030	848	1250
1,1,2,2-Tetrachloroethane	BPQL	BPQL	1250
Toluene	643	570	1250
Chlorobenzene	BPQL	BPQL	1250
Ethylbenzene	985	908	1250
Styrene	BPQL	BPQL	2000
m Xylene	2290	2280	2000
o,p-Xylene	2810	2530	2000
1,3-Dichlorobenzene	BPQL	BPQL	2000
1,2-Dichlorobenzene	BPQL	BPQL	2000
1,4-Dichlorobenzene	BPQL	BPQL	2000

EPA Method 8240, SW 846, 3RD ED., Nov 1986
BPQL = Below Practical Quantitation Limit.
Note: All compounds found were in the range of the EPA Method 8240 PQL level but above our Method Detection Limits.

SCITEST LABORATORY SERVICES

Amitz Solv. #5

CHANNEL A INJECT 03/08/92 10:15:39



Limit of Solid 4 10%

NEL A INJECT :03/08/92 11:25:36



SCITEST
LABORATORY SERVICES

P.O. Box 339
Randolph, Vermont 05060-0339
(802) 728-6313

August 31, 1993
78611

Don Maynard
The Johnson Co
5 State Street
Montpelier VT 05060

Subject: Sample Nos 2-0367

Dear Don,

As you requested, we are supplying copies of the chromatograms that we obtained during the analysis of these samples for volatile organics.

Please call me if there are any questions.

Sincerely,

Roderick Lamothe
SCITEST INC.

TOTAL ION CHROMATOGRAM



Data File: >R00001::DA Quant Output File: >R00001::QT
Name: 2-0367 SOIL#1 3/6/92
Misc: JLO- FOTOHUT MEOH EXT

Id File: 30_OCT92::SD
Title: 5 Point Calibration FOR 8240 & 624
Last Calibration: 920706 14:24

Operator ID: RS
Quant Time: 920706 22:56
Injected at: 920706 23:22

TOTAL ION CHROMATOGRAM



Data File: >R0924::02   Quant Output File: ^R0924::QT
Name: 2-0367 SOLV#4 3/9/92
Misc: JCO-FOTOHUT, 0.1/10ML,.002/5ML

Id File: ID_CL9::SC
Title: 5 Point Calibration FOR 8240 & 624
Last Calibration: 920304 14:24

Operator ID: RS
Quant Time: 920309 14:15
Injected at: 920309 13:25

(1) 105 91 77 65 39 ions
C_9H_{12}
75 → 46%. match

(2) 105, 57, 43, 85, 71, 120 ions
C_9H_{12}
47 → 35%

(4) 105, 120, + several small ions
63% C_9H_{12}

0.1 → 10ml MeOH 100
.002 → 5ml 2500] x 250,000 for ppb
250 for ppm

TOTAL ION CHROMATOGRAM

File >R0823 35.0-650.0 amu. 2-0367 SOLV#5 3/9/92JCU-FOTOHUT. 0.1/10M



Data File: >R0823::R2 Quant Output File: >R0823::QT

Method: 2-0367 SOLV#5 3/9/92

Text: JCU-FOTOHUT. 0.1/10ML, 002/SPL

Cal File: ID_CL3::SC

Title: 5 Point Calibration FOR 8240 & 624

Last Calibration: 920304 14:24

Operator ID: RS

Run Time: 920410 12:46

Started at: 920410 11:51

(1) Same chart for March + March w/ Solv. #4.

(2) 55, 83, 92, 53, 41 ppb

67% $C_{10}H_{22}$

TOTAL ION CHROMATOGRAM :



Data File: R0803::D2 Quant Output File: *R0803::QT
Name: 2-0367 SOIL#2 3/6/92
Misc: JCO- FOTOHOT MEOH EXT

IS File: IS_510::DS
Title: 5 Point Calibration 500 8240 & 624
Last Calibration: 920706 14:24

Operator ID: RS
Quant Time: 920730: 22:17
Injected at: 920730: 21:57

TOTAL ION CHROMATOGRAM



Data File: 980804::02 Quant Output File: 980804::QT
Name: 2-0367 BLK 3/6/92
Text: JCO- FOTOHUT MEOH EXT

ID File: ID_CLQ::SC
Title: 5 Point Calibration FOR 8240 & 624
Last Calibration: 920306 14:24

Operator ID: BS
Count Time: 920706 22:02
Injected at: 920706 22:17

ION CHROMATOGRAM



Data File: R0805::02 Quant Output File: R0205::QT
Name: 2-0347 SOIL#3 3/6/92
Misc: FOTOHUT MECH EXT

ID File: ID_CLP::SC
Title: 5 Point Calibration FOR 8240 & 624
Last Calibration: 920706 14:14

Operator ID: PS
Quant Time: 920706 23:37
Injected at: 920706 22:56



Data File: B90814::02 Quant Output File: B90814::QT
Name: 2-0347 SOLVW4 3/8/92JCO-FOTOHOT MEOH DIL
Misc: 200-FOTOHOT MEOH DIL

ID File: ID_CLQ::CC
Title: 5 Point Calibration FOR 8240 & 624
Last Calibration: 920306 14:24

Operator ID: PS
Quant Time: 920309 14:39
Injected at: 920309 15:54

TOTAL ION CHROMATOGRAM

File JR0816 35.0-260.0 amu. 8-0067 SOLVNS 8/8/92JCO-FOTONUT N2OR DIL

TIC



Data File: JR0816:02 Quant Output File: JR0816::QT

Method: 8-0067 SOLVNS 8/8/92

Title: JCO-FOTONUT N2OR DIL

Data File: JD_CL0::5C

Title: 5 Point Calibration FOR 8240 & 624

Last Calibration: 8/20/92 14:31

Operator ID: RS

Last Time: 8/20/92 17:42

Injected at: 8/8/92 17:12

carry over to
Same sample next run

TOTAL ION CHROMATOGRAM :



Data File: >RC802::02 Quant Output File: 'RC802::QT
Name: 2-0367 BLK 3/6/92
Misc: JEO- FOTONUT NEON EXT

Id File: ID_CLC::IC
Title: 5 Point Calibration FID 3240 & 624
Last Calibration: 920306 14:24

Operator ID: BS
Quant Time: 920306 21:59
Injected at: 920306 21:00

Slight Xylene after Run #5 See BLK — NP Xylene carryover — only junk

CLIENT NAME:	The JORNSON Company	LABORATORY NO.:	[illegible]
ADDRESS:	5 State Street	PROJECT NO.:	78611
	Montpelier, VT 05602	DATE OF SAMPLE:	1/15/92
SITE LOCATION:	Fotohut, Rutland, VT	DATE OF ANALYSIS:	1/29/92
ATTENTION:	Mike Pottinger	DATE OF REPORT:	2/14/92

VOLATILE ORGANIC DATA FOR WATER SAMPLE
RESULTS IN MICROGRAMS/LITER (ppb)

PARAMETER	Groundwater Tank #1	PRACTICAL QUANTITATION LIMIT
Chloromethane	BPQL	600
Bromomethane	BPQL	300
Vinyl Chloride	BPQL	300
Chloroethane	BPQL	300
Methylene Chloride	BPQL	300
Acetone	BPQL	600
Trichlorofluoromethane	BPQL	300
Carbon Disulfide	BPQL	300
1,1-Dichloroethene *	BPQL	300
1,1-Dichloroethane	BPQL	300
1,2-Dichloroethene (Total)	BPQL	300
Chloroform	BPQL	150
1,2-Dichloroethane	BPQL	150
2-Butanone (MEK)	BPQL	600
1,1,1-Trichloroethane	BPQL	150
Carbon Tetrachloride	BPQL	300
Vinyl Acetate	BPQL	600
Bromodichloromethane	BPQL	150
1,2-Dichloropropane	BPQL	150
c-1,3-Dichloropropene	BPQL	150
Trichloroethene *	BPQL	150
Dibromochloromethane	BPQL	150
1,1,2-Trichloroethane	BPQL	150
Benzene *	BPQL	150
t-1,3-Dichloropropene	BPQL	150
2-Chloroethylvinylether	BPQL	300
Bromoform	BPQL	300
4-Methyl-2-Pentanone (MIBK)	BPQL	600
2-Hexanone	BPQL	600
Tetrachloroethene	BPQL	150
1,1,2,2-Tetrachloroethane	BPQL	150
Toluene *	BPQL	150
Chlorobenzene *	BPQL	150
Ethylbenzene	BPQL	150
Styrene	BPQL	300
m-Xylene	686 31,256	300
o,p-Xylene	570	300
1,3-Dichlorobenzene	BPQL	300
1,2-Dichlorobenzene	BPQL	300
1,4-Dichlorobenzene	BPQL	300

EPA Method 8240, SW 846, 3rd Ed., Nov 1986. * = CLP Spike Compound (5 total)
BPQL = Below Practical Quantitation Limits.

SCITEST
LABORATORY SERVICES

LABORATORY REPORT

CLIENT NAME: Chittenden Bank
SAMPLE LOCATION: Fotohut, Rutland VT
LABORATORY NUMBER: 1118-90
PROJECT NUMBER: 89721

DATE OF SAMPLE: 08-15-90
DATE OF RECEIPT: 08-15-90
DATE ANALYZED: 08-24-90

PARAMETER	Solvent H	Solvent I	Soil F	Soil C
Chloromethane	<240000	<50000	<5	<3
Bromoform	<240000	<50000	<5	<3
Bromomethane	<240000	<50000	<5	<3
Dibromochloromethane	<240000	<50000	<5	<3
Vinyl Chloride	<240000	<50000	<5	<3
2-Chloroethylvinyl Ether	<240000	<50000	<5	<3
Chloroethane	<240000	<50000	<5	<3
Methylene Chloride	<240000	<50000	<5	<3
Trichloroethylene	<240000	<50000	<5	<3
Trichlorofluoromethane	<240000	<50000	<5	<3
1,1-Dichloroethene	<240000	<50000	<5	<3
1,1-Dichloroethane	<240000	<50000	<5	<3
cis or trans-1,2-Dichloroethylene	<240000	<50000	<5	<3
Chloroform	<240000	<50000	<5	<3
1,2-Dichloroethane	<240000	<50000	<5	<3
1,1,1-Trichloroethane	<240000	<50000	<5	<3
Carbon Tetrachloride	<240000	<50000	<5	<3
Bromodichloromethane	<240000	<50000	<5	<3
1,2-Dichloropropane	<240000	<50000	<5	<3
trans-1,3-Dichloropropene	<240000	<50000	<5	<3
cis-1,3-Dichloropropene	<240000	<50000	<5	<3
1,1,2,2-Tetrachloroethane	<240000	<50000	<5	<3
1,1,2-Trichloroethane	<240000	<50000	<5	<3
Tetrachloroethylene - dry cleaning solvent	137000	<50000	238	<3
Benzene	<240000	<50000	<5	<3
Toluene	Int. interference	Int	Int	<3
Ethylbenzene	Int	Int	Int	<3
Chlorobenzene	<240000	<50000	<5	<3
1,4-Dichlorobenzene	<240000	<50000	<5	<3
1,3-Dichlorobenzene	<240000	<50000	<5	<3
1,2-Dichlorobenzene	<240000	<50000	<5	<3
Xylenes	Int	Int	Int	<3
8020 - Miscellaneous double bonded Hydrocarbons as Xylenes	>28%	>15.6%	>143000	<3

EPA Method 8010 & 8020; All results reported as ug/kg or ppb. parts per billion
Toluene, Ethylbenzene and Xylenes were not quantitated due to interference peaks from the sample matrix.

Another peak with relatively high boiling point

Respectfully submitted,

SCITEST, INC.

Frederick J. Lamothe
Laboratory Director

RJL/trs

SCITEST

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-029-01
Project:	1-0342-2-FOTOHUT	Sample:	MW-1S
Report Date:	10/19/93	Type:	Soil
Collected:	09/30/93	Container:	Glass
Received:	10/05/93		
Analyzed:	10/07/93	Dilution	
By:	GMT	Factor:	1

Purgable Halocarbons

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt.)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 2 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-029-01
Project:	1-0342-2-FOTOHUT	Sample:	MW-1S

Purgable Aromatics

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt
30	Benzene	1	BQL
31	Ethylbenzene	1	BQL
32	Toluene	1	BQL
33	Xylenes	1	2
34	Methyl-t-butylether	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	87 %
1,4-Difluorobenzene	80 %

Comment:

BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.

FORM MA8010/2(S) Rev. 082692

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-029-02
Project:	1-0342-2-FOTOHUT	Sample:	MW-3
Report Date:	10/19/93	Type:	Soil
Collected:	09/30/93	Container:	Glass
Received:	10/05/93		
Analyzed:	10/07/93	Dilution	
By:	GMT	Factor:	2.1

Purgable Halocarbons

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt.)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 2 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-029-02
Project:	1-0342-2-FOTOHUT	Sample:	MW-3

Purgable Aromatics

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt
30	Benzene	1	BQL
31	Ethylbenzene	1	18
32	Toluene	1	BQL
33	Xylenes	1	29
34	Methyl-t-butylether	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	103 %
1,4-Difluorobenzene	92 %

Comment:
BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
Smaller amount of sample analyzed due to the high concentration of target compounds present.
Smaller amount of sample analyzed due to the presence of non-target compounds.

FORM MA8010/2(S) Rev. 082692

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-029-03
Project:	1-0342-2-FOTOHUT	Sample:	MW-4
Report Date:	10/19/93	Type:	Soil
Collected:	10/01/93	Container:	Glass
Received:	10/05/93		
Analyzed:	10/11/93	Dilution	
By:	GMT	Factor:	1.1

Purgable Halocarbons

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt.)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 2 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-029-03
Project:	1-0342-2-FOTOHUT	Sample:	MW-4

Purgable Aromatics

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt
30	Benzene	1	BQL
31	Ethylbenzene	1	BQL
32	Toluene	1	BQL
33	Xylenes	1	1
34	Methyl-t-butylether	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	84 %
1,4-Difluorobenzene	87 %

Comment:

BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.

FORM MA8010/2(S) Rev. 082692

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-029-04
Project:	1-0342-2-FOTOHUT	Sample:	MW-5
Report Date:	10/19/93	Type:	Soil
Collected:	10/01/93	Container:	Glass
Received:	10/05/93		
Analyzed:	10/07/93	Dilution	
By:	GMT	Factor:	56

Purgable Halocarbons

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt.)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 2 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-029-04
Project:	1-0342-2-FOTOHUT	Sample:	MW-5

Purgable Aromatics

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt
30	Benzene	1	BQL
31	Ethylbenzene	1	560
32	Toluene	1	67
33	Xylenes	1	3,200 ppb
34	Methyl-t-butylether	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	47 %
1,4-Difluorobenzene	43 %

Comment:
BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
Smaller amount of sample analyzed due to the high concentration of target compounds present.
Quantitation limit elevated due to smaller amount of sample analyzed.

FORM MA8010/2(S) Rev. 082692

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-029-05
Project:	1-0342-2-FOTOHUT	Sample:	MW-6
Report Date:	10/19/93	Type:	Soil
Collected:	10/01/93	Container:	Glass
Received:	10/05/93		
Analyzed:	10/07/93	Dilution	
By:	GMT	Factor:	66

Purgable Halocarbons

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt.)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 2 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-029-05
Project:	1-0342-2-FOTOHUT	Sample:	MW-6

Purgable Aromatics

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt
30	Benzene	1	BQL
31	Ethylbenzene	1	930
32	Toluene	1	BQL
33	Xylenes	1	7,200
34	Methyl-t-butylether	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	65 %
1,4-Difluorobenzene	68 %

Comment:
BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
Smaller amount of sample analyzed due to the high concentration of target compounds present.
Quantitation limit elevated due to smaller amount of sample analyzed.

FORM MA8010/2(S) Rev. 082692

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-029-06
Project:	1-0342-2-FOTOHUT	Sample:	MW-7
Report Date:	10/19/93	Type:	Soil
Collected:	10/01/93	Container:	Glass
Received:	10/05/93		
Analyzed:	10/07/93	Dilution	
By:	GMT	Factor:	1

Purgable Halocarbons

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt.)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 2 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-029-06
Project:	1-0342-2-FOTOHUT	Sample:	MW-7

Purgable Aromatics

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt
30	Benzene	1	BQL
31	Ethylbenzene	1	BQL
32	Toluene	1	BQL
33	Xylenes	1	BQL
34	Methyl-t-butylether	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	78 %
1,4-Difluorobenzene	87 %

Comment:

BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.

FORM MA8010/2(S) Rev. 082692

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 1 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-031-01
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW8-5
Report Date:	10/28/93	Type:	Soil
Collected:	10/11/93	Container:	Glass
Received:	10/14/93		
Analyzed:	10/25/93	Dilution	
By:	GMT	Factor:	270

Purgable Halocarbons

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt.)
1	Bromodichloromethane	1	BQL
2	Bromoform	1	BQL
3	Bromomethane	1	BQL
4	Carbon tetrachloride	1	BQL
5	Chlorobenzene	1	BQL
6	Chloroethane	1	BQL
7	2-Chloroethylvinyl ether	1	BQL
8	Chloroform	1	BQL
9	Chloromethane	1	BQL
10	Dibromochloromethane	1	BQL
11	1,2-Dichlorobenzene	1	BQL
12	1,3-Dichlorobenzene	1	BQL
13	1,4-Dichlorobenzene	1	BQL
14	Dichlorodifluoromethane	1	BQL
15	1,1-Dichloroethane	1	BQL
16	1,2-Dichloroethane	1	BQL
17	1,1-Dichloroethene	1	BQL
18	trans-1,2-Dichloroethene	1	BQL
19	1,2-Dichloropropane	1	BQL
20	cis-1,3-Dichloropropene	1	BQL
21	trans-1,3-Dichloropropene	1	BQL
22	Methylene chloride	1	BQL
23	1,1,2,2-Tetrachloroethane	1	BQL
24	Tetrachloroethene	1	BQL
25	1,1,1-Trichloroethane	1	BQL
26	1,1,2-Trichloroethane	1	BQL
27	Trichloroethene	1	BQL
28	Trichlorofluoromethane	1	BQL
29	Vinyl chloride	1	BQL

IEA
An Aquarion Company

Analysis Report: EPA Methods 8010/8020
(PAGE 2 OF 2 PAGES)

Client:	Johnson Company	IEA ID:	J104-031-01
Project:	1-0342-2(044), 77A Woodstock	Sample:	MW8-5

Purgable Aromatics

Number	Compound	PQL (ug/kg dry wt.)	Result (ug/kg dry wt
30	Benzene	1	BQL
31	Ethylbenzene	1	3,800
32	Toluene	1	270
33	Xylenes	1	39,000
34	Methyl-t-butylether	1	BQL

Surrogate Standard Recovery:

1,4-Dichlorobutane	95 %
1,4-Difluorobenzene	100 %

Comment:

BQL = Below Quantitation Limit
PQL = Practical Quantitation Limit
Quantitation limits for this sample are obtained by multiplying the PQL by the dilution factor.
Smaller amount of sample analyzed due to the high concentration of target compounds present.
Quantitation limit elevated due to smaller amount of sample analyzed.

CHAIN OF CUSTODY RECORD

№ 1104

Client/Project Name	Project Location
I-0342-2-FOTOHUT	RUTLAND, VT
Project No.	**Field Logbook No.**
I-0342-2	DM 8A
Sampler: (Signature)	**Chain of Custody Tape No.**
	1032

ANALYSES: 8010-8020

Sample No./ Identification	Date	Time	Lab Sample Number	Type of Sample	REMARKS
MW15	9/30	10:30		TWO GLASS SOIL	PID 20 PPM
MW3	9/30	14:45		TWO GLASS SOIL	PID 115 PPM
MW4	10/1	12:05		TWO GLASS SOIL	PID 7 PPM - BACKGROUND need lowdetect.
MW5	10/1	12:30		TWO GLASS SOIL	PID 190 PPM
MW6	10/1	14:10		" "	PID 250 PPM
MW7	10/1	15:40		" "	PID-0.7 PPM need LOW DETECT LIMITS

SAVE FOR ADDITIONAL ANALYSIS IF NECESSARY

Relinquished by: (Signature)	Date	Time	Received by: (Signature)	Date	Time
	10/1/93	14:30			
Relinquished by: (Signature)	Date	Time	Received by: (Signature)	Date	Time
				10/5/93	16:00
Relinquished by: (Signature)	Date	Time	Received for Laboratory: (Signature)	Date	Time
				10/5/93	16:00
Sample Disposal Method:	Disposed of by: (Signature)			Date	Time

SAMPLE COLLECTOR

5 State Street
Montpelier, VT 05602
(802) 229-4600
Fax: (802) 229-5876

THE JOHNSON COMPANY, INC.
Environmental Sciences and Engineering

ANALYTICAL LABORATORY IEA N. BILLERICA, MASS

RESULTS TO DM Maynard - JOHNSON CO.

INVOICE TO CHRIS BISHOP
CHITTENDEN BANK
2 BURLINGTON SQUARE PO BOX 820
BURLINGTON, VT 05402

1974-3-84

WHITE - To accompany sample to the lab and returned to the Johnson Co. YELLOW - Lab copy PINK - Transporter copy ORANGE - Sampler copy

CLIENT NAME:	The JOHNSON Company	LABORATORY NO.:	2-0367
ADDRESS:	5 State Street	PROJECT NO.:	78611
	Montpelier, VT 05602	DATE OF SAMPLE:	3/5-6/92
SITE LOCATION:	Fotohut, Rutland, VT	DATE OF ANALYSIS:	3/6/92
ATTENTION:	Mike Pottinger	DATE OF REPORT:	3/11/92

VOLATILE ORGANIC DATA FOR SOIL SAMPLES
RESULTS IN MICROGRAMS/KILOGRAM (ppb) wet weight

PARAMETER	Soil #1 SP 3-5' SPOIL PILE	Soil #2 T1 W7' TANK PIT	Soil #3 T1 W9' TANK PIT	Dup #1 SP 3-5'	%RD	PRACTICAL QUANTITATION LIMIT
Chloromethane	BPQL	BPQL 7'6"	BPQL 9'6"	BPQL	---	3000
Bromomethane	BPQL	BPQL	BPQL	BPQL	---	3000
Vinyl Chloride	BPQL	BPQL	BPQL	BPQL	---	3000
Chloroethane	BPQL	BPQL	BPQL	BPQL	---	3000
Methylene Chloride	BPQL	BPQL	BPQL	BPQL	---	3000
Acetone	BPQL	BPQL	BPQL	BPQL	---	6000
Trichlorofluoromethane	BPQL	BPQL	BPQL	BPQL	---	3000
Carbon Disulfide	BPQL	BPQL	BPQL	BPQL	---	3000
1,1-Dichloroethene	BPQL	BPQL	BPQL	BPQL	---	1500
1,1-Dichloroethane	BPQL	BPQL	BPQL	BPQL	---	1500
1,2-Dichloroethene (Total)	BPQL	BPQL	BPQL	BPQL	---	1500
Chloroform	BPQL	BPQL	BPQL	BPQL	---	1500
1,2-Dichloroethane	BPQL	BPQL	BPQL	BPQL	---	1500
2-Butanone (MEK)	BPQL	BPQL	BPQL	BPQL	---	6000
1,1,1-Trichloroethane	BPQL	BPQL	BPQL	BPQL	---	1500
Carbon Tetrachloride	BPQL	BPQL	BPQL	BPQL	---	1500
Vinyl Acetate	BPQL	BPQL	BPQL	BPQL	---	6000
Bromodichloromethane	BPQL	BPQL	BPQL	BPQL	---	1500
1,2-Dichloropropane	BPQL	BPQL	BPQL	BPQL	---	1500
cis-1,3-Dichloropropene	BPQL	BPQL	BPQL	BPQL	---	1500
Trichloroethene	BPQL	BPQL	BPQL	BPQL	---	1500
Dibromochloromethane	BPQL	BPQL	BPQL	BPQL	---	1500
1,1,2-Trichloroethane	BPQL	BPQL	BPQL	BPQL	---	1500
Benzene	BPQL	BPQL	BPQL	BPQL	---	1500
trans-1,3-Dichloropropene	BPQL	BPQL	BPQL	BPQL	---	1500
2-Chloroethylvinylether	BPQL	BPQL	BPQL	BPQL	---	3000
Bromoform	BPQL	BPQL	BPQL	BPQL	---	3000
4-Methyl-2-Pentanone (MIBK)	BPQL	BPQL	BPQL	BPQL	---	6000
2-Hexanone	BPQL	BPQL	BPQL	BPQL	---	6000
Tetrachloroethene	6820	BPQL	BPQL	7720	8.8%	1500
1,1,2,2-Tetrachloroethane	BPQL	BPQL	BPQL	BPQL	---	1500
Toluene	3490	BPQL	BPQL	4160	12.4%	1500
Chlorobenzene	BPQL	BPQL	BPQL	BPQL	---	1500
Ethylbenzene	3780	1569	1850	8340	0.5%	1500
Styrene	BPQL	BPQL	BPQL	BPQL	---	3000
m-Xylene	23,000	3360	6540	26,800	10.8%	3000
o-Xylene	35,500	4300	4300	32,100	7.1%	3000
1,3-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	---	3000
1,2-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	---	3000
1,4-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	---	3000
		Note 1				

EPA Method 8240, SW846, 3RD ED., Nov 1986 by Methanol Extraction.
BPQL = Below Practical Quantitation Limit.
Note 1: A trace of Tetrachloroethylene detected at an approximate concentration of 330 ppb.

SCITEST LABORATORY SERVICES

L: NT NAME:	The JOHNSON Company	LABORATORY NO.:	2-0089
DDRESS:	5 State Street Montpelier, VT 05602	PROJECT NO.:	78611
		DATE OF SAMPLE:	1/15/92
I: LOCATION:	Fotohut, Rutland, VT	DATE OF ANALYSIS:	1/29/92
T NTION:	Mike Pottinger	DATE OF REPORT:	2/14/92

418.1 SOIL RESULTS

(Expressed as milligrams/kilogram [mg/kg] except as noted)

Location	Concentration	PRACTICAL QUANTITATION LIMIT
SS-1 0-12"	1,000	30
SS-1 2-3"	13,000	30
SS-2 0-12"	860	30
SS-2 1.2-2.2"	580	30
SS-3 0-11"	1,500	30
SS-3 11-22"	BPQL	30

E \ Method 418.1, SW-846, 3rd Ed., Nov 1986.
BPQL = Below Practical Quantitation Limits.

Respectfully submitted

SCITEST, INC.

Roderick Lamothe

Roderick J. Lamothe
Laboratory Director

F L/cha

SCITEST
LABORATORY SERVICES

ADDRESS:	5 State Street Montpelier, VT 05602	PROJECT NO.:	78611
SITE LOCATION:	Fotohut, Rutland, VT	DATE OF SAMPLE:	1/15/92
ATTENTION:	Mike Pottinger	DATE OF ANALYSIS:	1/29/92
		DATE OF REPORT:	2/14/92

VOLATILE ORGANIC DATA FOR SOIL SAMPLES
RESULTS IN MICROGRAMS/KILOGRAM (ppb)

PARAMETER	SS 1 0-12"	PRACTICAL QUANTITATION LIMIT
Chloromethane	BPQL	80
Bromomethane	BPQL	40
Vinyl Chloride	BPQL	40
Chloroethane	BPQL	40
Methylene Chloride	BPQL	40
Acetone	BPQL	80
Trichlorofluoromethane	BPQL	40
Carbon Disulfide	BPQL	40
1,1-Dichloroethene	BPQL	40
1,1-Dichloroethane	BPQL	40
1,2-Dichloroethene (Total)	BPQL	40
Chloroform	BPQL	20
1,2-Dichloroethane	BPQL	20
2-Butanone (MEK)	BPQL	80
1,1,1-Trichloroethane	BPQL	20
Carbon Tetrachloride	BPQL	40
Vinyl Acetate	BPQL	80
Bromodichloromethane	BPQL	20
1,2-Dichloropropane	BPQL	20
cis-1,3-Dichloropropene	BPQL	20
Trichloroethene	BPQL	20
Dibromochloromethane	BPQL	20
1,1,2-Trichloroethane	BPQL	20
Benzene	BPQL	20
trans-1,3-Dichloropropene	BPQL	20
2-Chloroethylvinylether	BPQL	40
Bromoform	BPQL	40
4-Methyl-2-Pentanone (MIBK)	BPQL	80
2-Hexanone	BPQL	80
Tetrachloroethene	423	20
1,1,2,2-Tetrachloroethane	BPQL	20
Toluene	48	20
Chlorobenzene	BPQL	20
Ethylbenzene	BPQL	20
Styrene	BPQL	40
m-Xylene	BPQL	40
o,p-Xylene	BPQL	40
1,3-Dichlorobenzene	BPQL	40
1,2-Dichlorobenzene	BPQL	40
1,4-Dichlorobenzene	BPQL	40

EPA Method 8240, SW846, 3RD ED., Nov 1986 BPQL = Below Practical Quantitation Limit.
Note: Late eluting hydrocarbons including the chemical formulas $C_{8}H_{12}$, $C_{9}H_{16}$, & $C_{10}H_{20}$.

KoL/cha

SCITEST
LABORATORY SERVICES

CLIENT NAME:	The JOHNSON Company	LABORATORY NO.:	2-0089
DDRESS:	5 State Street	PROJECT NO.:	78611
	Montpelier, VT 05602	DATE OF SAMPLE:	1/15/92
SITE LOCATION:	Fotohut, Rutland, VT	DATE OF ANALYSIS:	1/29/92
ATTENTION:	Mike Pottinger	DATE OF REPORT:	2/14/92

VOLATILE ORGANIC DATA FOR SOIL SAMPLES
RESULTS IN MICROGRAMS/KILOGRAM (ppb)

ARAMETER	SS 1 2-3"	SS 2 0-12"	SS 2 1.1-2.2"	SS 3 0-11	SS 3 11-12"	Spike SS 2 0-12"	PRACTICAL QUANTITATIO LIMIT
Chloromethane	BPQL	BPQL	BPQL	BPQL	BPQL	---	<4000
romomethane	BPQL	BPQL	BPQL	BPQL	BPQL	---	<2000
inyl Chloride	BPQL	BPQL	BPQL	BPQL	BPQL	---	<2000
Chloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	---	<2000
Methylene Chloride	BPQL	BPQL	BPQL	BPQL	BPQL	93%	<2000
cetone	BPQL	BPQL	BPQL	BPQL	BPQL	---	<4000
richlorofluoromethane	BPQL	BPQL	BPQL	BPQL	BPQL	---	<2000
Carbon Disulfide	BPQL	BPQL	BPQL	BPQL	BPQL	---	<2000
,1-Dichloroethene	BPQL	BPQL	BPQL	BPQL	BPQL	105%	<2000
,1-Dichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	82%	<2000
1,2-Dichloroethene (Total)	BPQL	BPQL	BPQL	BPQL	BPQL	111%	<2000
hloroform	BPQL	BPQL	BPQL	BPQL	BPQL	---	<1000
,2-Dichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	86%	<1000
2-Butanone (MEK)	BPQL	BPQL	BPQL	BPQL	BPQL	---	<4000
1,1,1-Trichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	101%	<1000
arbon Tetrachloride	BPQL	BPQL	BPQL	BPQL	BPQL	90%	<2000
inyl Acetate	BPQL	BPQL	BPQL	BPQL	BPQL	---	<4000
Bromodichloromethane	BPQL	BPQL	BPQL	BPQL	BPQL	---	<1000
,2-Dichloropropane	BPQL	BPQL	BPQL	BPQL	BPQL	82%	<1000
-1,3-Dichloropropene	BPQL	BPQL	BPQL	BPQL	BPQL	---	<1000
Trichloroethene	BPQL	BPQL	BPQL	BPQL	BPQL	100%	<1000
ibromochloromethane	BPQL	BPQL	BPQL	BPQL	BPQL	---	<1000
,1,2-Trichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	81%	<1000
Benzene	BPQL	BPQL	BPQL	BPQL	BPQL	87%	<1000
t-1,3-Dichloropropene	BPQL	BPQL	BPQL	BPQL	BPQL	---	<1000
-Chloroethylvinylether	BPQL	BPQL	BPQL	BPQL	BPQL	---	<2000
romoform	BPQL	BPQL	BPQL	BPQL	BPQL	---	<2000
4-Methyl-2-Pentanone (MIBK)	BPQL	BPQL	BPQL	BPQL	BPQL	---	<4000
-Hexanone	BPQL	BPQL	BPQL	BPQL	BPQL	---	<4000
etrachloroethene	3550	BPQL	BPQL	BPQL	BPQL	102%	<1000
1,1,2,2-Tetrachloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	61%	<1000
oluene	1500	BPQL	BPQL	BPQL	BPQL	95%	<1000
lorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	87%	<1000
thylbenzene	5160	BPQL	BPQL	BPQL	BPQL	109%	<1000
Styrene	BPQL	BPQL	BPQL	BPQL	BPQL	---	<2000
-Xylene	24700	BPQL	BPQL	BPQL	BPQL	140%	<2000
,p-Xylene	27900	BPQL	BPQL	BPQL	BPQL	100%	<2000
1,3-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	---	<2000
,2-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	---	<2000
,4-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	---	<2000
	Note 1		Note 2			Note 3	

PA Method 8240, SW 846, 3rd Ed., Nov 1986.
BPQL = Below Practical Quantitation Limits.
Note 1: Hydrocarbon peaks present includes C_9H_{18}.
ote 2: Hydrocarbon peaks present included C_9H_{18} & $C_{10}H_{20}$
ote 3: Spike level was 5500 ug/kg.

SCITEST LABORATORY SERVICES

CHAIN OF CUSTODY RECORD

PROJECT NO. 1-0342-1 | PROJECT NAME FOTO HUT RUTLAND | CHITTENDEN BANK

SAMPLERS: (Signature)

STA NO	DATE	TIME	COMP.	GRAB	STATION LOCATION	NO. OF CONTAINERS	8240	418.1	MASS SPECIFIED	REMARKS
1	2/5	11:25			SPOIL #3-5' BGS	4		✓	✓	
2	2/6	9:52			TANK 1 west 7' BGS	4		✓	✓	
3	2/6	10:00			TANK 1 WEST 9' BGS	4		✓	✓	
4	2/6	1058			Free Product Tank 2	2			✓	
5	2/6	1100			Free Product TANK 3	2			✓	

Relinquished by: (Signature)	Date / Time	Received by: (Signature)	Relinquished by: (Signature)	Date / Time	Received by: (Signature)
	2/6/92 16:50				
Relinquished by: (Signature)	Date / Time	Received by: (Signature)	Relinquished by: (Signature)	Date / Time	Received by: (Signature)
Relinquished by: (Signature)	Date / Time	Received for Laboratory by: (Signature)	Date / Time	Remarks	

CHAIN OF CUSTODY RECORD

Client/Project Name: CHITTENDEN BANK / FOTOHUT

Project Location: RUTLAND, VT

Project No.: 1-0342-1 (54)

Field Logbook No.:

Sampler: (Signature) Michael Fotty

Chain of Custody Tape No.:

ANALYSES

Sample No./ Identification	Date	Time	Lab Sample Number	Type of Sample	8010	8020					REMARKS
B1	11/29/90		1702-90	SOIL	X	X					TOP 4 inches
B2					X	X					TOP 4 inches
B3					X	X					TOP 4 inches
B4					X	X					TOP 4 inches
B5					X	X					TOP 4 inches and bottom
B6					X	X					TOP 4 inches
B7					X	X					TOP 4 inches bottom 4
B8					X	X					TOP 4 inches bottom 4

	Date	Time		Date	Time
Relinquished by: (Signature) Michael Fotty	11/30	8AM	Received by: (Signature)	11/30	8AM
Relinquished by: (Signature)	Date	Time	Received by: (Signature)	Date	Time
Relinquished by: (Signature)	Date	Time	Received for Laboratory: (Signature) James P Moore	Date 12/3/90	Time 10?
Sample Disposal Method:	Disposed of by: (Signature)			Date	Time

SAMPLE COLLECTOR

5 State Street
Montpelier, VT 05602
(802) 229-4600
Fax: (802) 229-5876

THE JOHNSON COMPANY, INC.
Environmental Sciences and Engineering

ANALYTICAL LABORATORY

1974-3-84

WHITE - To accompany sample to the lab and returned to the Johnson Co. YELLOW - Lab copy PINK - Transporter copy ORANGE - Sampler co

CHAIN OF CUSTODY RECORD

Client/Project Name: CHITTENDEN BANK / FOTOHUT	Project Location: RUTLAND, VT
Project No.: 1-0342-1 (54)	Field Logbook No.
Sampler: (Signature)	Chain of Custody Tape No.

DECANALYSES 4/1990

THE JOHNSON CO., INC.
MONTPELIER, VERMONT

Sample No./ Identification	Date	Time	Lab Sample Number	Type of Sample	8010	8020					REMARKS
OUT 1	11/29/90	—	1702-90	SOIL	X	X					
OUT 2	"			"	X	X					
OUT 3	"			"	X	X					
OUT 4	"			"	X	X					
OUT 5	"			"	X	X					
OUT 6	"			"	X	X					
NONE HERE	"			"	X	X					shipped but not mentioned on COC
TRIP	"			"	X	X					

	Date	Time		Date	Time
Relinquished by: (Signature) Michael Fetty	11/30	8am	Received by: (Signature) Reynolds	11/30	8am
Relinquished by: (Signature)	Date	Time	Received by: (Signature)	Date	Time
Relinquished by: (Signature)	Date	Time	Received for Laboratory: (Signature) James P Mons	Date 12/3/90	Time 10:
Sample Disposal Method:			Disposed of by: (Signature)	Date	Time

SAMPLE COLLECTOR

5 State Street
Montpelier, VT 05602
(802) 229-4600
Fax: (802) 229-5876
THE JOHNSON COMPANY, INC.
Environmental Sciences and Engineering

ANALYTICAL LABORATORY

1974-3-84

WHITE - To accompany sample to the lab and returned to the Johnson Co. YELLOW - Lab copy PINK - Transporter copy ORANGE - Sampler

NO 284

CHAIN OF CUSTODY RECORD

Client/Project Name: Chittenden Bank - Foto Hut	Project Location: Rutland
Project No.: 1-0342-1	Field Logbook No.:
Sampler: (Signature) Jammy Jacques	Chain of Custody Tape No.: JCO-713

Sample No./ Identification	Date	Time	Lab Sample Number	Type of Sample	8240	418.1					REMARKS
SS-1 0-12"	1-15-92	12:15 pm	Z-0089-01	Soil	X	X					
SS-1 2-3'	1-15-92	12:15 pm	02	Soil	X	X					
SS-2 0-12"	1-15-92	2:00 pm	03	Soil	X	X					
SS-2 12-22'	1-15-92	2:00 pm	04	Soil	X	X					
SS-3 0-11"	1-15-92	3:30 pm	05	Soil	X	X					
SS-3 11"-22'	1-15-92	3:30 pm	06	Soil	X	X					
Groundwater	1-15-92	11:00 am	07	Water	X						

	Date	Time		Date	Time
Relinquished by: (Signature) Jammy Jacques	1-17-92	12:00	Received by: (Signature)		
Relinquished by: (Signature)			Received by: (Signature)		
Relinquished by: (Signature)			Received for Laboratory: (Signature) Jim Moore	1/17/92	205
Sample Disposal Method:			Disposed of by: (Signature)		

SAMPLE COLLECTOR

5 State Street
Montpelier, VT 05602
(802) 229-4600
Fax: (802) 229-5876
THE JOHNSON COMPANY, INC.
Environmental Sciences and Engineering

ANALYTICAL LABORATORY

Scitest

1974-3-84

YELLOW - Lab copy PINK - Transporter copy ORANGE - Sampler copy

. HE JOHNSON COMPANY, II
Environmental Sciences and Engineering
5 State Street, Montpelier Vermont 05602
Phone: (802)229-4600
FAX: (802)229-5876

FACSIMILE COVER PAGE
May 12, 1992 11.58

TO:	Mr. Bill M^{c}Cambridge		
COMPANY:	AMREC®		
FAX #:	(508) 248-7701	TELEPHONE #:	(508) 248-3777
JCO #:	1-0342-1	PHONE CODE:	597
FROM:	Hugo Martinez Cazon		

NUMBER OF PAGES, INCLUDING COVER PAGE: 14

Please call Harriet if there are any problems with this transmission.

MESSAGE

Dear Bill,

Here's an explanation of the "Station ID" remarks on the labsheets. X1 represents a composite sample from the roll-off containing soils from Tank 1. This is the sample used by TWM, Inc. to characterize the waste. X2 represents a composite sample collected from the roll-off containing soils that surrounded tanks 2 and 3. X4 represents the contents of tanks 2 and 3. X4 in the labsheets seem to be the sample identified as X3 in the Chain of Custody form, attached.

Michael has not signed the enclosed copy of Attachment 1, he thinks it more appropriate that the Generator sign this form. I am wondering if this unsigned form is enough, along with the analytical results, to initiate the MA-DEP approval process. Please let me know if I can be of further assistance or call Mr. Michael Pottinger, Project Manager at (802) 229-4600.

Sincerely,
THE JOHNSON COMPANY, INC.

By: Hugo Martinez Cazon
Hugo Martinez Cazon
Project Engineer

Reviewed by: hmc
J:\PROJECTS\1-0342-1\AMREC1.FAX May 12, 1992 12.20 mhp

AMERICAN RECLAMATION CORPORATION
AMREC

ATTACHMENT 1

GENERATOR PREQUALIFICATION INFORMATION
PURSUANT TO DEP POLICY #WSC-400-89

INFORMATION ON THE RELEASE:

GENERATOR NAME: THE CHITTENDEN BANK

ADDRESS: 2 Burlington Sq.
Burlington, VT 05402

SITE OF RELEASE: 77A Woodstock Ave Rutland, VT

MATERIAL RELEASED: Uncertain. Lab characterized as Kerosine + fuel oil

BRIEF DESCRIPTION OF RELEASE: Very old tanks discovered during investigation of property. Tanks out of service for at least 20 years.

MATERIAL STOCKPILED? YES X NO ____

ESTIMATED VOLUME OF CONTAMINATED SOIL: ~20 yards

CONTACT PERSON: Michael P. Pottinger TELEPHONE: (802) 229-4600

BILLING AND DOCUMENTATION INFORMATION

Indicate to whom billing and supporting documentation should be sent:

Billing	Documentation
Gene Fucile	Michael Pottinger
The Chittenden Bank	The Johnson Company
2 Burlington Sq.	5 State St
Burlington, VT 05402	Montpelier, VT 05602

CERTIFICATION OF RELEASE OF VIRGIN PETROLEUM PRODUCT

I certify that the ~~analytical results~~ petroleum-containing soil, which is being sent to AmRec for recycling, originated from a release of virgin petroleum product, based on the analytical results. MP

Signature: ____
Typed/Printed Name: ____
Title: ____
Date: ____

225 Turnpike Road
Southborough, MA 01772
(508) 624-7006
Fax (508) 481-5393

Plant: 130 Route 20
Charlton, MA 01508
(508) 248-3777
Fax (508) 248-7701

environmental testing inc.

115 Commerce Way
Portsmouth, New Hampshire 03801
(603) 436-5111

April 2, 1992

Mr. Todd Johnson
Total Waste Management
142 River Road
Newington, NH 03801

CLIENT SAMPLE ID

Client Project: Chittenden Bank, Rutland, VT
Project Number: 1554 KS
Station ID: X1 = Tank 1

SAMPLE DATA

Lab #:	29961-02
Matrix:	Soil
Percent Solid:	78
Dilution Factor:	1
Collection Date:	3/17/92
Lab Receipt Date:	3/17/92
Extraction Date:	3/19/92
Analysis Date:	3/25/92

ANALYTICAL RESULTS SEMI-VOLATILES PAGE TWO

COMPOUND	Detection Limit: µg/kg	Result: µg/kg	COMPOUND	Detection Limit: µg/kg	Result: µg/kg
BASE NEUTRAL COMPOUNDS:					
Acenaphthene	300	ND	N-Nitrosodi-n-propylamine	300	ND
Acenaphthylene	300	ND	N-Nitrosodiphenylamine	300	ND
Anthracene	300	ND	Pyridine	300	ND
Benzo (a) anthracene	300	<300	2-Methylnaphthalene	300	1064
Benzo (a) pyrene	300	<300	2-Chloronaphthalene	300	ND
Benzo (b) fluoranthene	300	<300	Naphthalene	300	3321
Benzo(g,h,i) perylene	300	ND	Biphenyl	300	ND
Benzo (k) fluoranthene	300	<300	Benzo (e) pyrene	300	ND
Chrysene	300	343	Perylene	300	ND
Dibenzo (a,h) anthracene	300	ND	Phenanthrene	300	335
Fluoranthene	300	<300	Dibenzofuran	300	ND
Fluorene	300	ND	Aniline	300	ND
Indeno (1,2,3-cd) pyrene	300	ND	4-Chloroaniline	300	ND
Pyrene	300	335	2-Nitroaniline	300	ND
Hexachloroethane	300	ND	3-Nitroaniline	300	ND
Isophorone	300	ND	4-Nitroaniline	300	ND
N-Nitrosodimethylamine	300	ND			

Base Neutral Surrogate Standard Recovery

d5-Nitrobenzene	104 %	2-Fluorobiphenyl	94 %	d14-p-Terphenyl	56 %

ND= None Detected <=Less than >=Greater than PR= Present but not calibrated for

METHODOLOGY: Water sample analysis was conducted according to "40 CFR part 136, EPA Method 625," and other matrices were analyzed according to "Test Methods for Evaluating Solid Waste, SW-846 Method 8270."

COMMENTS: Detection limit increased due to dilution factor. Results are expressed on a dry weight basis.

Authorized Signature

Ronald W. Tregoning
Laboratory Director

ENSECO environmental laboratory inc.
185 Commerce Way
Portsmouth, New Hampshire 038
603/436-5111

April 2, 1992

Mr. Todd Johnson
Total Waste Management
142 River Road
Newington, NH 03801

CLIENT SAMPLE ID

Client Project: Chittenden Bank, Rutland, VT
Project Number: 1554 KS
Station ID: X1

SAMPLE DATA

Lab #: 28661-02
Matrix: Soil
Percent Solid: 78
Dilution Factor: 1
Collection Date: 3/17/92
Lab Receipt Date: 3/17/92
Extraction Date: 3/19/92
Analysis Date: 3/25/92

ANALYTICAL RESULTS SEMI-VOLATILES

COMPOUND	Detection Limit µg/kg	Result µg/kg	COMPOUND	Detection Limit µg/kg	Result µg/kg
ACID COMPOUNDS:					
2-Chlorophenol	300	ND	Pentachlorophenol	1000	ND
4-Chloro-3-methylphenol	1000	ND	Phenol	300	ND
2,4-Dichlorophenol	300	ND	2,4,5-Trichlorophenol	300	ND
2,4-Dimethylphenol	300	ND	2,4,6-Trichlorophenol	300	ND
2,4-Dinitrophenol	300	ND	Benzoic Acid	300	ND
4,6-Dinitro-2-methylphenol	300	ND	m-Cresol	300	ND
2-Nitrophenol	300	ND	o,p-Cresol	300	ND
2,6-Dichlorophenol	300	ND	Benzyl alcohol	300	ND
4-Nitrophenol	300	ND	2,3,4,6-Tetrachlorophenol	300	ND

Acid Surrogate Standard Recovery

2,4,6-Tribromophenol	53 %	2-Fluorophenol	72 %	d5-Phenol	84 %

BASE NEUTRAL COMPOUNDS:					
1,2-Dichlorobenzene	300	ND	Hexachlorobenzene	300	ND
1,3-Dichlorobenzene	300	ND	Benzidine	2000	ND
1,4-Dichlorobenzene	300	ND	3,3'-Dichlorobenzidine	2000	ND
2,4-Dinitrotoluene	300	ND	Azobenzene	300	ND
2,6-Dinitrotoluene	300	ND	Bis (2-chloroethoxy) methane	300	ND
Nitrobenzene	300	ND	Bis (2-chloroethyl) ether	300	ND
Hexachlorobutadiene	300	ND	Bis (2-chloroisopropyl) ether	300	ND
Dimethyl phthalate	300	ND	4-Bromophenyl phenyl ether	300	ND
Di-n-butyl phthalate	300	ND	Butyl benzyl phthalate	300	ND
Di-n-octyl phthalate	300	ND	4-Chlorophenyl phenyl ether	300	ND
Bis (2-ethylhexyl) phthalate	300	ND	Diethyl phthalate	300	ND
1,2,4-Trichlorobenzene	300	ND	Hexachlorocyclopentadiene	300	ND

ND= None Detected <=Less than >=Greater than PR= Present but not calibrated for

METHODOLOGY: Water sample analysis was conducted according to "40 CFR part 136, EPA Method 625," and other matrices were analyzed according to "Test Methods for Evaluating Solid Waste, SW-846 Method 8270."

Authorized signature

Kenneth W. Teague
Laboratory Director

Chemtech Environmental Laboratory Inc.
196 Commerce Way
Portsmouth, New Hampshire 03801
603/436-8111

April 2, 1992

Mr. Todd Johnson
Total Waste Management
142 River Road
Newington, NH 03801

Client Project: Chittendon Bank, Rutland, VT

Project Number: 1554 KS
Station ID: X1

Lab #: 28661-02
Matrix: Soil
Percent Solid: 78
Dilution Factor: 1
Collection Date: 3/17/92
Lab Receipt Date: 3/17/92
Extraction Date: 3/19/92
Analysis Date: 3/25/92

TOTAL PETROLEUM HYDROCARBON ANALYSIS

Sample	Result	Units	Detection Limit
28661-02	230	mg/kg	1

ND denotes none detected.

Methodology: Water samples were prepared by Seperatory Funnel Liquid/Liquid Extraction, EPA Method 3510; other matrices were prepared by Soxhlet Extraction, EPA Method 3540. All matrices were analyzed according to "Test Methods for Evaluating Solid Waste, SW-846 Method 8100."

Comments:

Results are expressed on a dry weight basis. Chromatographic fingerprint is indicative of 6 mg/ml #2 fuel oil and 224 mg/kg kerosene.

Authorized signature

Kenneth W. Taylor
Laboratory Director

Groundwater environmental laboratory inc.

195 Commerce Way
Portsmouth, New Hampshire 0380
603-436-5111

April 2, 1992

Mr. Todd Johnson
Total Waste Management
142 River Road
Newington, NH 03801

CLIENT SAMPLE ID

Client Project: Chittenden Bank, Rutland, VT
Project Number: 1554 KS
Station ID: X1

SAMPLE DATA

Lab #:	28661-01
Matrix:	Soil
Percent Solid:	78
Dilution Factor:	100
Collection Date:	3/17/92
Lab Receipt Date:	3/17/92
Analysis Date:	3/20/92

ANALYTICAL RESULTS VOLATILE ORGANICS

COMPOUND	Detection Limit µg/kg	Result µg/kg	COMPOUND	Detection Limit µg/kg	Result µg/kg
Vinyl chloride	500	ND	Ethylbenzene	500	<500
1,1-Dichloroethene	500	ND	m-Xylene	500	1754
1,2-Dichloroethene (cis or trans)	500	ND	o&p-Xylene	500	2090
Trichloroethene	500	ND	Methyl t-butyl ether	500	ND
Tetrachloroethene	500	<500	m-Dichlorobenzene	500	ND
Chloromethane	500	ND	o-Dichlorobenzene	500	ND
Methylene chloride	500	ND	p-Dichlorobenzene	500	ND
Chloroform	500	ND	1,2-Dichloropropane	500	ND
Carbon tetrachloride	500	ND	cis-1,3-Dichloropropene	500	ND
Bromodichloromethane	500	ND	trans-1,3-Dichloropropene	500	ND
Dibromochloromethane	500	ND	2-Chloroethylvinyl ether	1500	ND
Bromomethane	500	ND	Acetone	1500	ND
Chloroethane	500	ND	Methyl ethyl ketone	1000	ND
1,1-Dichloroethane	500	ND	Methyl isobutyl ketone	1000	ND
1,2-Dichloroethane	500	ND	Dichlorodifluoromethane	500	ND
1,1,1-Trichloroethane	500	ND	Trichlorofluoromethane	500	ND
1,1,2-Trichloroethene	500	ND	Tetrahydrofuran	1500	ND
1,1,2,2-Tetrachloroethane	500	ND	Styrene	500	ND
Chlorobenzene	500	ND	Carbon disulfide	500	ND
Bromoform	500	ND	Vinyl acetate	1500	ND
Benzene	500	ND	2-Hexanone	1000	ND
Toluene	500	ND			

Surrogate Standard Recovery

d4-1,2-Dichloroethane	* %	d8-Toluene	* %	Bromofluorobenzene	* %

ND=None Detected <=Less than >=Greater than PR=Present but not calibrated for

METHODOLOGY: Water sample analysis was conducted according to "40 CFR Part 136, EPA Method 624" and other matrices were analyzed according to "Test Methods for Evaluating Solid Waste, SW-846 Method 8240."

COMMENTS: Detection limits increased due to dilution factor. Results are expressed on a dry weight basis. *The surrogates were diluted out.

environmental laboratory inc.

195 Commerce Way
Portsmouth, New Hampshire 03801
603-436-5111

Mr. Todd Johnson
Total Waste Management
142 River Road
Newington, NH 03801

April 2, 1992

Client Project: Chittendon Bank, Rutland, VT
Project Number: 1554 KS
Station ID: X1

Lab #: 28661-02
Matrix: Soil
Collection Date: 3/17/92
Lab Receipt Date: 3/17/92
Analysis Date: 3/20/92

FLASH POINT ANALYSIS

Sample	Result
28661-02	>160 degrees Fahrenheit

Methodology: Sample analysis was conducted according to "Test Methods for Evaluating Solid Waste, EPA SW-846, Method 1010."

Comments:

Authorized signature

Kenneth W. Tosseo
Laboratory Director

Analytical Technologies, Inc.
165 Commerce Way
Portsmouth, New Hampshire 03
603-436-8111

April 2, 1992

CLIENT SAMPLE ID

SAMPLE DATA

Client Project: Chittendon Bank, Rutland, VT

Project Number: 1554 KS

Station ID: X1

Lab #: 28661-02

Matrix: Soil

TCLP

Extraction Date: 3/24/92

ANALYTICAL RESULTS

TCLP

SEMI-VOLATILE EXTRACTION DATA:

Preliminary sample evaluation:

The initial pH of the sample was greater than 5.00. After the appropriate treatment with HCL and heat, the pH was remeasured. If the pH of the sample was less than 5.00, then extraction fluid #1 was used. Extraction fluid #1 is 5.7 ml glacial acetic acid, 63.4 ml of 1N NaOH, diluted to one liter with deionized water resulting in a pH of 4.93 ± 0.05. If the pH was greater than 5.00 after treatment, extraction fluid #2 was used. Extraction fluid #2 is 5.7 ml glacial acetic acid diluted to one liter with deionized water, resulting in a pH of 2.88 ± 0.05.

EXTRACTION PROCEDURE DATA:

Initial pH	7.35
pH After Treatment	1.15
Final pH	5.16
TCLP Solids	100 %
Total Weight Extracted	100 grams
Total Extraction Time	18 hours

METHODOLOGY: EPA Federal Register Vol. 55, No. 126; June 29, 1990.

Authorized signature

Kenneth W. Tetzlaff
Laboratory Director

Credelle environmental laboratory inc.

195 Commerce Way
Portsmouth, New Hampshire 03
603-433-5111

April 2, 1992

Mr. Todd Johnson
Total Waste Management
142 River Road
Newington, NH 03801

CLIENT SAMPLE ID

Client Project: Chittendon Bank, Rutland, VT
Project Number: 1554 KS
Station ID: X1

SAMPLE DATA

Lab #:	28661-02
Matrix:	Soil
Percent Solids:	78
Dilution Factor:	10
Collection Date:	3/17/92
Lab Receipt Date:	3/17/92
Extraction Date:	3/20/92
Analysis Date:	3/28/92

ANALYTICAL RESULTS PESTICIDES & PCB'S

COMPOUND	Detection Limit µg/kg	Result µg/kg	COMPOUND	Detection Limit µg/kg	Result µg/kg
Aldrin	100	ND	Endrin Aldehyde	100	ND
a-BHC	100	ND	Heptachlor	100	ND
b-BHC	100	ND	Heptachlor Epoxide	100	ND
d-BHC	100	ND	Toxaphene	100	ND
g-BHC (Lindane)	100	ND	Methoxychlor	100	ND
Chlordane	100	ND	PCB-1016	100	ND
4,4'-DDD	100	ND	PCB-1221	100	ND
4,4'-DDE	100	ND	PCB-1232	100	ND
4,4'-DDT	100	ND	PCB-1242	100	ND
Dieldrin	100	ND	PCB-1248	100	ND
Endosulfan I	100	ND	PCB-1254	100	ND
Endosulfan II	100	ND	PCB-1260	100	ND
Endosulfan Sulfate	100	ND	PCB-1262	100	ND
Endrin	100	ND			

ND=None Detected <=Less than >=Greater then PR=Present but not calibrated for

METHODOLOGY: Water sample analysis was conducted according to "40 CFR Part 136, EPA Method 608" and all other matrices were analyzed according to "Test Methods for Evaluating Solid Waste, SW-846 Method 8080."

COMMENTS: Detection limits increased due to dilution factor. Results are expressed on a dry weight basis.

Authorized signature

Kenneth W. Feagin

SENT BY: 4- 3-92 ;10:20AM ; 603 436 0154-603 431 3805 2# 4

analytics environmental laboratory inc.

195 Commerce Way
Portsmouth, New Hampshire 03801
603-436-5111

April 2, 1992

Mr. Todd Johnson
Total Waste Management
142 River Road
Newington, NH 03801

CLIENT SAMPLE ID

Client Project: Chittenden Bank, Rutland, VT
Project Number: 1554 KS
Station ID: X1

SAMPLE DATA

Lab #:	28661-02
Matrix:	Soil
Percent Solid:	78
Dilution Factor:	1
Collection Date:	3/17/92
Lab Receipt Date:	3/17/92
Extraction Date:	3/20/92
Analysis Date:	4/1/92

ANALYTICAL RESULTS CHLORINATED HERBICIDES

COMPOUND	Detection Limit µg/kg	Result µg/kg
Dichloroprop	100	ND
Dalapon	100	ND
2,4-D	100	ND
2,4,5-TP	100	ND
2,4,5-T	100	ND
Dicamba	100	ND
MCPA	100	ND
MCPP	100	ND
2,4-DB	100	ND

ND=None Detected <=Less than >=Greater than PR=Present but not calibrated for

METHODOLOGY: Water sample analysis was conducted according to "40 CFR Part 136, EPA Method 615," and other matrices were analyzed according to "Test Methods for Evaluating Solid Waste, SW-846 Method 8150."

COMMENTS: Detection limits increased due to dilution factor. Results are expressed on a dry weight basis.

environmental laboratory inc.
[illegible] Commerce Way
Portsmouth, New Hampshire 03801
603-431-1111

April 3, 1992

Mr. Todd Johnson
Total Waste Management
142 River Road
Newington, NH 03801

CLIENT SAMPLE ID

Client Project: Chittendon Bank, Rutland, VT
Project Number: 1554 KS
Station ID: X-4 Tank sludge drums Tank 2+3 contents

SAMPLE DATA

Lab #:	28551-04
Matrix:	Soil
Percent Solids:	43
Dilution Factor:	25200
Collection Date:	3/17/92
Lab Receipt Date:	3/17/92
Analysis Date:	4/2/92

ANALYTICAL RESULTS VOLATILE ORGANICS

COMPOUND	Detection Limit: µg/kg	Result: µg/kg	COMPOUND	Detection Limit: µg/kg	Result: µg/kg
Vinyl chloride	126000	ND	Ethylbenzene	126000	ND
1,1-Dichloroethene	126000	ND	o-Xylene	126000	ND
1,2-Dichloroethene (cis or trans)	126000	ND	m&p-Xylene	126000	<126000
Trichloroethene	126000	ND	Methyl t-butyl ether	126000	ND
Tetrachloroethene	126000	ND	m-Dichlorobenzene	126000	ND
Chloromethane	126000	ND	o-Dichlorobenzene	126000	ND
Methylene chloride	126000	ND	p-Dichlorobenzene	126000	ND
Chloroform	126000	ND	1,2-Dichloropropane	126000	ND
Carbon tetrachloride	126000	ND	cis-1,3-Dichloropropene	126000	ND
Bromodichloromethane	126000	ND	trans-1,3-Dichloropropene	126000	ND
Dibromochloromethane	126000	ND	2-Chloroethylvinyl ether	378000	ND
Bromomethane	126000	ND	Acetone	378000	ND
Chloroethane	126000	ND	Methyl ethyl ketone	252000	ND
1,1-Dichloroethane	126000	ND	Methyl isobutyl ketone	252000	ND
1,2-Dichloroethane	126000	ND	Dichlorodifluoromethane	126000	ND
1,1,1-Trichloroethane	126000	ND	Trichlorofluoromethane	126000	ND
1,1,2-Trichloroethane	126000	ND	Tetrahydrofuran	378000	ND
1,1,2,2-Tetrachloroethane	126000	ND	Styrene	126000	ND
Chlorobenzene	126000	ND	Carbon disulfide	126000	ND
Bromoform	126000	ND	Vinyl acetate	378000	ND
Benzene	126000	ND	2-Hexanone	252000	ND
Toluene	126000	ND			

Surrogate Standard Recovery

d4-1,2-Dichloroethane	* %	d8-Toluene	* %	Bromofluorobenzene	* %

ND=None Detected <=Less than >=Greater than PR=Present but not calibrated for

METHODOLOGY: Water sample analysis was conducted according to "40 CFR Part 136, EPA Method 624" and other matrices were analyzed according to "Test Methods for Evaluating Solid Waste, SW-846 Method 8240."

COMMENTS: Detection limits increased due to dilution factor. Results are expressed on a dry weight basis. *The surrogates were diluted out. Dilution necessary due to excessive foaming. Dilution necessary due to a contarget compound.

Authorized signature

Kenneth W. Teague
Laboratory Director

Analytics Environmental Laboratory Inc.
185 Commerce Way
Portsmouth, New Hampshire 03801
603-436-5111

April 2, 1992

Mr. Todd Johnson
Total Waste Management
142 River Road
Newington, NH 03801

CLIENT SAMPLE ID

Client Project: Chittendon Bank, Rutland, VT
Project Number: 1554 KS
Station ID: X2 = Spoils pile 96

SAMPLE DATA

Lab #:	28661-03
Matrix:	Soil
Percent Solid:	82
Dilution Factor:	10
Collection Date:	3/17/92
Lab Receipt Date:	3/17/92
Extraction Date:	3/21/92
Analysis Date:	3/28/92

ANALYTICAL RESULTS POLYCHLORINATED BIPHENYLS

COMPOUND	Detection Limit µg/kg	Result µg/kg
PCB 1016	100	ND
PCB 1221	100	ND
PCB 1232	100	ND
PCB 1242	100	ND
PCB 1248	100	ND
PCB 1254	100	ND
PCB 1260	100	ND
PCB 1262	100	ND

ND=None Detected <=Less than >=Greater than PR=Present but not calibrated for

METHODOLOGY: Water sample analysis was conducted according to "40 CFR Part 136, EPA Method 608" and other matrices were analyzed according to "Test Methods for Evaluating Solid Waste, SW-846, Method 8080."

COMMENTS: Detection limits increased due to dilution factor. Results are expressed on a dry weight basis.

Authorized signature

Kenneth W. Teague
Laboratory Director

Analytics environmental laboratory inc.
195 Commerce Way
Portsmouth, New Hampshire 038
603-436-5111

April 2, 1992

Mr. Todd Johnson
Total Waste Management
142 River Road
Newington, NH 03801

CLIENT SAMPLE ID

Client Project: Chittendon Bank, Rutland, VT
Project Number: 1554 KS
Station ID: X2

SAMPLE DATA

Lab #:	28661-03
Matrix:	Soil
Percent Solid:	82
Dilution Factor:	100
Collection Date:	3/17/92
Lab Receipt Date:	3/17/92
Analysis Date:	3/20/92

ANALYTICAL RESULTS VOLATILE ORGANICS

COMPOUND	Detection Limit µg/kg	Result µg/kg	COMPOUND	Detection Limit µg/kg	Result µg/kg
Vinyl chloride	500	ND	Ethylbenzene	500	7831
1,1-Dichloroethene	500	ND	m-Xylene	500	39365
1,2-Dichloroethene (cis or trans)	500	ND	o&p-Xylene	500	52513
Trichloroethene	500	ND	Methyl t-butyl ether	500	ND
Tetrachloroethene	500	ND	m-Dichlorobenzene	500	ND
Chloromethane	500	ND	o-Dichlorobenzene	500	ND
Methylene chloride	500	ND	p-Dichlorobenzene	500	ND
Chloroform	500	ND	1,2-Dichloropropane	500	ND
Carbon tetrachloride	500	ND	cis-1,3-Dichloropropene	500	ND
Bromodichloromethane	500	ND	trans-1,3-Dichloropropene	500	ND
Dibromochloromethane	500	ND	2-Chloroethylvinyl ether	1500	ND
Bromomethane	500	ND	Acetone	1500	ND
Chloroethane	500	ND	Methyl ethyl ketone	1000	ND
1,1-Dichloroethane	500	ND	Methyl isobutyl ketone	1000	ND
1,2-Dichloroethane	500	ND	Dichlorodifluoromethane	500	ND
1,1,1-Trichloroethane	500	ND	Trichlorofluoromethane	500	ND
1,1,2-Trichloroethane	500	ND	Tetrahydrofuran	1500	ND
1,1,2,2-Tetrachloroethane	500	ND	Styrene	500	ND
Chlorobenzene	500	ND	Carbon disulfide	500	ND
Bromoform	500	ND	Vinyl acetate	1500	ND
Benzene	500	ND	2-Hexanone	1000	ND
Toluene	500	ND			

Surrogate Standard Recovery

d4-1,2-Dichloroethane	*%	d8-Toluene	*%	Bromofluorobenzene	*%

ND=None Detected <=Less than >=Greater than PR=Present but not calibrated for

METHODOLOGY: Water sample analysis was conducted according to "40 CFR Part 136, EPA Method 624" and other matrices were analyzed according to "Test Methods for Evaluating Solid Waste, SW-846 Method 8240."

COMMENTS: Detection limits increased due to dilution factor. Results are expressed on a dry weight basis. *The surrogates were diluted out.

LABORATORY:

Analytics Environmental Laboratory
P.O. Box 433, 195 Commerce Way
Portsmouth, NH 03801
(603) 436-5111

CLIENT:

Total Waste Management Corp.
142 River Rd.
Newington, NH 03801
(603) 431-2420 Fax (603) 431-3806

PROJECT # 1554 KS

PROJECT NAME CHITTENDEN BANK Rutland VT

SAMPLER K. SCHMIT

STATION NUMBER	DATE	TIME	STATION LOCATION	Analytics Sample#	Matrix: 1=Water, 2=Soil 3=Oil, 4=Other	Preservation: 1=Ice 2=HNO3, 3=Other	Number of containers	MTS Testing	EPA 8010 Soil, (Rebuttal) Halocarbons	Modified 8020/602 BTEX, (Gas Tanks) TPH, Gasoline Standard	EPA 8240 Soil/624 Water, VOCs	8020 soil/602 water (Oil Tanks) BTEX & MTBE	TPH (High Resolution) (Oil Tanks) Fuel Oil Standard, Type of Fuel	REMARKS
1	3/17/92		ROLL OFF #1	28661-01 28661-02	2	for VOA only	3	X						REMARKS
2	3/17/92		ROLL OFF #2	28661-03	2		1				X			REMARKS
3	3/11/92		TANK SLUDGE DRUMS	28661-04	2		1				X			REMARKS X3 Sample received w/ headspace (VOA)
														REMARKS
														REMARKS
														REMARKS
														REMARKS

Sample Container Requirements.

Test	Quantity	Type	Sample Type
8010	1	2 oz. jar	soil/oil
Mod. 8020	1	2 oz. jar	soil/oil
Mod 602	2	Vials *	water
8240	1	2 oz. jar	soil/oil
624	2	vials	water
8020	1	2 oz. jar	soil/oil
602	2	Vials *	water
TPH High Res.	1	4 oz. jar	soil/oil
TPH High Res.	1	liter bottle	water
MTS Samples	2	8 oz. jar	soil
	1	2 oz. jar	soil

* Vials must be used. Containers larger than 2 oz. may be used. Fill all completely. Clean dirt off threads before replacing lid.

RELINQUISHED BY	Date	Time	RECEIVED BY	RELINQUISHED BY	Date	Time	RECEIVED BY
K Schmit	3/17/92				3/17/92		
RELINQUISHED BY	Date	Time	RECEIVED BY	RELINQUISHED BY	Date	Time	RECEIVED BY

RECEIVED FOR LABORATORY

TURNAROUND REQUEST Standard _____ Priority P.O. Number: 1554 KS

04/03/1992 11:1. TOTAL WASTE MANAGEMENT 603 .1 3825 P.01

LABORATORY REPORT

CLIENT NAME: Johnson Co.
SITE LOCATION: Chittenden Bank/Fotohut
LABORATORY NO: 1702-90
PROJECT NO: 78611
ATTENTION: Mike Pottinger

DATE OF SAMPLE: 11/29/90
DATE OF RECEIPT: 12/3/90
DATE OF ANALYSIS: 12/4/90
DATE OF REPORT: 1/16/91

PARAMETER	B - 1	B - 2	B - 3	B - 4	B - 5 TOP	B - 5 Bottom
Chloromethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Bromoform	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Bromomethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Dibromochloromethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Vinyl Chloride	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
2-Chloroethylvinyl Ether	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Chloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Methylene Chloride	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Trichloroethylene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Trichlorofluoromethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1-Dichlorethene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1-Dichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
c or t-1,2-Dichloroethylene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Chloroform	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,2-Dichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1,1-Trichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Carbon Tetrachloride	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Bromodichloromethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,2-Dichloropropane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
t-1,3-Dichloropropene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
c-1,3-Dichloropropene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1,2,2-Tetrachloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1,2-Trichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Tetrachloroethylene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Benzene	4	5	112	BPQL	10	2073
Toluene	BPQL	BPQL	BPQL	BPQL	11	1590
Ethylbenzene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Chlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,4-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,3-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,2-Dichlorobenzene	80	26	110	BPQL	61	2410
Xylenes	1518	296	3335	BPQL	436	115000
Total Aromatics as Xylene	2.5	1.9	1.8	3.1	2.1	691
QL Raised by Factor of:	80.6%	78.1%	81.5%	81.7%	84.3%	75.5%
% Solids	Note1	Note1	Note1		Note1	Note1

EPA Method 8010 & 8020; All results reported as ug/l or ppb as dry weight.
BPQL = Below Practical Quantitation Limit.
5 ppb for Bromoform, 2-Chloroethylvinyl Ether, & Methylene Chloride
1 ppb for All other parameters, 10 ppb for Total Aromatics.
Note 1: Many unknown late eluting Aromatic or Alkene peaks found.

Respectfully Submitted,
SCITEST, INC.

Roderick J. Lamothe
Laboratory Director

RJL/cha

SCITEST
LABORATORY SERVICES

LABORATORY REPORT

CLIENT NAME: Johnson Co.
SITE LOCATION: Chittenden Bank/Fotohut
LABORATORY NO: 1702-90
PROJECT NO: 78611
ATTENTION: Mike Pottinger

DATE OF SAMPLE: 11/29/90
DATE OF RECEIPT: 12/3/90
DATE OF ANALYSIS: 12/5/90
DATE OF REPORT: 1/16/91

PARAMETER	B - 6	B - 7 TOP	B - 7 BOTTOM	B - 8 TOP	B - 8 BOTTOM	Near Hol
Chloromethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Bromoform	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Bromomethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Dibromochloromethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Vinyl Chloride	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
2-Chloroethylvinyl Ether	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Chloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Methylene Chloride	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Trichloroethylene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Trichlorofluoromethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1-Dichlorethene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1-Dichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
c or t-1,2-Dichloroethylene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Chloroform	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,2-Dichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1,1-Trichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Carbon Tetrachloride	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Bromodichloromethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,2-Dichloropropane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
t-1,3-Dichloropropene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
c-1,3-Dichloropropene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1,2,2-Tetrachloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1,2-Trichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Tetrachloroethylene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Benzene	BPQL	12300	3170	211	BPQL	2120
Toluene	BPQL	1400	2500	BPQL	BPQL	3850
Ethylbenzene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Chlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,4-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,3-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,2-Dichlorobenzene	BPQL	31900	54100	BPQL	BPQL	15700
Xylenes	BPQL	351000	359000	3140	BPQL	420000
Total Aromatics as Xylene	2.7	139	265	178	2.0	525
QL Raised by Factor of:	83.2%	74.2%	79.4%	89.3%	89.2%	85.5%
% Solids		Note1	Note1	Note1		Note1

EPA Method 8010 & 8020; All results reported as ug/l or ppb as dry weight.
BPQL = Below Practical Quantitation Limit.
5 ppb for Bromoform, 2-Chloroethylvinyl Ether, & Methylene Chloride
1 ppb for All other parameters, 10 ppb for Total Aromatics.
Note 1: Many unknown late eluting Aromatic or Alkene peaks found.

Respectfully Submitted,
SCITEST, INC.

Roderick J. Lamothe
Laboratory Director

RJL/cha

SCITEST
LABORATORY SERVICES

LABORATORY REPORT

CLIENT NAME: Johnson Co.
SITE LOCATION: Chittenden Bank/Fotohut
LABORATORY NO: 1702-90
PROJECT NO: 78611
ATTENTION: Mike Pattinger

DATE OF SAMPLE: 11/29/90
DATE OF RECEIPT: 12/3/90
DATE OF ANALYSIS: 12/10/90
DATE OF REPORT: 1/16/91

PARAMETER	OUT 1	OUT 2	OUT 3	OUT 4	OUT 5	OUT 6
Chloromethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Bromoform	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Bromomethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Dibromochloromethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Vinyl Chloride	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
2-Chloroethylvinyl Ether	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Chloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Methylene Chloride	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Trichloroethylene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Trichlorofluoromethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1-Dichlorethene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1-Dichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
c or t-1,2-Dichloroethylene	4350	BPQL	BPQL	BPQL	BPQL	BPQL
Chloroform	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,2-Dichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1,1-Trichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Carbon Tetrachloride	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Bromodichloromethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,2-Dichloropropane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
t-1,3-Dichloropropene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
c-1,3-Dichloropropene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1,2,2-Tetrachloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,1,2-Trichloroethane	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Tetrachloroethylene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Benzene	742	BPQL	BPQL	BPQL	BPQL	BPQL
Toluene	32700	1408	18600	BPQL	BPQL	3
Ethylbenzene	69500	BPQL	56300	BPQL	BPQL	BPQL
Chlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,4-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,3-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
1,2-Dichlorobenzene	BPQL	BPQL	BPQL	BPQL	BPQL	BPQL
Xylenes	189000	1530	199000	BPQL	BPQL	10
Total Aromatics as Xylene	4030000	36300	4790000	BPQL	BPQL	192
QL Raised by Factor of:	219	179	1400	2.6	2.7	2.4
% Solids	83.1%	86.1%	82.7%	86.6%	83.0%	88.2%
	Note1	Note1	Note1			Note1

EPA Method 8010 & 8020; All results reported as ug/l or ppb as dry weight.
BPQL = Below Practical Quantitation Limit.
5 ppb for Bromoform, 2-Chloroethylvinyl Ether, & Methylene Chloride
1 ppb for All other parameters, 10 ppb for Total Aromatics.
Note 1: Many unknown late eluting Aromatic or Alkene peaks found.

Respectfully Submitted,
SCITEST, INC.

Roderick J. Lamothe
Laboratory Director

RJL/cha

SCITEST
LABORATORY SERVICES

LABORATORY REPORT

CLIENT NAME:	Johnson Co.	DATE OF SAMPLE:	11/29/90
ITE LOCATION:	Chittenden Bank/Fotohut	DATE OF RECEIPT:	12/3/90
ABORATORY NO:	1702-90	DATE OF ANALYSIS:	12/6/90
PROJECT NO:	78611	DATE OF REPORT:	1/9/91
TTENTION:	Mike Pottinger		

PARAMETER	TANK #1
hloromethane	<10
romoform	<50
Bromomethane	<10
ibromochloromethane	<10
inyl Chloride	<10
2-Chloroethylvinyl Ether	<50
hloroethane	<10
ethylene Chloride	<50
Trichloroethylene	<10
Trichlorofluoromethane	<10
,1-Dichlorethene	<10
,1-Dichloroethane	<10
c or t-1,2-Dichloroethylene	<10
hloroform	<10
,2-Dichloroethane	<10
1,1,1-Trichloroethane	<10
arbon Tetrachloride	<10
romodichloromethane	<10
1,2-Dichloropropane	<10
-1,3-Dichloropropene	<10
-1,3-Dichloropropene	<10
,1,2,2-Tetrachloroethane	<10
1,1,2-Trichloroethane	<10
etrachloroethylene	<10
enzene	<10
Toluene	384
thylbenzene	241
hlorobenzene	<10
1,4-Dichlorobenzene	<10
1,3-Dichlorobenzene	<10
,2-Dichlorobenzene	<10
ylenes	5900
	Note 1

RECEIVED

JAN 10 1991

THE JOHNSON CO., INC.
MONTPELIER, VERMONT

PA Method 601 & 602; All results reported as ug/l or ppb.

ote 1: The Tank sample contained many heavy unknown aromatic hydrocarbons.

Respectfully Submitted,
SCITEST, INC.

Roderick J. Lamothe
Laboratory Director

JL/cha

SCITEST
LABORATORY SERVICES

APPENDIX E

Monitoring Well Water Level Data

WELL ID	WATER LEVEL	TOC ELEV	GS ELEV	DATE	H20 ELEV
MW-1	5.65	689.70	689.90	10/01/93	684.05
MW-1	5.10	689.70	689.90	10/07/93	684.60
MW-1	4.86	689.70	689.90	10/12/93	684.84
MW-1	4.28	689.70	689.90	11/08/93	685.42
MW-2	4.03	689.26	689.76	10/01/93	685.23
MW-2	4.61	689.26	689.76	10/07/93	684.65
MW-2	3.84	689.26	689.76	10/12/93	685.42
MW-2	3.29	689.26	689.76	11/08/93	685.97
MW-3	5.56	689.44	689.59	10/01/93	683.88
MW-3	4.71	689.44	689.59	10/07/93	684.73
MW-3	4.97	689.44	689.59	10/12/93	684.47
MW-3	4.58	689.44	689.59	11/08/93	684.86
MW-4	4.96	689.37	689.87	10/01/93	684.41
MW-4	4.08	689.37	689.87	10/07/93	685.29
MW-4	4.39	689.37	689.87	10/12/93	684.98
MW-4	4.04	689.37	689.87	11/08/93	685.33
MW-5	7.35	688.05	688.55	10/01/93	680.70
MW-5	4.96	688.05	688.55	10/07/93	683.09
MW-5	4.98	688.05	688.55	10/12/93	683.07
MW-5	4.64	688.05	688.55	11/08/93	683.41
MW-6	4.70	0.00	688.48	10/01/93	683.78
MW-7	6.77	687.95	688.51	10/01/93	681.18
MW-7	4.73	687.95	688.51	10/07/93	683.22
MW-7	4.84	687.95	688.51	10/12/93	683.11
MW-7	4.54	687.95	688.51	11/08/93	683.41
MW-8	5.47	690.31	688.43	10/12/93	684.84
MW-8	5.06	690.31	688.43	11/08/93	685.25
OB-1	7.15	692.25	690.25	10/01/93	685.10
OB-1	5.93	692.25	690.25	10/07/93	686.32
OB-1	6.78	692.25	690.25	10/12/93	685.47
OB-1	6.36	692.25	690.25	11/08/93	685.89
PZ-1	4.48	690.13	690.10	11/08/93	685.85

H2O elevations not corrected for vertical hydraulic gradient.
Elevations in feet above National Geodetic Vertical Datum

11/9 - FOT/ONIOT

1100 - 1130 ψ contour maps

Downward HG 11/8 correct: 0.052 ft/ft

	WE	CTR screen	Correct ψ Elev
MW1	685.42	676.5	685.60
PZ1	685.85	681.73	685.60
MW2	685.97	683.36	685.85
MW3	684.86	682.34	684.74
MW4	685.33	680.22	685.32
MW5	683.41	681.53	683.33 ✓
MW7	683.41	681.53	683.33 ✓
MW8	685.25	683.03	685.19
OB1	685.89	681.75	685.80
OB2			

Normalize to 680.0 → (680 − CTRS) 0.052 + WElev

Calc CTR Screen ψ MW5

TOC − casing = TOS

688.05 − 3.8 = 684.25

IF TOS > WE Then $CTR_{screen} = \frac{WE - BSE}{2} + BSE$

684.25 > 683.41

MW5 CTR screen = $\frac{683.41 - 679.65}{2}$

= 681.53

IF TOS < WE Then

$CTR_{screen} = \frac{TOS - BOS}{2} + BOS$

Backfill around TP5 -
Dig around TP-3 - refusal is rock!! / rubble
Smell "sweet odor" near TP7

TP location



OB-2 to 7 = 21.6'

stopped raining @ 1:15

offsite 1100

11/8 1-0372-2 | 13222
FOTOHAT 12:15
RANDOPH 1:15 12247
ONSITE 1400

	WL		Time	TOC	ELEV
PZ1	4.18		14:10	690.13	685.95
MW1	4.28	↑	14:13	689.70	685.42
MW2	3.29	↑	14:40	689.26	685.97
MW3	4.58	↑	14:25	689.44	684.86
MW4	4.04	↑	14:20	689.37	685.33
MW5	4.64	↑	14:35	688.05	683.41
MW7	4.54	↑	14:30	687.95	683.41
OB1	6.36	↕	14:43	692.25	685.89
OB2	6.30		14:45	EST 692.7±	EST 687.5
MW8	5.66	↑	14:52	690.31	685.25

$\frac{(PZ1\ E - MW1\ E)}{(684.8 - 676.5)} = \frac{(0.43)}{(8.23)} = 0.052\ ft/ft$ Downward

~~685.72~~ ctr screen

TOC PZ1 5 3/8" above TOC MW1 0.45'
" " 2.5" " TOG MW1 0.21
~~MW2~~ .23

OFFSITE 15:00

MW1 TOC = 689.70 TOG = 689.90
CALC PZ1 TOC/GS 690.15 690.11
AVE 690.13 FMSL

APPENDIX F

Water Supply Well Data

SITE 91-1011
FOTO HUT PROPERTY

APA OR WHPA
PUBLIC SUPPLY

PUBLIC UNCONS. OR GRAVEL WELL

PUBLIC BEDROCK WELL

250 Private gravel

TOWN LINE

Surface Water

Rutland City Corp Boundry

16C
Proctor, VT
1944

WSID 5237
POP=127
(1) ROCK

WSID 5231
POP=44
(1) GRAVEL

26A
Chittenden, VT
1961
Photorev.
1988

MENDON TOWN LINE

WSID 5235
POP=46
(1) ROCK

WSID 5234
POP=15
(1) ROCK

WSID 5378
POP=56
(2) ROCK

WSID 5429
POP=198
(2) ROCK

2 MILE RAD

26B
Rutland, VT
1961
Photorev.
1988

16D
Rutland, VT
1964
Photorev.
1972

SCALE 1:24000

1 0 1 MILE

1000 0 1000 2000 3000 4000 5000 6000 7000 FEET

1 .5 0 1 KILOMETER

CONTOUR INTERVAL 20 FEET
DATUM IS MEAN SEA LEVEL

VILLAGE

WELL NO. / TAG NO. 5-90 (For Driller's Use)

This report must be completed and submitted to the Department of Environmental Conservation 103 South Main Street (10N), Waterbury, VT 05676 no later than 60 days after completion of the well.

State of Vermont
Dept. of Environmental Conservation
103 South Main Street (10N)
Waterbury, Vt. 05676

WELL COMPLETION REPORT

SEP 23 1991

Location map attached to WCR ____

DEPARTMENT USE ONLY
E.C. 19 U.S.G.S. ____
Field Location ☐ Map area 2684
Latitude ____ ° ' " Elev. ____
Longitude ____ ° ' " Topo. ____
Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐
Data in Town Files ☐

1. WELL OWNER Mr. + Mrs. B. Alexander, 100 Meadow St., Rutland, Vt.
(Name) (Permanent Mailing Address)
OR
WELL PURCHASER ____
(Name) (Permanent Mailing Address)

2. LOCATION OF WELL: TOWN Rutland City SUBDIVISION ____ LOT NO. ____

3. DATE WELL WAS COMPLETED 2/12/90

4. PROPOSED USE OF WELL: ☑ Domestic, ☐ Other ____

5. REASON FOR DRILLING WELL: ☑ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other ____

6. DRILLING EQUIPMENT: ☐ Cable Tool, ☑ Rotary with A-P, ☐ Other ____

7. TYPE OF WELL: ☑ Open Hole in Bedrock, ☐ Open End Casing, ☐ Screened or Slotted, ☐ Other ____

8. TOTAL DEPTH OF WELL: 185 feet below land surface.

9. CASING FINISH: ☐ Above ground, Finished, ☑ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other ____

10. CASING DETAILS: Total length 165 ft Length below L.S. 163½ ft Dia. 6 in. Material steel Wt. 17 lb./ft

11. LINER OR INNER CASING DETAILS: Length used ____ ft Diameter ____ in. Material ____ Weight ____ lb./ft

12. METHOD OF SEALING CASING TO BEDROCK: ☑ Drive Shoe, ☐ Grout - type ____, Drilled ____ in. hole ____ ft in Bedrock, ☐ Other ____

13. SCREEN DETAILS: Make and Type ____, Material ____, Length ____ ft, Diameter ____ in., Slot Size ____, Depth to top of screen in feet below land surface ____ ft., Gravel pack if used, Gravel Size or Type ____

14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☑ Compressed Air, for 1 Hours at 20 Gallons per minute
Measured by ☑ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline installed

15. STATIC WATER LEVEL: ____ feet below land surface, Date or Time measured ____, Overflows at ____ G P M

16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☐ No, If Yes, Where ____

17. SPECIAL NOTES: ____

18. WELL LOG

Depth from Land Surface Feet	Depth from Land Surface Feet	Water Bearing	Formation Description	Sketch
Ground Surface	140		Brown sand, stones, boulders	
140	185	✓	White + brown limestone	

19. SITE MAP
Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well. Indicate local street name and subdivision lot number.



20. TESTED YIELD
If the yield was tested at different depths during drilling, list below.

Feet	Gallons Per Minute

WELL DRILLED BY: Charles "Doc" Higgins
P. O. Box 1024
Castleton, VT 05735

DOING BUSINESS AS: ____ (Company or Business Name)

REPORT FILED BY: L. M. DiDio (Authorized Signature)

DATE OF REPORT: 5/90 WELL DRILLERS LIC. NO. 227

WELL NO. / TAG NO. 22-89
(For Driller's Use)

This report must be completed and submitted to the Department of Environmental Conservation 103 South Main Street (10N), Waterbury, Vt 05676 no later than 60 days after completion of the well

State of Vermont
Dept. of Environmental Conservation
103 South Main Street (10N)
Waterbury, Vt. 05676

WELL COMPLETION REPORT

AUG 30 1990

Location map attached to WCR ____

DEPARTMENT USE ONLY
E.C. 17 U.S.G.S. ____
Field Location ☐ Map area 26B4
Latitude ____ ° ' " Elev. ____
Longitude ____ ° ' " Topo. ____
Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐
Data in Town Files ☐

1. WELL OWNER ____ Name ____ Permanent Mailing Address
OR
WELL PURCHASER Mark Stockton Name Mendon Vt Permanent Mailing Address
2. LOCATION OF WELL: TOWN ~~Mendon~~ Rutland City SUBDIVISION ____ LOT NO. ____
3. DATE WELL WAS COMPLETED 6/19/89
4. PROPOSED USE OF WELL: ☑ Domestic, ☐ Other ____
5. REASON FOR DRILLING WELL: ☑ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other ____
6. DRILLING EQUIPMENT: ☐ Cable Tool, ☑ Rotary with A-P, ☐ Other ____
7. TYPE OF WELL: ☑ Open Hole in Bedrock, ☐ Open End Casing, ☐ Screened or Slotted, ☐ Other ____
8. TOTAL DEPTH OF WELL: 275 feet below land surface.
9. CASING FINISH: ☐ Above ground, Finished, ☑ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other ____
10. CASING DETAILS: Total length 240 ft. Length below L.S. 238.5 ft. Dia. 6 in. Material steel Wt. 17 lb./ft.
11. LINER OR INNER CASING DETAILS: Length used ____ ft. Diameter ____ in. Material ____ Weight ____ lb./ft.
12. METHOD OF SEALING CASING TO BEDROCK: ☑ Drive Shoe, ☐ Grout – type ____, Drilled ____ in. hole ____ ft. in Bedrock ☐ Other ____
13. SCREEN DETAILS: Make and Type ____, Material ____, Length ____ ft., Diameter ____ in. Slot Size ____, Depth to top of screen in feet below land surface ____ ft., Gravel pack if used: Gravel Size or Type ____
14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☑ Compressed Air, for 1 Hours at 30 Gallons per minute
Measured by ☑ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline installed
15. STATIC WATER LEVEL: ____ feet below land surface, Date or Time measured ____, Overflows at ____ G.P.M.
16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☐ No, If Yes, Where ____
17. SPECIAL NOTES: ____

18. WELL LOG

Depth from Land Surface Feet	Depth from Land Surface Feet	Water Bearing	Formation Description	Sketch
Ground Surface	200		Brown hard pan and stones	
200	275	✓	Brown and white limestone	

19. SITE MAP
Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well. Indicate local street name and subdivision lot number



20. TESTED YIELD
If the yield was tested at different depths during drilling, list below.

Feet	Gallons Per Minute

WELL DRILLED BY: Charles "Doc" Higgins
DOING BUSINESS AS: P. O. Box 1024, Castleton, VT 05735
Company or Business Name
REPORT FILED BY: C. M. DiTuro
Authorized Signature
DATE OF REPORT: 6-89
WELL DRILLERS LIC. NO. 227

(For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well.

DEPARTMENT OF WATER RESOURCES AND ENVIRONMENTAL ENGINEERING

WELL COMPLETION REPORT

JAN 28 1986

Location map attached to WCR ____

W.R. 14 U.S.G.S. ____

Field Location ☐ Map area 26B1

Latitude ____ ' ____ " Elev. ____

Longitude ____ ' ____ " Topo. ____

Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐

Data in Town Files ☐

1. WELL OWNER ____ (Name) ____ (Permanent Mailing Address) Gleeson Rd.
   OR
   WELL PURCHASER Kingdom Hall of Jehovah's Witnesses (Name) Rutland, Vt. (Permanent Mailing Address)
2. LOCATION OF WELL: TOWN Rutland City SUBDIVISION ____ LOT NO. ____
3. DATE WELL WAS COMPLETED 9-7-85
4. PROPOSED USE OF WELL: ☐ Domestic, ☒ Other Church
5. REASON FOR DRILLING WELL: ☒ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other ____
6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with A-P, ☐ Other ____
7. TYPE OF WELL: ☒ Open Hole in Bedrock, ☐ Open End Casing, ☐ Screened or Slotted, ☐ Other ____
8. TOTAL DEPTH OF WELL: 185 feet below land surface.
9. CASING FINISH: ☒ Above ground, Finished, ☐ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other ____
10. CASING DETAILS: Total length 60 ft. Length below L S 58 ft Dia. 6 in. Material Steel Wt 19 lb./ft.

N/A LINER OR INNER CASING DETAILS: Length used ____ ft. Diameter ____ in. Material ____ Weight ____ lb./ft.

12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☒ Grout - type cement, Drilled ____ in. hole ____ ft in Bedrock ☐ Other ____

N/A SCREEN DETAILS: Make and Type ____, Material ____, Length ____ ft, Diameter ____ in., Slot Size ____, Depth to top of screen in feet below land surface ____ ft, Gravel pack if used: Gravel Size or Type ____

14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☒ Compressed Air, for 4 Hours at 7 Gallons per minute
    Measured by ☒ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline installed
15. STATIC WATER LEVEL: 25 feet below land surface, Date or Time measured ____, Overflows at ____ G.P.M.
16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☐ No, If Yes, Where ____
17. SPECIAL NOTES: grouted 55

18. WELL LOG

Depth from Land Surface Feet	Depth from Land Surface Feet	Water Bearing	Formation Description	Sketch
Ground Surface	0-60		Gravel	
60	185		Limestone	

19. SITE MAP
Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well. Indicate local street name and subdivision lot number



well is 111' from septic.

20. TESTED YIELD
If the yield was tested at different depths during drilling, list below

Feet	Gallons Per Minute

WELL DRILLED BY: Gerald Parker, Jr.

DOING BUSINESS AS: Parker Water Wells (Company or Business Name)

REPORT FILED BY: Gerald Parker (Authorized Signature)

DATE OF REPORT: 1/14/86 WELL DRILLERS LIC. NO. 176

WELL NUMBER

(For Driller's Use)

Form WR-59
Rev. 7-72

2681

State of Vermont
DEPARTMENT OF WATER RESOURCES

WELL COMPLETION REPORT

6
~~137~~ DO NOT FILL IN

(This report must be completed and submitted to the Department of Water Resources, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of well. Complete or line out all blanks.)

WELL OWNER Mr. John LaFountain (Name) Gleason Road Rutland, Vt. 05701 (Mailing Address)

TOWN IN WHICH WELL IS LOCATED: Rutland ~~Town~~ City

DATE WELL WAS COMPLETED: 11/15/1973

(Please locate well on a large scale map to accompany this report. Maps are available on request.)

PROPOSED USE OF WELL: ☒ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial ☐ Other (Specify)

DRILLING EQUIPMENT: ☒ Cable Tool ☒ Rotary ☐ Air Percussion ☐ Other (Specify)

TOTAL DEPTH OF WELL: 107 STATIC WATER LEVEL: 35

CASING DETAILS: Length 107 ft. Diameter 6 in. Material Steel Weight 19 lb./ft.

SCREEN DETAILS: Make Material Length ft. Diameter in. Slot Size

METHOD OF SEALING CASING TO SCREEN OR BEDROCK: Drive shoe

FINAL YIELD TEST: ☐ Bailed, or ☒ Pumped, or ☒ Compressed Air
6 Hours at 7 gallons per minute
Water level during yield test

WELL LOG

Depth From Ground Surface		Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse, color of material, structure (loose, packed, cemented, hard). For example: Surface to 27 ft. fine, packed, yellow sand; to 134 ft. gray granite.
Surface to 89	ft.	Sand, gravel, boulders and quicksand
89 to 94	ft.	Blue clay
94 to 107	ft.	Sand, gravel and boulders
to	ft.	
to	ft.	

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

90	ft.	7	G.P.M.
	ft.		G.P.M.
	ft.		G.P.M.

WATER ANALYSIS: Has water been analyzed? ☐ Yes ☐ No If Yes, Where
Include Analysis

DRILLED BY: Charles Wilkins Allen Moyer (Signature)

DOING BUSINESS AS: Ottauquechee Drilling Co., Inc. Vice President (Company)

DATE OF REPORT: 12/12/1973 WELL DRILLERS LICENSE NO.

5M 7-73

70-005

2684

State of Vermont
DEPARTMENT OF WATER RESOURCES

Form WR-59

WELL COMPLETION REPORT

WR #5 USGS RTW-237
Field Loc ☒ Map Des (Rutland City)
La 43°36'30 Alt 870 TS
Lo 72°56'20 ☐ HU
Scale: 62500☐, 25000☐, 24000☐

mitted to
ate Office
later than

Do not fill in
State Well No. 4336 22
Other No. 72 5731

WELL OWNER McLaughlin (Name) Killington Roe (Mailing Address) Rutland Vt.

WELL DRILLER A & W Artesian Well Co of Vt. Inc (Name) Man. Depot Vt (Mailing Address)

PROPOSED USE OR USES (Check):

☑ Domestic ☐ Agricultural ☑ Business ~~Establishment~~ ☐ Municipal ☐ Industrial

☐ Other (Specify use)

CASING DETAILS (Inside)	YIELD TEST		WATER LEVEL (From land surface) (if possible)	SCREEN DETAILS
Length: 427 Feet	☐ Bailed or ☐ Pumped or ☑ Compressed Air	6 Hours	Static: 130 Feet	Make:
Diameter: 6 Inches		30 GPM	During Yield Test: 420 Feet	Material:
Kind: Steel			DRILLING EQUIPMENT ☐ Cable Tool ☐ Rotary ☐ Air Percussion ☐ Other (specify)	Slot Size Length: Ft.
Weight: 19-45 lbs/p/ft				Diameter: in.
☑ New ☐ Used	Yield: 30 GPM			

TOTAL DEPTH OF WELL 430 FEET TOWN WELL IS LOCATED IN: Rutland
(Make sketch of well location on reverse side of sheet)

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse) color of material, structure (loose, packed, cemented, hard). For example: 0 ft. to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.
0 ft. to 90 ft.	Hardpan & Packed Gravel
90 ft. to 170 ft.	Limestone
170 ft. to 415 ft.	Hardpan Dry
415 ft. to ft.	
ft. to 430 ft.	Gravel.

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

ft.	G.P.M.
ft.	G.P.M.
ft.	G.P.M.

Has sample of well water been analyzed?

Where was sample analyzed?
(Include analysis of sample if analyzed by other than Department of Water Resources.)

Date Well was Completed 4-9-'71 Date of Report

Water Well Driller's License No. 16 Well Driller Pete Rotti mgr. (signature)

CC 070004

26 B 1

State of Vermont
DEPARTMENT OF WATER RESOURCES

Form WR-59

WELL COMPLETION REPORT

(This report must be completed and submitted to the Department of Water Resources, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of well.)

Do not fill in
State Well No. 4336 41
Other No. 12 07 40

WELL OWNER Mr. Garth Guyette (Name) Gleason Road Rutland, Vt. 05701 (Mailing Address)

WELL DRILLER Ottauquechee Drilling Co., Inc. (Name) West Bridgewater, Vt. 05035 (Mailing Address)

672 5020

PROPOSED USE OR USES (Check):

☒ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial

☐ Other (Specify use)

CASING DETAILS (Inside)	YIELD TEST	WATER LEVEL (From land surface) (if possible)	SCREEN DETAILS
Length: 57 Feet	☐ Bailed or ☒ Pumped or ☐ Compressed Air; 12 Hours; 6 GPM	Static: Flowing Feet	Make:
Diameter: 6 Inches		During Yield Test: Feet	Material:
Kind: Steel		DRILLING EQUIPMENT: ☒ Cable Tool ☐ Rotary ☐ Air Percussion ☐ Other (specify)	Slot Size; Length: Ft.
Weight: 19 lbs/p/ft			Diameter: in.
☒ New ☐ Used	Yield: 6 GPM		

TOTAL DEPTH OF WELL 57 FEET

TOWN WELL IS LOCATED IN: Rutland City ~~Towne~~
(Make sketch of well location on reverse side of sheet)

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse) color of material, structure (loose, packed, cemented, hard). For example: 0 ft. to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.
0 ft. to 41 ft.	Fine sand, muck, cobbles and boulders.
41 ft. to 57 ft.	Sand and gravel.
ft. to ft.	
ft. to ft.	
ft. to ft.	

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

30 ft.	6 G.P.M.
ft.	G.P.M.
ft.	G.P.M.

Has sample of well water been analyzed?

Where was sample analyzed?
(Include analysis of sample if analyzed by other than Department of Water Resources.)

Date Well was Completed 2/15/71

Date of Report 3/15/71

Water Well Driller's License No. 6

Well Driller Lloyd W. Boyer Bros. (signature)

WELL NO. / TAG NO.

254
(For Driller's Use)

This report must be completed and submitted to the Department of Environmental Conservation 103 South Main Street (10N), Waterbury, Vt. 05676 no later than 60 days after completion of the well.

State of Vermont
Dept. of Environmental Conservation
103 South Main Street (10N)
Waterbury, Vt. 05676

WELL COMPLETION REPORT

FEB 3 1989

Location map attached to WCR ____

DEPARTMENT USE ONLY

E.C. 441 U.S.G.S ____
Field Location ☐ Map area 36B4
Latitude ____ ° ' " Elev ____
Longitude ____ ° ' " Topo ____
Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐
Data in Town Files ☐

1. WELL OWNER David Stone (Name) Townline Rd., Rutland, VT. 05701 (Permanent Mailing Address)
OR
WELL PURCHASER ____ (Name) ____ (Permanent Mailing Address)

2. LOCATION OF WELL: TOWN Rutland SUBDIVISION ____ LOT NO. ____

3. DATE WELL WAS COMPLETED 12/19/88

4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other ____

5. REASON FOR DRILLING WELL: ☒ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other ____

6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with A-P, ☐ Other ____

7. TYPE OF WELL: ☒ Open Hole in Bedrock, ☐ Open End Casing, ☐ Screened or Slotted, ☐ Other ____

8. TOTAL DEPTH OF WELL: 800 feet below land surface

9. CASING FINISH: ☐ Above ground, Finished ☒ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other ____

10. CASING DETAILS: Total length 101 ft Length below L S 99 ft Dia 6 in Material steel wt 17 lb./ft

11. LINER OR INNER CASING DETAILS: Length used ____ ft Diameter ____ in Material ____ Weight ____ lb./ft

12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☐ Grout - Type ____, Drilled ____ in hole ____ ft in Bedrock ☐ Other ____

13. SCREEN DETAILS: Make and Type ____, Material ____, Length ____ ft, Diameter ____ in., Slot Size ____, Depth to top of screen in feet below land surface ____ ft, Gravel pack if used Gravel Size or Type ____

14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☒ Compressed Air, for 2 Hours at 2 Gallons per minute
Measured by ☒ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline installed

15. STATIC WATER LEVEL: 130 feet below land surface, Date or Time measured 12/20/88, Overflows at ____ G P M

16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☒ No, If Yes, Where ____

17. SPECIAL NOTES: ____

18. WELL LOG

Depth from Land Surface Feet	Depth from Land Surface Feet	Water Bearing	Formation Description	Sketch
Ground Surface	67		LOAMY SAND & BOULDERS	
67	78		COARSE GRAVEL & OCHER	
78	800	X	GRAY LIMESTONE	

19. SITE MAP
Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well. Indicate local street name and subdivision lot number.



20. TESTED YIELD
If the yield was tested at different depths during drilling, list below.

Feet	Gallons Per Minute
800	2

WELL DRILLED BY: CARLTON MOREY

DOING BUSINESS AS: MOREY WELL DRILLING (Company or Business Name)

REPORT FILED BY: ____ (Authorized Signature)

DATE OF REPORT: 12/20/88 WELL DRILLERS LIC. NO 196

WELL NO. / TAG NO.
1988-72
(For Driller's Use)

This report must be completed and submitted to the Department of Environmental Conservation 103 South Main Street (10N), Waterbury, VT 05676 no later than 60 days after completion of the well.

State of Vermont
Dept. of Environmental Conservation
103 South Main Street (10N)
Waterbury, Vt. 05676

WELL COMPLETION REPORT

NOV 16 1988

DEPARTMENT USE ONLY
E.C. 435 U.S.G.S. _____
Field Location ☐ Map area 26b4
Latitude _____ ° _____ ' _____ " Elev. _____
Longitude _____ ° _____ ' _____ " Topo. _____
Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐
Location map attached to WCR 432 Data in Town Files ☐

1. WELL OWNER David Fucci (Name) Box 117 Rutland, VT. (Permanent Mailing Address)
OR
WELL PURCHASER _____ (Name) _____ (Permanent Mailing Address)

2. LOCATION OF WELL: TOWN Rutland Town SUBDIVISION Grand View Acres LOT NO. _____

3. DATE WELL WAS COMPLETED 9-16-88

4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other _____

5. REASON FOR DRILLING WELL: ☒ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other _____

6. DRILLING EQUIPMENT: ☐ Cable Tool ☒ Rotary with A-P, ☐ Other _____

7. TYPE OF WELL: ☐ Open Hole in Bedrock, ☒ Open End Casing, ☐ Screened or Slotted, ☐ Other _____

8. TOTAL DEPTH OF WELL: 308 feet below land surface.

9. CASING FINISH: ☐ Above ground, Finished, ☒ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other _____

10. CASING DETAILS: Total length 310 ft. Length below L.S. 308 ft. Dia. 6 in. Material Steel Wt. 17 lb./ft.

11. LINER OR INNER CASING DETAILS: Length used _____ ft. Diameter _____ in. Material _____ Weight _____ lb./ft.

12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☐ Grout – type _____, Drilled 8¾ in. hole 113 ft in Bedrock ☐ Other _____

13. SCREEN DETAILS: Make and Type _____, Material _____, Length _____ ft., Diameter _____ in., Slot Size _____, Depth to top of screen in feet below land surface _____ ft., Gravel pack if used: Gravel Size or Type _____

14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☒ Compressed Air, for 2 Hours at 20 Gallons per minute
Measured by ☒ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline installed

15. STATIC WATER LEVEL: 35 feet below land surface, Date or Time measured 9-17-88, Overflows at _____ G.P.M.

16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☒ No, If Yes, Where _____

17. SPECIAL NOTES: _____

18. WELL LOG

Depth from Land Surface Feet	Depth from Land Surface Feet	Water Bearing	Formation Description	Sketch
Ground Surface	195		Glacial Till	
195	308	V	Fractured Dolomite	

19. SITE MAP
Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well. Indicate local street name and subdivision lot number.



20. TESTED YIELD
If the yield was tested at different depths during drilling, list below.

Feet	Gallons Per Minute

WELL DRILLED BY: Ray & Jeff Leonard
DOING BUSINESS AS: Green Mt. Drilling Co., Inc. (Company or Business Name)
REPORT FILED BY: Raymond L. Leonard Jr. (Authorized Signature)
DATE OF REPORT: 9-18-88 WELL DRILLERS LIC. NO. 51

WELL NUMBER

1986-97

(For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well.

State of Vermont

DEPARTMENT OF WATER RESOURCES AND ENVIRONMENTAL ENGINEERING

WELL COMPLETION REPORT

WATER RESOURCE USE ONLY

W.R. 381 U.S.G.S. _____

Field Location ☐ Map area _____

Latitude _____ ° _____ ' _____ " Elev. _____

Longitude _____ ° _____ ' _____ " Topo. _____

Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐

Location map attached to WCR 328 Data in Town Files ☐

1. WELL OWNER Keith Young (Name) Chasanna Dr. Rutland, Vt. (Permanent Mailing Address)
   OR
   WELL PURCHASER _____ (Name) _____ (Permanent Mailing Address)
2. LOCATION OF WELL: TOWN Rutland Town SUBDIVISION _____ LOT NO. _____
3. DATE WELL WAS COMPLETED 10-27-86
4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other _____
5. REASON FOR DRILLING WELL: ☒ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other _____
6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with A-P, ☐ Other _____
7. TYPE OF WELL: ☒ Open Hole in Bedrock, ☐ Open End Casing, ☐ Screened or Slotted; ☐ Other _____
8. TOTAL DEPTH OF WELL: 140 feet below land surface.
9. CASING FINISH: ☐ Above ground, Finished, ☒ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other _____
10. CASING DETAILS: Total length 60 ft. Length below L.S. 58'6" Dia. 6 in. Material Steel Wt 17 lb./ft.
11. LINER OR INNER CASING DETAILS: Length used _____ ft. Diameter _____ in. Material _____ Weight _____ lb./ft.
12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☐ Grout – type _____, Drilled 8 3/4 in. hole 13'6" ft. in Bedrock ☐ Other _____
13. SCREEN DETAILS: Make and Type _____, Material _____, Length _____ ft, Diameter _____ in. Slot Size _____, Depth to top of screen in feet below land surface _____ ft., Gravel pack if used: Gravel Size or Type _____
14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☒ Compressed Air, for 1 Hours at 50 Gallons per minute Measured by ☒ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline installed
15. STATIC WATER LEVEL: 15 feet below land surface, Date or Time measured 10-28-86 Overflows at _____ G.P.M.
16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☒ No, If Yes, Where _____
17. SPECIAL NOTES: _____
18. WELL LOG

Depth from Land Surface Feet	Depth from Land Surface Feet	Water Bearing	Formation Description	Sketch
Ground Surface	20		SAND	
20	45		GLACIAL TILL	
45	140	✓	DUNHAM DOLOMITE	
	118	✓	LG. FRACTURE W/WATER	

19. SITE MAP

Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well indicate local street name and subdivision lot number.



20. TESTED YIELD

If the yield was tested at different depths during drilling, list below.

Feet	Gallons Per Minute

WELL DRILLED BY: Ray & Jeff Leonard

DOING BUSINESS AS: Green Mt. Drilling Co., Inc. (Company or Business Name)

REPORT FILED BY: Raymond L. Leonard Jr. (Authorized Signature)

DATE OF REPORT: 11-8-86 WELL DRILLERS LIC. NO. 51

WELL NUMBER

1986-38

(For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well

State of Vermont

DEPARTMENT OF WATER RESOURCES AND ENVIRONMENTAL ENGINEERING

WELL COMPLETION REPORT

JUN 13 1986

Location map attached to WCR 365

WATER RESOURCE USE ONLY

W.R. 368 U.S.G.S. ____

Field Location ☐ Map area 26B4

Latitude ___ ° ___ ' ___ " Elev. ____

Longitude ___ ° ___ ' ___ " Topo. ____

Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐

Data In Town Files ☐ ____

1. WELL OWNER Chris Ficci (Name) West View Terr. Rutland, Vt. (Permanent Mailing Address)
   OR
   WELL PURCHASER David Ficci (Name) Box 117 Rutland, Vt (Permanent Mailing Address)
2. LOCATION OF WELL: TOWN Rutland Town SUBDIVISION ____ LOT NO. ____
3. DATE WELL WAS COMPLETED 5-27-86
4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other ____
5. REASON FOR DRILLING WELL ☒ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other ____
6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with Air, ☐ Other ____
7. TYPE OF WELL: ☐ Open Hole in Bedrock ☒ Open End Casing, ☐ Screened or Slotted, ☐ Other ____
8. TOTAL DEPTH OF WELL: 240 feet below land surface
9. CASING FINISH: ☐ Above ground, Finished ☒ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other ____
10. CASING DETAILS: Total length 242 ft., Length below LS 240 ft. Dia. 6 in. Material Steel wt. 17 lb./ft.
11. LINER OR INNER CASING DETAILS: Length used ____ ft. Diameter ____ in. Material ____ Weight ____ lb./ft.
12. METHOD OF SEALING CASING TO BEDROCK ☒ Drive Shoe, ☐ Grout - type ____, Drilled $8\frac{3}{4}$ in. hole 29 ft. in Bedrock ☐ Other ____
13. SCREEN DETAILS: Make and Type ____ Material ____ Length ____ ft., Diameter ____ in., Slot Size ____, Depth to top of screen in feet below land surface ____ ft., Gravel pack Used, Gravel Size or Type ____
14. YIELD TEST: ☐ Bailed, ☐ Pumped ☒ Compressed Air, for 1 hours at 7½ Gallons per minute
    Measured by ☒ Bucket, ☐ ____, ☐ Wier ☐ Meter ☐ Permanent Airline installed
15. STATIC WATER LEVEL: ____ feet below land surface, Date ____ measured ____ Overflows at ____ G.P.M.
16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☒ No, If Yes, Where ____
17. SPECIAL NOTES: ____
18. WELL LOG

Depth from Land Surface Feet	Feet	Water Bearing	Formation Description	Sketch
Ground Surface	211		Glacial Till w/Boulders	
211	240	✓	Fractured Dolomite	

19. SITE MAP
Show permanent structure such as buildings, septic tanks, and/or other land marks and in scale not less than two distances to the well. Indicate road, street name and subdivision lot number.



20. TESTED YIELD
If the yield was tested at different depths during drilling, list below

Feet	Gallons Per Minute

WELL DRILLED BY: Ray & Jeff Leonard

DOING BUSINESS AS: Green Mt. Drilling Co, Inc. (Company or Business Name)

REPORT FILED BY Raymond L. Leonard Jr. (Authorized Signature)

DATE OF REPORT 6-12-86 WELL DRILLERS LIC NO 51

Well #1
(For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well

DEPARTMENT OF WATER RESOURCES AND ENVIRONMENTAL ENGINEERING
WELL COMPLETION REPORT

DEC 29 1986

Location map attached to WCR ____

W.R. 360 U.S.G.S. ____
Field Location ☐ Map area 26B1
Latitude ____ ° ' " Elev. ____
Longitude ____ ° ' " Topo. ____
Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐
Data in Town Files ☐

1 WELL OWNER Rick Hackett (Name) Susan Lane Rutland, Vt 05701 (Permanent Mailing Address)
OR
WELL PURCHASER ____ (Name) ____ (Permanent Mailing Address)

2. LOCATION OF WELL: TOWN Rutland SUBDIVISION ____ LOT NO. ____
3. DATE WELL WAS COMPLETED 5-10-85
4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other ____
5. REASON FOR DRILLING WELL: ☒ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other ____
6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with A-P, ☐ Other ____
7. TYPE OF WELL: ☒ Open Hole in Bedrock, ☐ Open End Casing, ☐ Screened or Slotted, ☐ Other ____
8. TOTAL DEPTH OF WELL: 125 feet below land surface.
9. CASING FINISH: ☒ Above ground, Finished, ☐ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other ____
10. CASING DETAILS: Total length 110 ft Length below L.S 108 ft Dia. 6 in. Material Steel wt 17 lb/ft.
NA LINER OR INNER CASING DETAILS: Length used ____ ft. Diameter ____ in. Material ____ Weight ____ lb./ft.
12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☐ Grout - type ____, Drilled ____ in hole ____ ft. in Bedrock ☐ Other ____
NA SCREEN DETAILS: Make and Type ____, Material ____, Length ____ ft., Diameter ____ in. Slot Size ____, Depth to top of screen in feet below land surface ____ ft, Gravel pack if used: Gravel Size or Type ____
14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☐ Compressed Air, for ____ Hours at ____ Gallons per minute Measured by ☐ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline Installed
15. STATIC WATER LEVEL: ____ feet below land surface, Date or Time measured ____, Overflows at ____ G.P.M
16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☐ No, If Yes, Where ____
17. SPECIAL NOTES: ____

18. WELL LOG

Depth from Land Surface Feet	Depth from Land Surface Feet	Water Bearing	Formation Description	Sketch
Ground Surface	66		SAND	
66	104		Broken up Lime Stone	
104	125		Mud Seams	

19. SITE MAP
Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well. Indicate local street name and subdivision lot number.



20. TESTED YIELD
If the yield was tested at different depths during drilling, list below

Feet	Gallons Per Minute

WELL DRILLED BY: Gerald Parker, Jr.
DOING BUSINESS AS: Parker Water Wells (Company or Business Name)
REPORT FILED BY: Gerald E. Parker Jr. (Authorized Signature)
DATE OF REPORT: 1/14/86 WELL DRILLERS LIC. NO. 17

WELL NUMBER

1985-94

(For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well.

State of Vermont

DEPARTMENT OF WATER RESOURCES AND ENVIRONMENTAL ENGINEERING

WELL COMPLETION REPORT

DEC 09 1985

Location map attached to WCR 357 Data in Town Files ☐

WATER RESOURCE USE ONLY

W.R. 364 U.S.G.S. _____

Field Location ☐ Map area 26B4

Latitude _____ ° _____ ' _____ " Elev. _____

Longitude _____ ° _____ ' _____ " Topo. _____

Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐

1. WELL OWNER Arthur Chisolm (Name) East Ridge Terrace (Permanent Mailing Address) Rutland Town, VT.

OR

WELL PURCHASER David Fucci (Name) Box 117 (Permanent Mailing Address) Rutland, VT. OK.

2. LOCATION OF WELL: TOWN Rutland Town SUBDIVISION Grand View Acres LOT NO. _____

3. DATE WELL WAS COMPLETED 11-19-85

4. PROPOSED USE OF WELL: X Domestic, ☐ Other _____

5. REASON FOR DRILLING WELL: X New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other _____

6. DRILLING EQUIPMENT: ☐ Cable Tool, X Rotary with A-P, ☐ Other _____

7. TYPE OF WELL: X Open Hole in Bedrock, ☐ Open End Casing, ☐ Screened or Slotted, ☐ Other _____

8. TOTAL DEPTH OF WELL: 400 Feet below land surface

9. CASING FINISH: ☐ Above ground, Finished, X Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other _____

10. CASING DETAILS: Total Length 161 ft. Length Below LS 159-6" ft. Dia 6 in. Material Steel at 18 lb./ft.

11. LINER OR INNER CASING DETAILS: Length used _____ ft. Diameter _____ in. Material _____ Weight _____ lb./ft.

12. METHOD OF SEALING CASING TO BEDROCK: X Drive Shoe, ☐ Grout - type _____ Drilled 8¾ in hole 19'-6" ft. in Bedrock ☐ Other _____

13. SCREEN DETAILS: Make and Type _____ Material _____ Length _____ ft., Diameter _____ in., Slot Size _____, Depth to top of screen in feet below land surface _____ ft., Gravel packed Gravel Size or Type _____

14. YIELD TEST: ☐ Bailed, ☐ Pumped X Compressed Air, for 1 hours at 2½ Gallons per minute. Measured by X Gauge, ☐ Weir, ☐ Pitot, ☐ Auger, ☐ Meter. ☐ Permanent Airline installed

15. STATIC WATER LEVEL 100 feet below land surface, Date Measured 11-20-85, Overflow at _____ G.P.M.

16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes X No, If Yes Where _____

17. SPECIAL NOTES: _____

18. WELL LOG

Depth from Land Surface Feet	Feet	Water Bearing	Formation Description	Sketch
Ground Surface	120		Glacial Till w/ Boulders	
120	140		Ocre	
140	400	V	Dunham Dolomite	

19. SITE MAP

Show permanent structure such as buildings, septic tanks, and/or other significant geographic features less than two distances to the well and color, road, street name and building number.



20. TESTED YIELD

If the yield was tested at different depths during the test, show below

Feet	Gallons Per Minute

WELL DRILLED BY: Ray & Jeff Leonard

DOING BUSINESS AS: Green Mt. Drilling Co., Inc. (Company or Business Name)

REPORT FILED BY: Raymond L. Leonard Jr. (Name & Title Signature)

DATE OF REPORT 11-26-85 WELL DRILLERS LIC. NO 51

WELL NUMBER _____ (For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well.

State of Vermont

DEPARTMENT OF WATER RESOURCES AND ENVIRONMENTAL ENGINEERING

WELL COMPLETION REPORT

FEB 11 1986

Location map attached to WCR _____

WATER RESOURCE USE ONLY

W.R. 362 U.S.G.S. _____

Field Location ☐ Map area 216B4

Latitude _____ ° ' " Elev. _____

Longitude _____ ° ' " Topo. _____

Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐

Data in Town Files ☐ _____

1. WELL OWNER _____ (Name) (Permanent Mailing Address)
   OR
   WELL PURCHASER Dave Stone (Name) West Ridge Terr. Rutland, Vt. (Permanent Mailing Address)
2. LOCATION OF WELL: TOWN Rutland SUBDIVISION _____ LOT NO. _____
3. DATE WELL WAS COMPLETED 11-2-85
4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other _____
5. REASON FOR DRILLING WELL: ☒ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other _____
6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with A-P, ☐ Other _____
7. TYPE OF WELL: ☒ Open Hole in Bedrock, ☐ Open End Casing, ☐ Screened or Slotted, ☐ Other _____
8. TOTAL DEPTH OF WELL: 300 feet below land surface.
9. CASING FINISH: ☒ Above ground, Finished, ☐ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other _____
10. CASING DETAILS: Total length 210 ft. Length below L.S. 208 ft. Dia. 6 in. Material Steel wt 17 lb./ft.
N/A LINER OR INNER CASING DETAILS: Length used _____ ft. Diameter _____ in. Material _____ Weight _____ lb./ft.
12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☐ Grout - type _____, Drilled ____ in. hole ____ ft. in Bedrock ☐ Other _____
N/A SCREEN DETAILS: Make and Type _____, Material _____, Length _____ ft., Diameter _____ in. Slot Size _____, Depth to top of screen in feet below land surface _____ ft., Gravel pack if used: Gravel Size or Type _____
14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☒ Compressed Air, for 4 Hours at 40 Gallons per minute Measured by ☒ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline installe
15. STATIC WATER LEVEL: 50 ft feet below land surface, Date or Time measured _____, Overflows at _____ G.P.M.
16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☐ No, If Yes, Where _____
17. SPECIAL NOTES: _____

18. WELL LOG

Depth from Land Surface: Feet	Feet	Water Bearing	Formation Description	Sketch
Ground Surface	210		mud & SAND	
210	300		Limestone	

19. SITE MAP

Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well. Indicate local street name and subdivision lot number



20. TESTED YIELD

If the yield was tested at different depths during drilling, list below.

Feet	Gallons Per Minute

WELL DRILLED BY: Gerald Parker, Jr.

DOING BUSINESS AS: Parker Water Wells (Company or Business Name)

REPORT FILED BY: Gerald E. Parker, Jr. (Authorized Signature)

DATE OF REPORT: 1/27/86 WELL DRILLERS LIC. NO. 176

WELL NUMBER

(For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well.

State of Vermont

DEPARTMENT OF WATER RESOURCES AND ENVIRONMENTAL ENGINEERING

WELL COMPLETION REPORT

DEC 7 1984

Location map attached to WCR ____ Data in Town Files ☐

WATER RESOURCE USE ONLY

W.R. 348 U.S.G.S. ____

Field Location ☐ Map area 26A3

Latitude ____ ° ____ ' ____ " Elev. ____

Longitude ____ ° ____ ' ____ " Topo. ____

Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐

1. WELL OWNER Name Frank Ciaffi Permanent Mailing Address

OR

WELL PURCHASER Name Permanent Mailing Address

2. LOCATION OF WELL: TOWN Rutland SUBDIVISION ____ LOT NO. ____

3. DATE WELL WAS COMPLETED 7/16/84

4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other ____

5. REASON FOR DRILLING WELL: ☒ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other ____

6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with A-P, ☐ Other ____

7. TYPE OF WELL: ☒ Open Hole in Bedrock, ☐ Open End Casing, ☐ Screened or Slotted, ☐ Other ____

8. TOTAL DEPTH OF WELL: 150 feet below land surface

9. CASING FINISH: ☒ Above ground, Finished, ☐ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other ____

10. CASING DETAILS: Total length 100 ft. Length below L S 98 ft Dia. 6 in Material Steel wt 17 lb /ft

NA LINER OR INNER CASING DETAILS: Length used ____ ft Diameter ____ in Material ____ Weight ____ lb /ft

12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☐ Grout – type ____, Drilled ____ in hole ____ ft in Bedrock ☐ Other ____

NA SCREEN DETAILS: Make and Type ____, Material ____, Length ____ ft, Diameter ____ in, Slot Size ____, Depth to top of screen in feet below land surface ____ ft, Gravel pack if used Gravel Size or Type ____

14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☒ Compressed Air, for 2 Hours at 30 Gallons per minute

Measured by ☒ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline installed

15. STATIC WATER LEVEL: 10 feet below land surface, Date or Time measured ____, Overflows at ____ G P M

16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☒ No, If Yes, Where ____

17. SPECIAL NOTES: ____

18. WELL LOG

Depth from Land Surface Feet	Depth from Land Surface Feet	Water Bearing	Formation Description	Sketch
Ground Surface	50		SAND	
50	100		LAYERS lime STONE	
100	150		Lime STONE	

19. SITE MAP

Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well indicate local street name and subdivision lot number

20. TESTED YIELD

If the yield was tested at different depths during drilling, list below

Feet	Gallons Per Minute

WELL DRILLED BY: Gerald E Parker Jr.

DOING BUSINESS AS: Parker Water Wells (Driller's business name)

REPORT FILED BY: Gerald E Parker Jr. (Authorized Signature)

DATE OF REPORT: 12/6/84 WELL DRILLERS LIC. NO 176

(For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well.

DEPARTMENT OF WATER RESOURCES AND ENVIRONMENTAL ENGINEERING

WELL COMPLETION REPORT

APR 1 1985

Location map attached to WCR 317

W.R. 334 U.S.G.S. _____

Field Location ☐ Map area 1607

Latitude _____ ° ' " Elev. _____

Longitude _____ ° ' " Topo. _____

Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐

Data in Town Files ☐ _____

Well No 18A

1. WELL OWNER (Name) John Martin (Permanent Mailing Address) RFD Center Rutland, Vt. 05736

OR

WELL PURCHASER (Name) _____ (Permanent Mailing Address) _____

2. LOCATION OF WELL: TOWN Rutland SUBDIVISION Flory Heights LOT NO. _____

3. DATE WELL WAS COMPLETED 3-8-85

4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other _____

5. REASON FOR DRILLING WELL: ☐ New Supply, ☒ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other _____

6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with A-P, ☐ Other _____

7. TYPE OF WELL: ☐ Open Hole in Bedrock, ☒ Open End Casing, ☐ Screened or Slotted; ☐ Other _____

8. TOTAL DEPTH OF WELL: 665 feet below land surface.

9. CASING FINISH: ☐ Above ground, Finished, ☒ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other _____

10. CASING DETAILS: Total length 60 ft. Length below L.S 58 ft. Dia. 6 in. Material Drive Steel Wt. 19 lb./ft.

11. N/A LINER OR INNER CASING DETAILS: Length used _____ ft. Diameter _____ in. Material _____ Weight _____ lb./ft.

12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☐ Grout - type _____, Drilled ____ in hole ____ ft in Bedrock ☐ Other _____

13. N/A SCREEN DETAILS: Make and Type _____, Material _____, Length _____ ft, Diameter _____ in, Slot Size _____, Depth to top of screen in feet below land surface _____ ft., Gravel pack if used: Gravel Size or Type _____

14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☒ Compressed Air, for 3 Hours at 1 Gallons per minute Measured by ☒ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline installed

15. STATIC WATER LEVEL: 200 feet below land surface, Date or Time measured 3-11-85, Overflows at _____ G.P.M.

16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☒ No, If Yes, Where _____

17. SPECIAL NOTES: Did not use the well because of low Static Level.

18. WELL LOG

Depth from Land Surface Feet	Depth from Land Surface Feet	Water Bearing	Formation Description	Sketch
Ground Surface	58		Clay & Rocks	
58	570		Black shale	
570	665		Limestone	

19. SITE MAP

Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well. Indicate local street name and subdivision lot number



20. TESTED YIELD

If the yield was tested at different depths during drilling, list below

Feet	Gallons Per Minute

WELL DRILLED BY: Gerald Parker Jr.

DOING BUSINESS AS: Parker Water Wells (Company or Business Name)

REPORT FILED BY: Gerald Parker Jr. (Authorized Signature)

DATE OF REPORT: 3/25/85 WELL DRILLERS LIC. NO. 176

WELL NUMBER
1984-43
(For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well.

State of Vermont
DEPARTMENT OF WATER RESOURCES
AND ENVIRONMENTAL ENGINEERING
WELL COMPLETION REPORT

SEP 17 1984

WATER RESOURCE USE ONLY
W.R. 310 U.S.G.S. ____
Field Location ☐ Map area 26B4
Latitude ____ ° ' " Elev. ____
Longitude ____ ° ' " Topo. ____
Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐
Location map attached to WCR ____ Data in Town Files ☐

1. WELL OWNER Frank Breen (Name) Susan Lane (Permanent Mailing Address) Rutland Town, Vt.
OR
WELL PURCHASER David Fucci (Name) David Rd. (Permanent Mailing Address) Rutland Town, Vt.
2. LOCATION OF WELL: TOWN Rutland Town SUBDIVISION Grand View Acres LOT NO. ____
3. DATE WELL WAS COMPLETED 7-24-84
4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other ____
5. REASON FOR DRILLING WELL: ☒ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other ____
6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with A-P, ☐ Other ____
7. TYPE OF WELL: ☒ Open Hole in Bedrock, ☐ Open End Casing, ☐ Screened or Slotted; ☐ Other ____
8. TOTAL DEPTH OF WELL: 200 feet below land surface.
9. CASING FINISH: ☐ Above ground, Finished, ☒ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other ____
10. CASING DETAILS: Total length 181 ft. Length below L.S. 179 ft. Dia. 6 in. Material Steel Wt 17 lb./ft.
11. LINER OR INNER CASING DETAILS: Length used ____ ft. Diameter ____ in. Material ____ Weight ____ lb./ft.
12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☐ Grout - type ____ Drilled 8 3/4 in hole 8 ft in Bedrock ☐ Other ____
13. SCREEN DETAILS: Make and Type ____ Material ____ Length ____ ft, Diameter ____ in, Slot Size ____, Depth to top of screen in feet below land surface ____ ft., Gravel pack if used: Gravel Size or Type ____
14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☒ Compressed Air, for 2 Hours at 100 Gallons per minute
Measured by ☒ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline Installed
15. STATIC WATER LEVEL: 95 feet below land surface, Date or Time measured 7-24-84 Overflows at ____ G.P.M.
16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☒ No, If Yes, Where ____
17. SPECIAL NOTES: ____

18. WELL LOG

Depth from Land Surface: Feet	Feet	Water Bearing	Formation Description	Sketch
Ground Surface	171		Glacial Till	
171	190		Dunham Dolomite	
190	200	L	Fractured Dolomite	

19. SITE MAP
Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distance to the well indicate local street name and subdivision lot number



20. TESTED YIELD
If the yield was tested at different depths during drilling, list below

Feet	Gallons Per Minute

WELL DRILLED BY: Ray E' Jeff Leonard
DOING BUSINESS AS: Green Mt. Drilling Co., Inc. (Company or Business Name)
REPORT FILED BY: Raymond L. Leonard Jr. (Authorized Signature)
DATE OF REPORT: 8-4-84 WELL DRILLERS LIC. NO. 51

WELL NUMBER

1984 - 21

(For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well.

State of Vermont

DEPARTMENT OF WATER RESOURCES AND ENVIRONMENTAL ENGINEERING

WELL COMPLETION REPORT

JUL 11 1984

Location map attached to WCR ____

WATER RESOURCE USE ONLY

W.R. 307 U.S.G.S. ____

Field Location ☐ Map area 26 A 3

Latitude ____ ° ____ ' ____ " Elev. ____

Longitude ____ ° ____ ' ____ " Topo. ____

Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐

Data in Town Files ☐

1. WELL OWNER ERNEST McKIRRYHER (Name) RFD (Permanent Mailing Address) RUTLAND, VT.

OR

WELL PURCHASER ____ (Name) ____ (Permanent Mailing Address)

2. LOCATION OF WELL: TOWN RUTLAND TOWN SUBDIVISION ____ LOT NO. ____

3. DATE WELL WAS COMPLETED 5-9-84

4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other ____

5. REASON FOR DRILLING WELL: ☒ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other ____

6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with A-P, ☐ Other ____

7. TYPE OF WELL: ☒ Open Hole in Bedrock, ☐ Open End Casing, ☐ Screened or Slotted, ☐ Other ____

8. TOTAL DEPTH OF WELL: 405 feet below land surface.

9. CASING FINISH: ☐ Above ground, Finished, ☒ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other ____

10. CASING DETAILS: Total length 138 ft. Length below L.S. 136 ft. Dia. 6 in. Material STEEL Wt 17 lb./ft.

11. LINER OR INNER CASING DETAILS: Length used ____ ft. Diameter ____ in. Material ____ Weight ____ lb./ft.

12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☐ Grout - type ____, Drilled 8¾ in hole 55 ft in Bedrock ☐ Other ____

13. SCREEN DETAILS: Make and Type ____, Material ____, Length ____ ft., Diameter ____ in., Slot Size ____, Depth to top of screen in feet below land surface ____ ft., Gravel pack if used: Gravel Size or Type ____

14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☒ Compressed Air, for 1 Hours at 2 Gallons per minute

Measured by ☒ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline Installed

15. STATIC WATER LEVEL: 30 feet below land surface, Date or Time measured 5-10-84, Overflows at ____ G P M

16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes, ☒ No, If Yes, Where ____

17. SPECIAL NOTES: ____

18. WELL LOG

Depth from Land Surface Feet	Depth from Land Surface Feet	Water Bearing	Formation Description	Sketch
Ground Surface	75		GLACIAL TILL	
75	85		OCRE	
85	115		ROTTEN LEDGE W/OCRE SEAMS	
115	315	V	DUNHAM DOLOMITE	
315	340		GRAY QUARTZ	
340	405	V	DUNHAM DOLOMITE	

19. SITE MAP

Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well. Indicate local street name and subdivision lot number



20. TESTED YIELD

If the yield was tested at different depths during drilling, list below.

Feet	Gallons Per Minute
280	½
330	½

WELL DRILLED BY: RAY & JEFF LEONARD

DOING BUSINESS AS: GREEN MT. DRILLING CO., INC. (Company or Business Name)

REPORT FILED BY: Raymond L. Leonard Jr. (Authorized Signature)

DATE OF REPORT: 5-9-84 WELL DRILLERS LIC. NO. 51

WELL NUMBER

(For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well.

State of Vermont

DEPARTMENT OF WATER RESOURCES AND ENVIRONMENTAL ENGINEERING

WELL COMPLETION REPORT

DEC 9 1983

Location map attached to WCR ____

WATER RESOURCE USE ONLY

W.R. 296 U.S.G.S. ____

Field Location ☐ Map area 26B1

Latitude ____ ° ____ ' ____ " Elev. ____

Longitude ____ ° ____ ' ____ " Topo. ____

Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐

Data in Town Files ☐

1. WELL OWNER ____ (Name) ____ (Permanent Mailing Address)

OR

WELL PURCHASER Tim Raymond (Name) Massey St. Rutland, VT. (Permanent Mailing Address)

2. LOCATION OF WELL: TOWN Rutland SUBDIVISION ____ LOT NO. ____

3. DATE WELL WAS COMPLETED 4/6/83

4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other ____

5. REASON FOR DRILLING WELL: ☒ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other ____

6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with A-P, ☐ Other ____

7. TYPE OF WELL: ☒ Open Hole in Bedrock, ☐ Open End Casing, ☐ Screened or Slotted, ☐ Other ____

8. TOTAL DEPTH OF WELL: 255 feet below land surface.

9. CASING FINISH: ☒ Above ground, Finished, ☐ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other ____

10. CASING DETAILS: Total length 120 ft. Length below L.S 115 ft Dia. 6 in Material Steel Wt 17 lb/ft

N/A LINER OR INNER CASING DETAILS: Length used ____ ft Diameter ____ in Material ____ Weight ____ lb/ft.

12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☐ Grout - type ____, Drilled ____ in hole ____ ft in Bedrock ☐ Other ____

N/A 13. SCREEN DETAILS: Make and Type ____, Material ____, Length ____ ft, Diameter ____ in, Slot Size ____, Depth to top of screen in feet below land surface ____ ft., Gravel pack if used Gravel Size or Type ____

14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☐ Compressed Air, for 2 Hours at 10 Gallons per minute

Measured by ☐ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline Installed

15. STATIC WATER LEVEL: 50' feet below land surface, Date or Time measured ____, Overflows at ____ G P M

16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☐ No, If Yes, Where ____

17. SPECIAL NOTES: ____

18. WELL LOG

Depth from Land Surface Feet	Depth from Land Surface Feet	Water Bearing	Formation Description	Sketch
Ground Surface	100		CLAY HARD PAN	
100	120		SOFT LIMESTONE	
120	255		QUARTZ LIMESTONE	255

19. SITE MAP

Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well indicate local street name and subdivision lot number



20. TESTED YIELD

If the yield was tested at different depths during drilling, list below

Feet	Gallons Per Minute

WELL DRILLED BY: Harold E Parker Jr.

DOING BUSINESS AS: PARKER WATER WELLS (Company or Business Name)

REPORT FILED BY: Harold E Parker (Authorized Signature)

DATE OF REPORT: ____ WELL DRILLERS LIC. NO. ____

WELL NUMBER
39
(For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well.

State of Vermont
DEPARTMENT OF WATER RESOURCES
AND ENVIRONMENTAL ENGINEERING

WELL COMPLETION REPORT

JUN 7 1983

WATER RESOURCE USE ONLY
W.R. 287 U.S.G.S. _____
Field Location ☐ Map area _____
Latitude _____ ° ' " Elev. _____
Longitude _____ ° ' " Topo. _____
Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐
Location map attached to WCR 286 Data in Town Files ☐

1. WELL OWNER Mike Mayhew (Name) Parkway Rd. Rutland, VT. (Permanent Mailing Address)
OR
WELL PURCHASER _____ (Name) _____ (Permanent Mailing Address)
2. LOCATION OF WELL: TOWN Rutland SUBDIVISION _____ LOT NO. _____
3. DATE WELL WAS COMPLETED 12/10/82
4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other _____
5. REASON FOR DRILLING WELL: ~~☐ New Supply~~, ☒ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other _____
6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with A-P, ☐ Other _____
7. TYPE OF WELL: ☐ Open Hole in Bedrock, ☒ Open End Casing, ☐ Screened or Slotted; ☐ Other _____
8. TOTAL DEPTH OF WELL: 163 feet below land surface.
9. CASING FINISH: ☐ Above ground, Finished, ☒ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other _____
10. CASING DETAILS: Total length 163 ft. Length below L.S. 163 ft. Dia. 6 in. Material steel Wt 19.45 lb./ft. New
11. LINER OR INNER CASING DETAILS: Length used _____ ft. Diameter _____ in. Material _____ Weight _____ lb./ft.
12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☐ Grout - type _____, Drilled ____ in. hole ____ ft. in Bedrock ☐ Other _____
13. SCREEN DETAILS: Make and Type _____, Material _____, Length _____ ft, Diameter _____ in., Slot Size _____, Depth to top of screen in feet below land surface _____ ft., Gravel pack if used: Gravel Size or Type _____
14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☒ Compressed Air, for 2½ Hours at 7 Gallons per minute Measured by ☒ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline installed
15. STATIC WATER LEVEL: _____ feet below land surface, Date or Time measured _____, Overflows at _____ G.P.M
16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☐ No, If Yes, Where _____
17. SPECIAL NOTES: gravel well
18. WELL LOG

Depth from Land Surface		Water Bearing	Formation Description	Sketch
Feet	Feet			
Ground Surface	50		GRAVEL	
50	105		Sand with boulders	
105	156		Sand	
156	163	✓	GRAVEL	

19. SITE MAP
Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well. Indicate local street name and subdivision lot number.

20. TESTED YIELD
If the yield was tested at different depths during drilling, list below.

Feet	Gallons Per Minute
160	7

WELL DRILLED BY: Edward Stromberg
DOING BUSINESS AS: Green Mtn Well Co. Inc.
(Company or Business Name)
REPORT FILED BY: _____ (Authorized Signature)
DATE OF REPORT: 12/13/82 WELL DRILLERS LIC. NO. 53

WELL NUMBER
1976-41
(For Driller's Use)

Form WR-59
Rev. 7-22

State of Vermont
DEPARTMENT OF WATER RESOURCES

WELL COMPLETION REPORT

WR #171 USGS RTW-208
Field Loc ☒ Map Des
La. 43°37'19 Alt 670 TS
Lo. 72°57'03 ☐ HU
Scale: 62500 ☐, 25000 ☐, 24000 ☐

SEP 7 1976

DO NOT FILL IN
#171

WELL OWNER FRANK PFENNING (Name) GLENSON Rd. (Mailing Address) RUTLAND TOWN, VT.

TOWN IN WHICH WELL IS LOCATED: RUTLAND TOWN

DATE WELL WAS COMPLETED: 9-2-76

(Please locate well on a large scale map to accompany this report. Maps are available on request.)

PROPOSED USE OF WELL: ☒ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial ☐ Other (Specify)

DRILLING EQUIPMENT: ☐ Cable Tool ☒ Rotary ☒ Air Percussion ☐ Other (Specify)

TOTAL DEPTH OF WELL: 70 STATIC WATER OVERFLOW TRICKLE

CASING DETAILS: Length 54 ft. Diameter 6 in. Material STEEL
Weight 19.45 lb./ft.

SCREEN DETAILS: Make — Material — Length — ft.
Diameter — in. Slot Size —

METHOD OF SEALING CASING TO SCREEN OR BEDROCK: CAULKING

FINAL YIELD TEST: ☐ Bailed, or ☐ Pumped, or ☒ Compressed Air
1 Hours at 4½ gallons per minute
Water level during yield test

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse, color of material, structure (loose, packed, cemented, hard). For example: Surface to 27 ft. fine, packed, yellow sand; to 134 ft. gray granite.
Surface to 25 ft.	CLAY
25 to 70 ft.	UNCONSOLIDATED QUARTZOM DOLOMITE
to ft.	
to ft.	
to ft.	

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

ft. G.P.M.
ft. G.P.M.
ft. G.P.M.

WATER ANALYSIS: Has water been analyzed? ☐ Yes ☒ No If Yes, Where
Include Analysis

DRILLED BY: Raymond L. Flanders Jr. (Signature)
DOING BUSINESS AS: Green Mt. Drilling Co., Inc. (Company)
DATE OF REPORT: 9-24-76 WELL DRILLERS LICENSE NO. 17

5M 12-73

WELL NUMBER

4

(For Driller's Use)

Form WR-59
Rev. 7-22

State of Vermont
DEPARTMENT OF WATER RESOURCES

WELL COMPLETION REPORT

(This report must be completed and submitted to the Department of Water Resources, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of well. Complete or line out all blanks.)

APR 21 1980

DO NOT FILL IN

950

WELL OWNER Ernest Gibeault (Name) Townline Rd Rutland VT 05701 (Mailing Address)

TOWN IN WHICH WELL IS LOCATED: Rutland

(Please locate well on a large scale map to accompany this report. Maps are available on request.)

DATE WELL WAS COMPLETED: End of Aug 1979

PROPOSED USE OF WELL: ☑ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial ☐ Other (Specify)

DRILLING EQUIPMENT: ☑ Cable Tool ☐ Rotary ☐ Air Percussion ☐ Other (Specify)

TOTAL DEPTH OF WELL: 30 ft. STATIC WATER 5 ft.

CASING DETAILS: Length 30 ft. ft. Diameter 10 in. Material Steel
Weight about 50 lb./ft.

SCREEN DETAILS: Make Material Length ft.
Diameter in. Slot Size

METHOD OF SEALING CASING TO SCREEN OR BEDROCK: No bedrock — worked about 5 yds. of fine sand around outside bottom of well by pumping endless amount of sand out.

FINAL YIELD TEST: ☑ Bailed, or ☑ Pumped, or ☐ Compressed Air
24 Hours at 3½ gallons per minute
Water level during yield test 24 ft

WELL LOG

Depth From Ground Surface

Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse, color of material, structure (loose, packed, cemented, hard). For example: Surface to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.

Surface to 2 ft. Hardpan
2 to 30 ft. Fine sandy clay — Please refer To other side
to ft. Well completed at 30 ft
to ft.

YIELD TEST DATA IN G.P.M.
If yield was tested at different depths during drilling, List Below

G.P.M. @	ft.	G.P.M. @	ft.
G.P.M. @	ft.	G.P.M. @	ft.

WATER ANALYSIS: Has water been analyzed? ☑ Yes ☐ No If Yes, Where
Include Analysis

DRILLED BY: Henry Eager (Signature)

DOING BUSINESS AS: Above (Company)

DATE OF REPORT: Apr 17 1980 WELL DRILLERS LICENSE NO. 159

5M 6-76

TACKBOARD-VILLAGE?

WELL NUMBER
367
(For Driller's Use)

Form WR-59
Rev. 7-22

State of Vermont
DEPARTMENT OF WATER RESOURCES

WELL COMPLETION REPORT

JUN 11 1981

(This report must be completed and submitted to the Department of Water Resources, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of well. Complete or line out all blanks.)

DO NOT FILL IN
258

WELL OWNER Mr. James McLaughlin 46 Lincoln Ave Rutland, VT 05701
Name Mailing Address

TOWN IN WHICH WELL IS LOCATED: Rutland

(Please locate well on a large scale map to accompany this report. Maps are available on request.)

DATE WELL WAS COMPLETED: Nov 17 1980

PROPOSED USE OF WELL: ☒ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial ☐ Other (Specify)

DRILLING EQUIPMENT: ☐ Cable Tool ☐ Rotary ☒ Air Percussion ☐ Other (Specify)

TOTAL DEPTH OF WELL: 205 ft. STATIC WATER 30 ft.

CASING DETAILS: Length 160 ft. Diameter 6 in. Material steel
Weight 19 lb./ft.

SCREEN DETAILS: Make — Material — Length — ft.
Diameter — in. Slot Size —

METHOD OF SEALING CASING TO SCREEN OR BEDROCK: drive shoe

FINAL YIELD TEST: ☐ Bailed, or ☐ Pumped, or ☒ Compressed Air
4 Hours at 100 gallons per minute
Water level during yield test 30 ft

WELL LOG

Depth From Ground Surface

Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse, color of material, structure (loose, packed, cemented, hard). For example: Surface to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.

Surface to 150 ft. hardpan sand + gravel
150 to 205 ft. limestone
to ft.
to ft.

YIELD TEST DATA IN G.P.M.
If yield was tested at different depths during drilling, List Below

G.P.M. @	ft.	G.P.M. @	ft.
G.P.M. @	ft.	G.P.M. @	ft.

WATER ANALYSIS: Has water been analyzed? ☐ Yes ☒ No If Yes, Where
Include Analysis

DRILLED BY: George Rossiter
Signature

DOING BUSINESS AS: Rossiter Water Wells
Company

DATE OF REPORT: Dec 1, 1980 WELL DRILLERS LICENSE NO.

5M 6-76

WELL NUMBER

128

(For Driller's Use)

This report must be completed and submitted to the Department of Water Resources and Environmental Engineering, State Office Building, Montpelier, Vermont 05602, no later than 60 days after completion of the well.

State of Vermont

DEPARTMENT OF WATER RESOURCES AND ENVIRONMENTAL ENGINEERING

WELL COMPLETION REPORT

FEB 27 1981

Location map attached to WCR ____

WATER RESOURCE USE ONLY

W.R. 254 U.S.G.S. ____

Field Location ☐ Map area ____

Latitude ____ ° ____ ' ____ " Elev. ____

Longitude ____ ° ____ ' ____ " Topo. ____

Scale: 62,500 ☐, 25,000 ☐, 24,000 ☐

Data in Town Files ☐

1. WELL OWNER Martin P. Hussey (Name) Permanent Mailing Address

OR

WELL PURCHASER Construction Management Inc. 112 Stratton Rd. Rutland, Vt. 05701 (Name) (Permanent Mailing Address)

2. LOCATION OF WELL: TOWN Rutland Town SUBDIVISION ____ LOT NO. ____

3. DATE WELL WAS COMPLETED 12/24/1980

4. PROPOSED USE OF WELL: ☒ Domestic, ☐ Other ____

5. REASON FOR DRILLING WELL: ☒ New Supply, ☐ Replace Existing Supply, ☐ Deepen Existing Well, ☐ Test or Exploration, ☐ Provide Additional Supply, ☐ Other ____

6. DRILLING EQUIPMENT: ☐ Cable Tool, ☒ Rotary with A-P, ☐ Other ____

7. TYPE OF WELL: ☒ Open Hole in Bedrock, ☒ Open End Casing, ☐ Screened or Slotted, ☐ Other ____

8. TOTAL DEPTH OF WELL: 105 feet below land surface.

9. CASING FINISH: ☐ Above ground, Finished, ☒ Above ground, Unfinished, ☐ Buried, ☐ In Pit, ☐ Removed, ☐ None used, ☐ Other ____

10. CASING DETAILS: Total length 105 ft. Length below L.S ____ ft Dia. 7 in. Material steel wt 23 lb./ft

11. LINER OR INNER CASING DETAILS: Length used ____ ft. Diameter ____ in. Material ____ Weight ____ lb./ft.

12. METHOD OF SEALING CASING TO BEDROCK: ☒ Drive Shoe, ☐ Grout - type ____, Drilled ____ in hole ____ ft. in Bedrock ☐ Other ____

13. SCREEN DETAILS: Make and Type ____, Material ____, Length ____ ft, Diameter ____ in., Slot Size ____, Depth to top of screen in feet below land surface ____ ft., Gravel pack if used: Gravel Size or Type ____

14. YIELD TEST: ☐ Bailed, ☐ Pumped, ☒ Compressed Air, for 1 Hours at 6 Gallons per minute

Measured by ☒ Bucket, ☐ Orifice pipe, ☐ Weir, ☐ Meter ☐ Permanent Airline installed

15. STATIC WATER LEVEL: 22 feet below land surface, Date or Time measured 12/24/80, Overflows at ____ G.P.M.

16. WATER ANALYSIS: Has the water been analyzed? ☐ Yes ☐ No, If Yes, Where ____

17. SPECIAL NOTES: ____

18. WELL LOG

Depth from Land Surface Feet	Depth from Land Surface Feet	Water Bearing	Formation Description	Sketch
Ground Surface	95		Sand & boulders	
95	105	x	Gravel	
			6 gpm @ 80 ft.	

19. SITE MAP

Show permanent structure such as buildings, septic tanks, and/or other land marks and indicate not less than two distances to the well. Indicate local street name and subdivision lot number

N

20. TESTED YIELD

If the yield was tested at different depths during drilling, list below.

Feet	Gallons Per Minute

WELL DRILLED BY: George Spear & Bob Hayward

DOING BUSINESS AS: Ottauquechee Drilling Co., Inc. (Company or Business Name)

REPORT FILED BY: Allen Thayer Jr. (Authorized Signature)

DATE OF REPORT: 1/31/1981 WELL DRILLERS LIC. NO. 6

#137

State of Vermont
DEPARTMENT OF WATER RESOURCES

Form WR-59

WELL COMPLETION REPORT

WR 137 USGS RTW-209
Field Loc ☒ Map Des
La. 43°37' Alt 750 TS
Lo. 72°56' ☐ HU
Scale: 62500☐, 25000☐, 24000☐

nitted to
ite Office
ater than

Do not fill in

WELL OWNER Mr Walter Rydjeski (Name) Elbern Ave Rutland, Vt. (Mailing Address)

WELL DRILLER C. & F. Rabtoy (Name) North Clarendon, Vt. 05759 (Mailing Address)

PROPOSED USE OR USES (Check):

☒ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial
☐ Other (Specify use)

CASTING DETAILS (Inside)	YIELD TEST	WATER LEVEL (From land surface) (if possible)	SCREEN DETAILS
Length: 76 Feet	☒ Bailed or ☐ Pumped or ☐ Compressed Air — 4 Hours — 25 GPM	Static: 4 Feet	Make: None
Diameter: 6 Inches		During Yield Test: 76 Feet	Material:
Kind: Morris pipe		DRILLING EQUIPMENT	Slot Size
Weight: 19 lbs/p/ft		☒ Cable Tool	Length: Ft.
☒ New ☐ Used	Yield: 25 GPM	☐ Rotary ☐ Air Percussion ☐ Other (specify)	Diameter: in.

TOTAL DEPTH OF WELL 76 FEET TOWN WELL IS LOCATED IN: Rutland, Vt.
(Make sketch of well location on reverse side of sheet)

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse) color of material, structure (loose, packed, cemented, hard). For example: 0 ft. to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.
0 ft. to 1 ft.	Loom
1 ft. to 10 ft.	Coarse gravel & boulders.
10 ft. to 63 ft.	Hardpan
63 ft. to 70 ft.	Sand tan
70 ft. to 76 ft.	Gravel. .062 1.250

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

ft.	G.P.M.
ft.	G.P.M.
ft.	G.P.M.

's sample of well water been analyzed? no

here was sample analyzed?
clude analysis of sample if analyzed by other than Department of Water Resources.)

te Well was Completed 6/8/73 Date of Report 7/5/73

ter Well Driller's License No. 41 Well Driller Calvin Rabtoy (signature)

5-71

HAFFACE 7.5'

State of Vermont
DEPARTMENT OF WATER RESOURCES

Form WR-59

WELL COMPLETION REPORT

WR #8 USGS RTW-76
Field Loc ☒ Map Des _____ tted to
La. 43° 39' 32 Alt 720 TS ___ Office
Lo. 73° 00' 05 ☐ HU _____ er than
Scale: 62500☐, 25000☐, 24000☐

Do not fill in
State Well No. N-43° 39' 18"
Other No. W-72° 59' 58"

WELL OWNER Norman S. Baker Name — Plains Road Mailing Address — Pittsford, Vt.

WELL DRILLER Green Mt. Drilling Co., Inc. Name — Center Rutland Mailing Address — Vt.

PROPOSED USE OR USES (Check):

☒ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial

☐ Other (Specify use)

CASTING DETAILS (Inside)	YIELD TEST	WATER LEVEL (From land surface) (if possible)	SCREEN DETAILS
Length: 28 Feet	☐ Bailed or ☐ Pumped or ☒ Compressed Air; 1 Hours; 6 GPM	Static: Feet	Make:
Diameter: 6 Inches		During Yield Test: Feet	Material: None
Kind: Steel		DRILLING EQUIPMENT	Slot Size
Weight: 16 lbs/p/ft		☐ Cable Tool	Length: Ft.
☒ New ☐ Used	Yield: 6 GPM	☒ Rotary ☐ Air Percussion ☐ Other (specify)	Diameter: in.

TOTAL DEPTH OF WELL 97 FEET TOWN WELL IS LOCATED IN: Rutland Town
(Make sketch of well location on reverse side of sheet)

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse) color of material, structure (loose, packed, cemented, hard). For example: 0 ft. to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.
0 ft. to 22 ft.	Med. Sand w/ Boulders
22 ft. to 97 ft.	Quartz
ft. to ft.	
ft. to ft.	
ft. to ft.	

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

ft.	G.P.M.
ft.	G.P.M.
ft.	G.P.M.

Has sample of well water been analyzed? No

Where was sample analyzed?
(Include analysis of sample if analyzed by other than Department of Water Resources.)

Date Well was Completed 2-28-67 Date of Report 3-1-67

Water Well Driller's License No. 51 Well Driller _____ (signature)



State of Vermont
DEPARTMENT OF WATER RESOURCES

Form WR-59

WELL COMPLETION REPORT

WR #7 USGS D-90
Field Loc ☐ Map Des ____ . ted to
La. 43°39'21 Alt 690 TS ____ . Office
Lo. 72°59'18 ☐ HU ____ . r than
Scale: 62500☐, 25000☐, 24000☐

Do not fill in
State Well No. N-43°39'24.7" W-72°59'18.5"
Other No.

WELL OWNER Edward Fenton (Name) Rutland Town, Vt. (Mailing Address)

WELL DRILLER Green Mountain Drilling Co., Inc. (Name) Center Rutland, Vt. (Mailing Address)

PROPOSED USE OR USES (Check):

☒ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial

☐ Other (Specify use)

CASTING DETAILS (Inside)	YIELD TEST	WATER LEVEL (From land surface) (if possible)	SCREEN DETAILS
Length: 50 Feet	☐ Bailed or ☐ Pumped or ☒ Compressed Air; 2 Hours; 5 GPM	Static: 4 Feet	Make:
Diameter: 3 Inches		During Yield Test: Feet	Material: None
Kind: Steel		DRILLING EQUIPMENT: ☐ Cable Tool ☒ Rotary ☐ Air Percussion ☐ Other (specify)	Slot Size; Length: Ft.
Weight: 16 lbs/p/ft			Diameter: in.
☒ New ☐ Used	Yield: 5 GPM		

TOTAL DEPTH OF WELL 128'-0 FEET

TOWN WELL IS LOCATED IN: (Make sketch of well location on reverse side of sheet) Rutland Town

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse) color of material, structure (loose, packed, cemented, hard). For example: 0 ft. to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.
0 ft. to 5 ft.	Sand
5 ft. to 45 ft.	Glacial Till
45 ft. to 128 ft.	Durham Dolomite
ft. to ft.	
ft. to ft.	

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

ft.	G.P.M.
ft.	G.P.M.
ft.	G.P.M.

Has sample of well water been analyzed? No

Where was sample analyzed?
Include analysis of sample if analyzed by other than Department of Water Resources.)

Date Well was Completed 12-14-66 Date of Report 12-24-66

Water Well Driller's License No. 51 Well Driller Lloyd A. Robert (signature)



TOWN 06-071-024

State of Vermont
DEPARTMENT OF WATER RESOURCES

Form WR-59

WELL COMPLETION REPORT

WR #24 USGS RTW-98
Field Loc ☒ Map Des
La. 43°38'07 Alt 620 TS
Lo. 72°58'51 ☐ RU
Scale: 62500☐, 25000☐, 24000☐

mitted to
ate Office
later than

Do not fill in
State Well No. N-43°38'16"
Other No. W-72°59'04"

WELL OWNER Rutland Town Fire Dept. Station #1 (Name) RFD Rutland, Vt. (Mailing Address)

WELL DRILLER Green Mt. Drilling Co., Inc. (Name) Box 26 Ctr, Rutland, Vt. (Mailing Address)

PROPOSED USE OR USES (Check):

☑ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial

☐ Other (Specify use)

CASING DETAILS (Inside)	YIELD TEST	WATER LEVEL (From land surface) (if possible)	SCREEN DETAILS
Length: 31 Feet	☐ Bailed or ☐ Pumped or ☑ Compressed Air; 1 Hours; 1 GPM	Static: 20 Feet	Make: None
Diameter: 6 Inches		During Yield Test: Feet	Material:
Kind: Steel		DRILLING EQUIPMENT	Slot Size
Weight: 16 lbs/p/ft		☐ Cable Tool ☑ Rotary ☐ Air Percussion	Length: Ft.
☑ New ☐ Used	Yield: 1 GPM	☐ Other (specify)	Diameter: in.

TOTAL DEPTH OF WELL 300 FEET TOWN WELL IS LOCATED IN: Rutland Town
(Make sketch of well location on reverse side of sheet)

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse) color of material, structure (loose, packed, cemented, hard). For example: 0 ft. to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.
0 ft. to 25 ft.	Clay
25 ft. to 300 ft.	Dolomite Lt. & Dk. Gray
ft. to ft.	
ft. to ft.	
ft. to ft.	

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

228 ft.	½ G.P.M.
300 ft.	1 G.P.M.
ft.	G.P.M.

Has sample of well water been analyzed? No

Where was sample analyzed?
(Include analysis of sample if analyzed by other than Department of Water Resources.)

Date Well was Completed 10-17-67 Date of Report 10-18-67

Water Well Driller's License No. 51 Well Driller Lloyd W. Pratt (signature)



06-071-017

State of Vermont
DEPARTMENT OF WATER RESOURCES

Form WR-59

WELL COMPLETION REPORT

WR# 19 USGS RTW-155
Field Loc ☒ Map Des
La. 43° 38' Alt 705 TS
Lo. 72° 57' ☐ HU
Scale: 62500☐, 25000☐, 24000☐

itted to
Office
er than

Do not fill in
State Well No.
Other No. Sec 06-071-006

WELL OWNER Robert Wynne Jr. — Name: Blue Ridge Drive — Mailing Address: Rutland Town

WELL DRILLER Green Mt. Drilling Co., Inc. — Name: Box 26 — Mailing Address: Ctr. Rutland, Vt.

PROPOSED USE OR USES (Check):

☑ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial

☐ Other (Specify use)

CASTING DETAILS (Inside)	YIELD TEST	WATER LEVEL (From land surface) (if possible)	SCREEN DETAILS
Length: 196 Feet	☐ Bailed or ☐ Pumped or ☑ Compressed Air; 1 Hours; 2½ GPM	Static: 40' Feet	Make: None
Diameter: 6 Inches		During Yield Test: Feet	Material:
Kind: Steel		DRILLING EQUIPMENT: ☐ Cable Tool ☑ Rotary ☐ Air Percussion ☐ Other (specify)	Slot Size Length: Ft.
Weight: 16 lbs/p/ft			Diameter: in.
☑ New ☐ Used	Yield: 2½ GPM		

TOTAL DEPTH OF WELL 328' FEET TOWN WELL IS LOCATED IN: Rutland Town
(Make sketch of well location on reverse side of sheet)

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse) color of material, structure (loose, packed, cemented, hard). For example: 0 ft. to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.
0 ft. to 190 ft.	Clay, Hardpan & Boulders
190 ft. to 328 ft.	Dunham Dolomite
ft. to ft.	
ft. to ft.	
ft. to ft.	

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

ft.	G.P.M.
ft.	G.P.M.
ft.	G.P.M.

Has sample of well water been analyzed? No

Where was sample analyzed?
(Include analysis of sample if analyzed by other than Department of Water Resources.)

Date Well was Completed 5-24-67 Date of Report 6-18-67

Water Well Driller's License No. 51 Well Driller Lloyd A. Robert (signature)



State of Vermont
DEPARTMENT OF WATER RESOURCES

Form WR-59

WELL COMPLETION REPORT

WR# 17 USGS RTW-156
Field Loc ☒ Map Des
La. 43°38' Alt 715 TS
Lo. 72°57' ☐ HU
Scale: 62500☐, 25000☐, 24000☐

mitted to
ite Office
ater than

Do not fill in
State Well No.
Other No. See 06-071-006

WELL OWNER Alexander Norden Post Road RD#2 Rutland, VT.
Name Mailing Address

WELL DRILLER Green Mt. Drilling Co. Box 26 Center Rutland, VT.
Name Mailing Address

PROPOSED USE OR USES (Check):

☑ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial

☐ Other (Specify use)

CASTING DETAILS (Inside)	YIELD TEST	WATER LEVEL (From land surface) (if possible)	SCREEN DETAILS
Length: 56 Feet	☐ Bailed or ☐ Pumped or ☑ Compressed Air; 1 Hours; 100 GPM	Static: ? Feet	Make: NONE
Diameter: 6 Inches		During Yield Test: Feet	Material:
Kind: STEEL		DRILLING EQUIPMENT: ☐ Cable Tool ☑ Rotary ☐ Air Percussion ☐ Other (specify)	Slot Size
Weight: 16 lbs/p/ft			Length: Ft.
☑ New ☐ Used	Yield: 100 GPM		Diameter: in.

TOTAL DEPTH OF WELL 172 FEET TOWN WELL IS LOCATED IN: Rutland Town
(Make sketch of well location on reverse side of sheet)

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse) color of material, structure (loose, packed, cemented, hard). For example: 0 ft. to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.
0 ft. to 45 ft.	Clay w/Boulders
45 ft. to 172 ft.	Dunham Dolomite
ft. to ft.	
ft. to ft.	
ft. to ft.	

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

ft.	G.P.M.
ft.	G.P.M.
ft.	G.P.M.

Has sample of well water been analyzed? NO

Where was sample analyzed?
Include analysis of sample if analyzed by other than Department of Water Resources.)

Date Well was Completed 5-16-67 Date of Report 5-21-67

Water Well Driller's License No. 51 Well Driller [signature]
(signature)



06-071-314

Rtw

State of Vermont
DEPARTMENT OF WATER RESOURCES

Form WR-59

WELL COMPLETION REPORT

WR 14 USGS RTW-88
Field Loc ☒ Map Des
La. 43°39'37 Alt 705 TS
Lo. 73°00'03 ☐ HU
Scale: 62500☐, 25000☐, 24000☐

itted to
e Office
ter than

Do not fill in
State Well No.
Other No. See 06-071-002

WELL OWNER Name: HENRY FITZGERALD, JR. Mailing Address: CEDAR AVE. RFD RUTLAND, VT.

WELL DRILLER Name: GREEN MT. DRILLING CO., INC. Mailing Address: BOX 26 CTR. RUTLAND, VT

PROPOSED USE OR USES (Check):

☑ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial

☐ Other (Specify use)

CASING DETAILS (Inside)	YIELD TEST	WATER LEVEL (From land surface) (if possible)	SCREEN DETAILS
Length: 30 Feet	☐ Bailed or ☐ Pumped or ☑ Compressed Air; 1 Hours; 6 GPM	Static: Feet	Make: NONE
Diameter: 6 Inches		During Yield Test: Feet	Material:
Kind: STEEL		DRILLING EQUIPMENT: ☐ Cable Tool ☑ Rotary ☐ Air Percussion ☐ Other (specify)	Slot Size Length: Ft.
Weight: 16 lbs/p/ft			Diameter: in.
☑ New ☐ Used	Yield: 6 GPM		

TOTAL DEPTH OF WELL 127 FEET TOWN WELL IS LOCATED IN: RUTLAND TOWN
(Make sketch of well location on reverse side of sheet)

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse) color of material, structure (loose, packed, cemented, hard). For example: 0 ft. to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.
0 ft. to 24 ft.	FINE SAND W/ BOULDERS
24 ft. to 127 ft.	DURHAM DOLOMITE
ft. to ft.	
ft. to ft.	
ft. to ft.	

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

ft.	G.P.M.
ft.	G.P.M.
ft.	G.P.M.

Has sample of well water been analyzed? NO

(Where was sample analyzed?
Include analysis of sample if analyzed by other than Department of Water Resources.)

Date Well was Completed 7-20-67 Date of Report 7-29-67

Water Well Driller's License No. 51 Well Driller (signature)



06-071-006

State of Vermont
DEPARTMENT OF WATER RESOURCES

Form WR-59

WELL COMPLETION REPORT

WR #6 , USGS RTW-126
Field Loc ☒ Map Des _____ itted to
La. 43°38' Alt 765 TS ___ : Office
Lo. 72°57' ☐ HU _____ er than
Scale: 62500☐, 25000☐, 24000☐

Do not fill in
State Well No. N-43°38'11"
Other No. W-72°57'45"

WELL OWNER MRS McCORMICH (Name) POST ROAD RUTLAND TOWN (Mailing Address)

WELL DRILLER GREEN MOUNTIAN DRILLING CO, INC. (Name) CENTER RUTLAND, VT. (Mailing Address)

PROPOSED USE OR USES (Check):

☒ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial

☐ Other (Specify use)

CASTING DETAILS (Inside)	YIELD TEST	WATER LEVEL (From land surface) (if possible)	SCREEN DETAILS
Length: 158 Feet	☐ Bailed or ☐ Pumped or ☐ Compressed Air; 4 Hours; 5 GPM	Static: 65 Feet	Make: NONE
Diameter: 6 Inches		During Yield Test: Feet	Material:
Kind: STEEL		DRILLING EQUIPMENT: ☐ Cable Tool ☒ Rotary ☐ Air Percussion ☐ Other (specify)	Slot Size Length: Ft.
Weight: 16 lbs/p/ft			Diameter: in.
☒ New ☐ Used	Yield: 5 GPM		

TOTAL DEPTH OF WELL 156 FEET TOWN WELL IS LOCATED IN: RUTLAND TOWN
(Make sketch of well location on reverse side of sheet)

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse) color of material, structure (loose, packed, cemented, hard). For example: 0 ft. to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.
0 ft. to 150 ft.	GLACIAL TILL, BOULDERS, CLAY
150 ft. to 156 ft.	ETC.
ft. to ft.	DURHAM DOLOMITE
ft. to ft.	
ft. to ft.	

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

ft.	G.P.M.
ft.	G.P.M.
ft.	G.P.M.

as sample of well water been analyzed? NO

Where was sample analyzed?
(Include analysis of sample if analyzed by other than Department of Water Resources.)

Date Well was Completed 9-23-66 Date of Report 12-2-66

Water Well Driller's License No. 51 Well Driller Lloyd H. Robert (signature)



State of Vermont
DEPARTMENT OF WATER RESOURCES

Form WR-59

WELL COMPLETION REPORT

WR _____, USGS W237
Field Loc. _____ Map Des _____
La. _____ Alt _____ TS _____
Lo. _____ HU _____
Scale: 62500 ☐, 25000 ☐, 24000 ☐

ted to Office r than

Do not fill in
State Well No. 43° 38' 16"
Other No. W- 72° 57' 45"

WELL OWNER LEE YOUNG (Name) CHASANNA DRIVE RUTLAND TOWN (Mailing Address)

WELL DRILLER GREEN MOUNTIAN DRILLING CO INC, Box 26 CENTER RUTLAND, VT (Name / Mailing Address)

PROPOSED USE OR USES (Check):

☑ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial

☐ Other (Specify use)

CASTING DETAILS (Inside)	YIELD TEST	WATER LEVEL (From land surface) (if possible)	SCREEN DETAILS
Length: 61 Feet	☐ Bailed or ☐ Pumped or ☒ Compressed Air; 3 Hours; 15 GPM	Static: 60 Feet	Make: NONE
Diameter: 6 Inches		During Yield Test: Feet	Material:
Kind: STEEL		DRILLING EQUIPMENT: ☐ Cable Tool ☐ Rotary ☐ Air Percussion ☐ Other (specify)	Slot Size; Length: Ft.
Weight: 16 lbs/p/ft			Diameter: in.
☑ New ☐ Used	Yield: 15 GPM		

TOTAL DEPTH OF WELL 152 FEET TOWN WELL IS LOCATED IN: RUTLAND TOWN
(Make sketch of well location on reverse side of sheet)

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse) color of material, structure (loose, packed, cemented, hard). For example: 0 ft. to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.
0 ft. to 55 ft.	GLACIAL TILL, BOULDERS CLAY
ft. to ft.	
ft. to ft.	
ft. to ft.	
ft. to ft.	

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

ft.	G.P.M.
ft.	G.P.M.
ft.	G.P.M.

Has sample of well water been analyzed? NO

Where was sample analyzed?
(Include analysis of sample if analyzed by other than Department of Water Resources.)

Date Well was Completed 9-30-66 Date of Report 12-2-66

Water Well Driller's License No. 51 Well Driller Floyd H Robert (signature)



06-071-004

State of Vermont
DEPARTMENT OF WATER RESOURCES

Form WR-59

WELL COMPLETION REPORT

WR #4 USGS RTW-80
Field Loc ☒ Map Des
La. 43°36'27 Alt 840 TS
Lo. 72°56 ☐ RU
Scale: 62500☐, 25000☐, 24000☐

Do not fill in
State Well No. N-43°36'26"
Other No. W-72°56'26"

WELL OWNER JOE SELVA — 95 FIRST ST. — RUTLAND CITY
Name — Mailing Address

WELL DRILLER GREEN MOUNTIAN DRILLING CO. INC. — BOX 26 CENTER RUTLAND VT.
Name — Mailing Address

PROPOSED USE OR USES (Check):

☒ Domestic ☐ Agricultural ☐ Business Establishment ☐ Municipal ☐ Industrial

☐ Other (Specify use)

CASTING DETAILS (Inside)	YIELD TEST	WATER LEVEL (From land surface) (if possible)	SCREEN DETAILS
Length: 155 Feet	☐ Bailed or ☐ Pumped or ☒ Compressed Air; 2 Hours; 45 GPM	Static: ? Feet	Make: NONE
Diameter: 6 Inches		During Yield Test: Feet	Material:
Kind: STEEL		DRILLING EQUIPMENT	Slot Size
Weight: 16 lbs/p/ft		☐ Cable Tool ☒ Rotary ☐ Air Percussion	Length: Ft.
☒ New ☐ Used	Yield: 45 GPM	☐ Other (specify)	Diameter: in.

TOTAL DEPTH OF WELL 232 FEET — TOWN WELL IS LOCATED IN: RUTLAND TOWN
(Make sketch of well location on reverse side of sheet)

WELL LOG

Depth From Ground Surface	Give description of formations penetrated, such as: peat, silt, sand, gravel, clay, hardpan, shale, limestone, granite, etc. Include size of gravel (diameter) and sand (fine, medium, coarse) color of material, structure (loose, packed, cemented, hard). For example: 0 ft. to 27 ft. fine, packed, yellow sand; 27 ft. to 134 ft. gray granite.
0 ft. to 150 ft.	GLACIAL TILL, BOULDERS & CLAY ETC
150 ft. to 232 ft.	DURHAM DOLOMITE
ft. to ft.	
ft. to ft.	
ft. to ft.	

YIELD TEST DATA IN G.P.M.
If yield was tested at different depth during drilling, List Below

ft.	G.P.M.
ft.	G.P.M.
ft.	G.P.M.

Has sample of well water been analyzed? NO

Where was sample analyzed?
(Include analysis of sample if analyzed by other than Department of Water Resources.)

Date Well was Completed 10-10-66 — Date of Report 12-2-66

Water Well Driller's License No. 51 — Well Driller Floyd E Rhuet (signature)